

# INSTALLATION RESTORATION PROGRAM

## CLOSURE ASSESSMENT REPORT FOR UST REMOVALS AT SITES 4 AND 5 - PETROLEUM, OILS, AND LUBRICANTS FACILITY

VIRGINIA AIR NATIONAL GUARD  
192nd FIGHTER GROUP  
RICHMOND INTERNATIONAL AIRPORT  
SANDSTON, VIRGINIA

FINAL  
NOVEMBER 1996



DISSEMINATION STATEMENT H  
Approved for public release  
Distribution Unlimited

DTIC QUALITY INSPECTED 3

Hazardous Waste Remedial Actions Program  
Oak Ridge, Tennessee 37831-7606  
Managed by LOCKHEED MARTIN ENERGY SYSTEMS, INC.  
For the U.S. Department of Energy under contract DE-AC05-84OR21400


19970825 029

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)	2. REPORT DATE NOVEMBER 1996	3. REPORT TYPE AND DATES COVERED CLOSURE ASSESSMENT REPORT		
4. TITLE AND SUBTITLE CLOSURE ASSESSMENT REPORT, VIRGINIA AIR NATIONAL GUARD, 192 ND FIGHTER GROUP, RICHMOND INTERNATIONAL AIRPORT, SANDSTON, VIRGINIA. VOL I / OF ONE VOL			5. FUNDING NUMBERS	
6. AUTHOR(S)				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) HAZWAP OAK RIDGE, TN 37831-7606			8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) ANG/CEVR 3500 FETCHET AVE ANDREWS AFB MD 20762-5157			10. SPONSORING/MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES				
12a. DISTRIBUTION AVAILABILITY STATEMENT APPROVED FOR PUBLIC RELEASE; DISTRIBUTION IS UNLIMITED			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words)  CLOSURE ASSESSMENT REPORT, VIRGINIA AIR NATIONAL GUARD, 192 ND FIGHTER GROUP, RICHMOND INTERNATIONAL AIRPORT, SANDSTON, VIRGINIA  THE FOLLOWING SITES WERE INVESTIGATED UNDER THE INSTALLATION RESTORATION PROGRAM: SITE 4 - UST NOS. 1, 2 & 2, AND 600 GAL UST & RELATED FACILITIES, AND UST NO. 4 & RELATED FACILITIES, SITE 5 - USTs & REPLACED FACILITIES. SOIL SAMPLES WERE COLLECTED & ANALYZED UNDER THE RAPID RESPONSE INITIATIVE (RRI). NO FURTHER ACTION IS RECOMMENDED FOR ANY OF THESE TWO SITES UNDER CURRENT LAND USE.  VOL I - REPORT & APPENDICES / OF ONE VOL.				
14. SUBJECT TERMS INSTALLATION RESTORATION PROGRAM, COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATION AND LIABILITY ACT (CERCLA); AIR NATIONAL GUARD, CLOSURE ASSESSMENT REPORT, VIRGINIA AIR NATIONAL GUARD, SANDSTON, VIRGINIA			15. NUMBER OF PAGES 250	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED	18. SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED	19. SECURITY CLASSIFICATION OF ABSTRACT UNCLASSIFIED	20. LIMITATION OF ABSTRACT NONE	

## CERTIFICATION OF CLOSURE

Sites 4 and 5 at the Virginia Air National Guard Base, Richmond International Airport, Sandston, Virginia have been closed in accordance with the requirements of the Commonwealth of Virginia's Department of Environmental Quality and the specifications and procedures described in the approved closure plan for Tank #4 at Site 4.

COL Robert O. Seifert  
Base Commander



Joseph H. Hawk  
Professional Engineer  
Commonwealth of Virginia  
License Number 0402 025417



NOTE: Professional engineering seal with original signature and date is on file with the Commonwealth of Virginia's Department of Environmental Quality.



COMMONWEALTH of VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL QUALITY

Peter W. Schmidt  
Director

Water Regional Office  
Post Office Box 6030  
Glen Allen, Virginia 23058  
(804) 527-5020

Gerard Seeley, Jr.  
Regional Director

October 27, 1994

Laura J. Boyer  
Virginia Air National Guard  
5680 Beulah Road  
Sandston, Virginia 23150

Re: PC# 95-4095, Site 4, POL Facility, Inactive USTs  
PC# 94-4096, Site 5, POL Facility, Abandoned USTs

Dear Ms. Boyer:

This correspondence is in regard to the above mentioned facility and the Closure Assessment Report for UST removals. The report details the closure assessment activities for five of the USTs at Site 4 and all twelve USTs at Site 5. Based upon the data in this report and other assessment information, the Department has concluded that the remaining petroleum contamination at these sites does not appear to pose a significant environmental hazard. These investigations are considered to be closed and further corrective action is not required at this time.

Be advised that should environmental problems develop in these areas, then additional information and/or corrective action may be required in accordance with applicable State and Federal regulations.

If you require additional information, please Meade Anderson at (804) 527-5022.

Sincerely,

A handwritten signature in cursive script, appearing to read "A. L. Willett".

A. L. Willett  
Regional Ground Water Manager

94-4095a/ma



**INSTALLATION RESTORATION PROGRAM**

**VIRGINIA AIR NATIONAL GUARD  
192nd FIGHTER GROUP  
RICHMOND INTERNATIONAL AIRPORT  
SANDSTON, VIRGINIA**

**CLOSURE ASSESSMENT REPORT FOR UST REMOVALS AT  
SITES 4 AND 5 - PETROLEUM, OILS, AND LUBRICANTS FACILITIES**

*Prepared For:*

**National Guard Bureau ANGRC/CEVR  
Andrews AFB, Maryland 20331-6008**

*Prepared By:*

**Advanced Sciences, Inc.  
800 Oak Ridge Turnpike, Suite C-102  
Oak Ridge, Tennessee 37830-6927**

*Submitted To:*

**Hazardous Waste Remedial Action Program  
Oak Ridge, Tennessee 37831-7606  
Managed by Lockheed Martin Energy Systems, Inc.  
for the U.S. Department of Energy under contract DE-AC05-84OR21400**

**November 1996**

## TABLE OF CONTENTS

	<u>Page</u>
LIST OF FIGURES .....	iv
LIST OF TABLES .....	v
LIST OF ACRONYMS/ABBREVIATIONS .....	vi
1.0 INTRODUCTION .....	1
1.1 BACKGROUND .....	1
1.2 SITE DESCRIPTION .....	1
1.2.1 Site 4 .....	1
1.2.2 Site 5 .....	6
1.3 ENVIRONMENTAL SETTING .....	6
1.3.1 Meteorology .....	6
1.3.2 Geology And Hydrogeology .....	6
1.3.3 Current And Projected Groundwater Uses .....	13
1.3.4 Physiography And Surface Drainage .....	14
2.0 SITE HISTORY .....	15
2.1 PREVIOUS INVESTIGATIONS — SITE 4 .....	15
2.1.1 August 1990 Tank Sampling .....	15
2.1.2 December 1990 Site Characterization .....	15
2.1.3 Supplemental Site Characterization Activities, February 1991 .....	17
2.1.4 Site Assessment Activities, May 1991 .....	17
2.1.5 Site Assessment Activities, April 1992 .....	19
2.2 PREVIOUS INVESTIGATIONS - SITE 5 .....	19
2.2.1 Tank Measurement/Sampling, December 1991 .....	19
2.2.2 Site Assessment Activities, April 1992 .....	19
3.0 CLOSURE ASSESSMENT ACTIVITIES .....	25
3.1 OBJECTIVES .....	25
3.2 REGULATORY GUIDANCE .....	25
3.3 SITE 4 CLOSURE ACTIVITIES .....	25
3.3.1 Closure Activities Associated with Petroleum USTs .....	27
3.3.1.1 Contractor Closure Activities .....	27
3.3.1.2 ASI Closure Assessment Sampling Activities .....	29
3.3.2 Closure Activities Associated with Tank No. 4 .....	31
3.3.2.1 Contractor Closure Activities .....	31
3.3.2.2 ASI Closure Assessment Sampling Activities .....	32

## TABLE OF CONTENTS (Continued)

	<u>Page</u>
3.4 SITE 5 .....	32
3.4.1 Contractor Closure Activities .....	32
3.4.2 ASI Closure Assessment Sampling Activities .....	36
4.0 CLOSURE ASSESSMENT FINDINGS .....	39
4.1 SITE 4 - CLOSURE SAMPLING RESULTS .....	39
4.2 SITE 5 - CLOSURE SAMPLING RESULTS .....	39
5.0 QUALITATIVE RISK EVALUATION SITES 4 AND 5 .....	52
6.0 CONCLUSIONS .....	53
6.1 SITE 4 - UST NOS. 1, 2, 3, AND 600GAL UST AND RELATED FACILITIES	53
6.2 SITE 4 - UST NO. 4 AND RELATED FACILITIES .....	53
6.3 SITE 5 - USTS AND REPLACED FACILITIES .....	53
6.4 RECOMMENDATIONS - SITES 4 AND 5 .....	53
7.0 REFERENCES .....	54
APPENDICES	
APPENDIX A	SELECTED PHOTOGRAPHS OF SITE 4 CLOSURE ACTIVITIES
APPENDIX B	MSDS FOR TANK CLEANING FLUID
APPENDIX C	ANALYTICAL RESULTS OF TANK NO. 4 CONTENTS
APPENDIX D	SELECTED PHOTOGRAPHS OF SITE 5 CLOSURE ACTIVITIES
APPENDIX E	ANALYTICAL RESULTS FOR CLOSURE SAMPLES COLLECTED AT SITE 4
APPENDIX F	ANALYTICAL RESULTS FOR CLOSURE SAMPLES COLLECTED AT SITE 5
APPENDIX G	LABORATORY QUALITY CONTROL DATA

## LIST OF FIGURES

<u>Figure</u>	<u>Title</u>	<u>Page</u>
1.1	VANG Location Map . . . . .	2
1.2	Topographic/Location Map . . . . .	3
1.3	Composite Activity Map - Site 4 and 5 . . . . .	4
1.4	Site 4 - POL Facility . . . . .	5
1.5	Site 5 - POL Facilities . . . . .	7
1.6	Generalized Hydrogeologic Stratigraphic Column of the Study Area . . . . .	8
1.7	Site 4 - Location Map, Geologic Cross Section A-A' . . . . .	9
1.8	Site 4 - Generalized Geologic Cross Section A-A' . . . . .	10
1.9	Site 4/5 - Location Map, Cross Section A-D . . . . .	11
1.10	Site 4/5 - Generalized Geologic Cross Section A-D . . . . .	12
3.1	Site 4 - POL Facilities . . . . .	26
3.2	Site 4 - Sample Locations, UST Pit Nos. 1,2,3, and Aquatrap Pits . . . . .	30
3.3	Site 4 - Sample Location, UST Pit No. 4 . . . . .	33
3.4	Site 5 - POL Facilities . . . . .	34
3.5	Site 5 - Sample Locations, UST Pit Nos. 1-12 . . . . .	37
3.6	Site 5 - Sample Locations, Piperuns, Pressure Control Pits, Valve Pits, Fill Pits, and Air Separator . . . . .	38
4.1	Site 4 - GRO/DRO Analytical Results from UST Pits 1,2,3 and Aquatrap Pits . . . . .	41
4.2	Site 4 - Total Metals, Arsenic Analytical Results, UST Pit No. 4 . . . . .	44
4.3	Site 4 - Total Metals, Barium Analytical Results, UST Pit No. 4 . . . . .	45
4.4	Site 4 - Total Metals, Chromium Analytical Results, UST Pit No. 4 . . . . .	46
4.5	Site 4 - Total Metals, Lead Analytical Results, UST Pit No. 4 . . . . .	47
4.6	Site 4 - Methylene Chloride Results, UST Pit No. 4 . . . . .	48
4.7	Site 5 - GRO/DRO Analytical Results, UST Pit Nos. 1-12 . . . . .	50

## LIST OF TABLES

<u>Table</u>	<u>Title</u>	<u>Page</u>
2.1	Summary of Analytical Results for UST Tank No. 4 Contents . . . . .	16
2.2	Site 4 - Summary of Analytical Results for Tanks 1, 2, and 3 . . . . .	18
2.3	Site 4 - Summary of Analytical Results of the Abandoned USTs (UST No. 3; 600gal) . . . . .	20
2.4	Site 5 - Depth to Top of Product and Water in 12 USTs . . . . .	21
2.5	Site 5 - Summary of Laboratory Analytical Data for Contents of 12-25,000gal USTs . . . . .	22
2.6	Site 5 - Summary of Laboratory Analytical Data, UST No. 4 . . . . .	24
3.1	Site 4 - Uniform Hazardous Waste Manifest List for Petroleum- Contaminated Wastewater Removed from UST Nos. 1, 2, 3 and 600gal Tank . . . . .	28
3.2	Site 5 - Uniform Hazardous Waste Manifest List for Petroleum- Contaminated Wastewater and Product Removed from Tanks and Associated Piping . . . . .	35
4.1	Site 4 - GRO/DRO Laboratory Analytical Results For Soil Samples From Pits for UST Nos. 1, 2, 3, and Aquatrap . . . . .	40
4.2	Site 4 - Total Metals Laboratory Analytical Results For Soil UST No. 4 Pit . . . . .	42
4.3	Site 4 - Volatile Organic Laboratory Analytical Results For Soil UST No. 4 Pit . . . . .	43
4.4	Site 5 - GRO/DRO Laboratory Analytical Results For Soil From UST Nos. 1 Through 12 Pits . . . . .	49
4.5	Site 5 - GRO/DRO Laboratory Analytical Results For Soils From Piperuns, Pressure Control Pits, Valve Pit, Fill Pit, and Air Separator Pit . . . . .	51

## LIST OF ACRONYMS/ABBREVIATIONS

ASI	Advanced Sciences, Inc.
AVGAS	aviation gasoline
BTEX	benzene, toluene, ethylbenzene, and xylenes
BTUs	British Thermal Units
CLP	Contract Laboratory Program
DOE	Department of Energy
DRO	diesel range organics
GC	gas chromatograph
GRO	gasoline range organics
HAZWRAP	Hazardous Waste Remedial Actions Program
JP-4	Jet Propulsion - 4
LMES, Inc.	Lockheed Martin Energy Systems, Inc.
MeCl	methylene chloride
MSL	mean sea level
NGB	National Guard Bureau
NOAA	National Oceanic and Atmospheric Administration
PCBs	polychlorinated biphenyls
POL	petroleum, oil, and lubricants
RRI	Rapid Response Initiative
SVOCs	semivolatile organic compounds
TCLP	Toxicity Characteristic Leaching Procedure
TOX	total organic halides
TPH	total petroleum hydrocarbons
UST	underground storage tank
VADEQ	Virginia Department of Environmental Quality
VANG	Virginia Air National Guard
VOCs	volatile organic compounds

## **1.0 INTRODUCTION**

### **1.1 BACKGROUND**

The National Guard Bureau (NGB) developed the Rapid Response Initiative (RRI) to conduct site assessments, evaluate potential corrective actions, and design the selected remedies at leaking underground storage tank (UST) and spill sites at Air National Guard facilities. The U.S. Department of Energy (DOE) provides technical assistance in implementing the RRI for the NGB through an existing Interagency Agreement with the Air Force and through the Hazardous Waste Remedial Actions Program (HAZWRAP). Lockheed Martin Energy Systems, Inc. (LMES, Inc.) is assigned the responsibility of operating HAZWRAP for DOE.


HAZWRAP selected Advanced Sciences, Inc. (ASI) to conduct closure assessment activities associated with UST removals at the Sites 4 and 5 Petroleum, Oils, and Lubricants (POL) facilities, located at the 192nd Fighter Group, Virginia Air National Guard (VANG), Richmond International Airport, Sandston, VA (hereinafter referred to as the Base) (Figure 1.1). Closure sampling activities and analytical results for soil samples within the excavations will be discussed in detail as well as the technical support role that ASI assumed during closure activities. All closure assessment activities were conducted in accordance with applicable requirements of the Virginia Department of Environmental Quality (VADEQ) Water Division and Waste Division.

The Sites 4 and 5 POL facilities are located in the northeastern portion of the Richmond International Airport complex (Figure 1.2). A portion of Site 4 is currently used as the principal storage and transfer facility for aviation fuels and related petroleum products while the remaining portion of Site 4 is inactive. Site 5 was used for aviation gasoline (AVGAS) storage and distribution from approximately 1942 to 1954 and is currently inactive. Figure 1.3 displays the relationship between these two sites as well as borings and monitoring wells completed during previous site characterization activities. Closure activities were only conducted at Site 5 and the inactive portion of Site 4.

### **1.2 SITE DESCRIPTION**

#### **1.2.1 Site 4**

The northern one-half of Site 4 is actively used for storage and dispensing of jet propulsion-4 (JP-4) fuel. As shown in Figure 1.4, the southern one-half of the Site 4 POL facility, inactive since 1955, consists of four 25,000gal USTs, one 600gal UST, four reinforced concrete tank manhead pits, two reinforced concrete aquatrap pits, and associated piping and equipment.



SOURCE: RICHMOND, VA. TELEPHONE DIRECTORY

ADVANCED SCIENCES, INC.


FILE: C&P

DATE: 1996

FIGURE 1.1  
VANG Location Map

VANG BASE  
192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia





SOURCE: U.S.G.S. 7.5 MINUTE SERIES  
DUTCH GAP AND SEVEN PINES, VA.


ADVANCED SCIENCES, INC.


FILE: C&P

DATE: 1996

FIGURE 1.2  
Topographic/Location  
Map

VANG BASE  
192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia





ADVANCED SCIENCES, INC.


RANG26

DATE: 1996

FIGURE 1.3  
Composite Activity Map - Site 4 and 5

VANG BA  
192nd Tactical F  
Richmond Internat  
Sandston, V

2



### LEGEND:







-  UST NO. 1
-  SOIL BORING
-  MONITORING WELL
-  PIEZOMETERS
-  TREE LINE

FIGURE 1.3  
Activity Map - Site 4 and 5

VANG BASE  
192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia



### **1.2.2 Site 5**

As shown in Figure 1.5, the Site 5 POL facility, inactive since 1954, consists of eight 25,000gal USTs, four 600gal USTs, reinforced concrete structures consisting of eight tank manhead pits, four aquatrap pits, two pressure control pits, three valve pits, two fill pits, one air separator pit, and associated fuel distribution piping and equipment.

## **1.3 ENVIRONMENTAL SETTING**


### **1.3.1 Meteorology**

Based on information from the Soil Survey of Henrico County, Virginia (Clay 1975) and the National Oceanic and Atmospheric Administration (NOAA), the climate at the Base consists of humid summers and mild winters. Average mean annual temperatures range from 55° to 60°F. Mean annual precipitation is 43in/yr, and the annual evaporation rate is 40in/yr.

### **1.3.2 Geology And Hydrogeology**









The Base is located in the Coastal Plain Province. The Coastal Plain Province consists of a layered sequence of sand and gravel aquifers separated by silt and clay confining beds. These sediments, which overlie metamorphic and igneous bedrock, thicken and dip eastward from their western limit (the Fall Line). Sediment thicknesses range from zero at the Fall Line to an estimated 350 to 400ft in the vicinity of the POL facility. This aquifer system is divided into an unconfined aquifer—the Yorktown Aquifer—and underlying confined aquifers called (in descending order) the Chickahominy, Aquia, and Potomac aquifers. Figure 1.6 shows the generalized sequence of unconsolidated sediments in the vicinity of the POL facility. Figures 1.7 through 1.10, represent the plan view and cross sectional views of the shallow subsurface soil/rock conditions in the vicinity of Sites 4 and 5. Specific shallow subsurface soil/rock descriptions are discussed in the following paragraphs.

The Yorktown Aquifer consists of sand and gravel, commonly clayey, interbedded with silt and clay. Although generally unconfined, it may be semiconfined locally. In the vicinity of the POL facility, it is 40–50ft thick. Recharge to the Yorktown Aquifer is a result of direct infiltration of precipitation. Recharge to the underlying confined aquifers originates chiefly at their outcrop areas near the Fall Line. The Calvert Formation, a plastic clay 25–30ft thick, separates the Yorktown Aquifer from the underlying Chickahominy Aquifer. It occurs at a depth of approximately 45ft below grade and acts as an aquitard, or semiconfining unit, retarding the vertical movement of groundwater. The stratigraphy of the Yorktown Aquifer encountered at Site 4 was generally consistent throughout the area. Except in areas where backfilling with sand has occurred, a uniform, gray-brown to reddish-yellow plastic, silty clay overlies the site from the ground surface to an approximate depth of 5ft. From 5 to 14ft below grade, a yellowish-red to brownish-yellow plastic, silty clay with higher sand content and iron staining is present. At depths of 14 to 21ft below grade, the soil consists of a yellowish-brown to light gray, fine- to medium-grained wet sand (M&E 1991a). The lower portion of the Yorktown Aquifer consists









GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.		<b>FIGURE 1.5</b> Site 5 - POL Facilities	<b>VANG BASE</b> 192nd Tactical Fighter Group Richmond International Airport Sandston, Virginia
FILE: TPSPCS6	DATE: 1996		

Age	Formation	Thickness	Lithology	Depth from Surface	Comments
Quaternary	Yorktown-Eastover	40-45'		10'	Underlies 8-10' of soil overburden Uppermost unconfined aquifer includes soil-water table
				50'	
Tertiary	Calvert	25-30'		80'	Confining aquiclude separating confined aquifers from soil-water table aquifer
	Chickahominy	10'		90'	Chickahominy aquifer
	Nanjemoy	35-40'			
	Marlboro	10'		130'	Confining Aquiclude
				140'	
	Aquia	50'			Aquia aquifer
Cretaceous				190'	
	Potomac	190-200'			Principal aquifer for groundwater supply; Potomac aquifer encompasses entire Potomac formation
Triassic				390'	
	Basement				"Basement Complex" Consolidated hard rock formations

LEGEND:


	SAND
	CLAY
	FOSSILIFEROUS SAND
	BEDDED SANDSTONE
	LITHIFIED SHALE
	SILTY CLAY

VERTICAL SCALE: 1:600

SOURCE: METCALF AND EDDY  
SITE 4 SITE CHARACTERIZATION, FEB. 1991

ADVANCED SCIENCES, INC.		FIGURE 1.6 Generalized Hydrogeologic Stratigraphic Column of the Study Area	VANG BASE 192nd Tactical Fighter Group Richmond International Airport Sandston, Virginia
FILE: RANG27	DATE: 1996		






ADVANCED SCIENCES, INC.

FILE: TPSPCS1

DATE: 1996

FIGURE 1.7  
Site 4, Location Map,  
Geologic Cross Section A-A'

VANG BASE  
192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia



VANG BASE

192nd Tactical Fighter Group

Richmond International Airport

Sandston, Virginia


FIGURE 1.8

Site 4 - Generalized Geologic Cross

Section A-A'


ADVANCED SCIENCES, INC.

FILE: TPSPECS2    DATE: 1996



ADVANCED SCIENCES, INC.		<b>FIGURE 1.9</b> Site 4 & 5 Location Map, Cross Section A-D	<b>VANG BASE</b> 192nd Tactical Fighter Group Richmond International Airport Sandston, Virginia
FILE: TPSPECS3	DATE: 1996		

HORIZONTAL SCALE IN FEET



**LEGEND:**

- WATER LEVEL
- MW — DENOTES MONITORING WELL
- TD — TOTAL DEPTH



SILTY CLAY  
YELLOW-BROWN (10 YR 8/6)  
MOTTLED WITH GRAY (10 YR 8/6)  
AND RED (5 YR 5/4) STREAKS.  
VERY FINE PARTICLES.  
SUBANGULAR TO SUBROUND  
FRAGMENTS. SEMICONSOLIDATED  
TO CONSOLIDATED WITH HIGH  
PLASTICITY. DRY TO SLIGHTLY  
MOIST.



SANDY CLAY  
GRAY (10 YR 8/2) MOTTLED WITH  
YELLOW-BROWN (10 YR 8/6) AND  
RED (5 YR 5/4) FINE GRAIN  
PARTICLES. SUBANGULAR TO SUB-  
ROUND FRAGMENTS. SEMICONSOLIDATED  
TO CONSOLIDATED. POOR SORTING  
AND MEDIUM PLASTICITY. MOIST TO  
WET.



SILTY SAND  
YELLOW-BROWN (10 YR 8/6)  
FINE TO MEDIUM GRAIN SAND WITH  
SOME SILT. POOR SORTING WITH  
SUBANGULAR TO SUBROUND FRAGMENTS.  
UNCONSOLIDATED AND WET AT  
APPROXIMATELY 14 FT. BGL.  
SATURATED AT 15 FT. BGL.

ADVANCED SCIENCES, INC.

FILE: TPSPECS4

DATE: 1996

**FIGURE 1.10**  
**Site 4 & 5 — Generalized Geologic**  
**Cross Section A-D**

**VANG BASE**  
**192nd Tactical Fighter Group**  
**Richmond International Airport**  
**Sandston, Virginia**

of unconsolidated sands. To a depth of 29ft below grade, light gray to gray-brown, fine- to medium-grained wet sands are present, with the sand content increasing markedly at 21ft below grade. From 29 to 41ft below grade, strong brown wet sands with large quartz pebbles and rock fragments up to 0.75in in diameter were encountered. A plastic clay, which acts as the confining or semi-confining layer (Calvert Formation), is expected to be present at a depth of approximately 45ft below grade (M&E 1991a).

Groundwater data collected during previous investigations indicate the direction of groundwater flow is to the south-southeast. Falling head slug tests performed at Site 4 indicate hydraulic conductivity values for the Yorktown Aquifer ranging from  $3.21\text{E-}4\text{cm/s}$  to  $4.62\text{E-}5\text{cm/s}$ . Using an average hydraulic conductivity value of  $3.67\text{E-}4\text{cm/s}$  and an approximate hydraulic gradient of 0.8 percent, the average groundwater velocity beneath Site 4 in the Yorktown Aquifer was calculated at 0.0453ft/day (16.5ft/yr).

The Chickahominy Aquifer consists of about 10ft of shelly sand, interbedded with thin indurated shell beds. This aquifer is essentially confined in the area of the facility. Beneath the Chickahominy Aquifer is 35–40ft of sandy clay (Nanjemoy Formation) and 10ft of plastic clay (Marlboro Formation), which in turn overlies the Aquia Aquifer (M&E 1991a).

The Aquia Aquifer is about 50ft thick in the area of the POL facility. It consists of a shelly, glauconitic sand interbedded with thin, indurated shell beds and silty clay intervals. This aquifer overlies the Potomac Aquifer, which is the principal source of groundwater in the vicinity of Site 4. The Potomac Aquifer is generally about 200ft thick and consists of sand and gravel with lenses of silt and clay (M&E 1991a).

### **1.3.3 Current And Projected Groundwater Uses**

Groundwater in Henrico County is used extensively for domestic, industrial, commercial, agricultural, and public supply purposes. The majority of the wells recorded for Henrico County are wells drilled to supply housing subdivisions. Groundwater in Henrico County is mainly derived from the unconsolidated Coastal Plain aquifers and is generally of good quality. Portions of Henrico County are supplied from wells drilled into the crystalline bedrock, most of which are located in the far western portion of the county.

Water supplied to the Base is purchased from the Henrico Department of Public Utilities. This water is derived from commercial water wells and an intake located on the James River approximately 8 miles south of the Base. The wells are screened in the Potomac Aquifer. Of 36 supply wells inventoried in the vicinity of the Base, 19 are screened in the Potomac Aquifer at depths of 225–275ft. Eleven wells are screened in the Aquia and Chickahominy Aquifers, at depths of 120–130ft and approximately 75ft, respectively. Six of the inventoried wells are screened in the uppermost Columbia Aquifer at depths of 35–40ft. None of these six wells, however, is closer than 3000ft to the Base. Of the six wells identified to be completed in the uppermost aquifer, only two domestic wells are located downgradient of the site. These two wells are located at least 3150ft away from the southern boundary of the Base.

#### **1.3.4 Physiography And Surface Drainage**

Henrico County, Virginia, which includes the Richmond International Airport, straddles the boundary between the Piedmont Province to the west and the Coastal Plain Province to the east. This boundary, which is referred to as the Fall Zone/Line, lies approximately seven miles west of the Base. The Piedmont area is characterized by gently rolling hills, while the Coastal Plain area is generally flat, with gently sloping topography. In the vicinity of the Base, the topography is nearly level, approximately 150–160ft above mean sea level (MSL).

The Base is located in the James River drainage basin. As shown on Fig. 1.2, surface drainage flow across the Base is to the east into White Oak Swamp Creek, which flows east-southeast into the Chickahominy River and ultimately into the James River, approximately 12 miles east of the Base.

## **2.0 SITE HISTORY**

### **2.1 PREVIOUS INVESTIGATIONS — SITE 4**

#### **2.1.1 August 1990 Tank Sampling**

On August 22, 1990, Tank No. 4 was determined to be full (25,021gal). Its contents were sampled and analyzed by Goode Environmental Services of Richmond, Virginia. Chemical analyses were performed on samples for flash point, corrosivity, reactive cyanide, reactive sulfide, EP toxicity, and volatile organic compounds (VOCs). The results are tabulated in Table 2.1. The fluids analyzed were indicative of fuel related compounds.

The Base contracted for the contents of Tank No.4 (approximately 25,000gal) to be removed and transported to GSX Services in Reidsville, North Carolina for incineration. The manifest used for transportation classified the wastes as D001, D006, D008, F002, F003, and F005 hazardous wastes (as designated in VR 672-10-1 Part III). After initial removal of Tank No. 4 contents, only small amounts of liquid and sludge remained at the bottom of the tank.

#### **2.1.2 December 1990 Site Characterization**

A site characterization was conducted by Metcalf & Eddy, Inc. in December 1990, in response to a fuel line leak on the active side of the POL facility. The fuel line leak was detected during a routine volumetric tightness test being conducted by the Base. The field investigation consisted of a soil gas survey, installation of soil borings, installation of piezometers and monitoring wells, and sampling and laboratory analysis of soil and groundwater. The purpose of the site characterization was to assess the nature and extent of the leak as well as to provide data to support future assessment activities at the POL facility.

In summary, the site characterization of the active northeastern side of the POL indicated that elevated levels of total petroleum hydrocarbons [(TPH) (54ppm to 1500ppm)] and benzene (0.98ppm) were primarily limited to the soils beneath the leak site. In the groundwater, which has a gradient that dips to the south/southeast, TPH (69ppm) and benzene (1.8ppm) were detected in a sample taken from MW6. MW6 is located immediately adjacent to the leak site. Characterization of the inactive southwestern one-half of the POL, which is cross-gradient from the leak site, indicated no elevated levels of contaminants were detected (by laboratory analysis) in the soil and/or groundwater.

In addition to the site characterization conducted in December 1990, contents of three 25,000gal USTs (Tank Nos. 1, 2, and 3) were sampled. The contents of these tanks were analyzed for: total metals, pH, Contract Laboratory Program (CLP) VOCs, CLP semivolatile organic compounds (SVOCs), polychlorinated biphenyls (PCBs), CLP pesticides, flashpoint, corrosivity,

**TABLE 2.1**  
**SITE 4**  
**SUMMARY OF ANALYTICAL RESULTS FOR UST TANK NO. 4 CONTENTS**  
**GOODE ENVIRONMENTAL SERVICES, AUGUST 1990.**

Virginia Air National Guard  
Richmond International Airport  
Sandston, Virginia

	UNITS	RESULTS
Cadmium	mg/L	7.5
Lead	mg/L	56.0
Benzene	µg/L	960,000.00
Toluene	µg/L	2,200,000.00
Ethylbenzene	µg/L	370,000.00
1,1,1-Trichloroethane	µg/L	43,000.00
Flash Point	°F	84

Note: Tank Contents were found not to be Corrosive and Reactive.



reactivity (cyanide and sulfide), British Thermal Units (BTUs), and total organic halides (TOX). The results of these analyses are shown in Table 2.2. All constituents detected in the three tanks were typical of compounds found in AVGAS, except for methylene chloride (MeCl).

### **2.1.3 Supplemental Site Characterization Activities, February 1991**

A supplemental site characterization was conducted by ASI at the Site 4 POL facility in February 1991 (ASI 1991a) to supplement information obtained during the site characterization conducted in December 1990 (M&E 1991a). The primary purpose of the supplemental site characterization was to verify the extent of soil and groundwater contamination from the line leak on the active side of the POL facility. A grab sample was also collected from the inactive 600-gal UST located adjacent to Tank Nos. 1 and 2. This sample was collected from the top of the tank fluids and was analyzed for TPH, benzene, toluene, ethylbenzene, and xylenes (BTEX), VOCs, SVOCs, Organochlorine Pesticides/PCBs, BTUs, TOX, flash point, reactivity, corrosivity, EP toxicity metals, and pH. In summary, the analyses of the 600gal UST fluids indicated that the detected concentrations of organics and petroleum hydrocarbons were typical of concentrations found in motor fuels, with the exception of the detection of MeCl (2700ppb). Because a field blank was not collected as part of this grab sample effort, the MeCl analyte could not be confirmed.

### **2.1.4 Site Assessment Activities, May 1991**

In May 1991, ASI conducted additional site assessment activities at Site 4 to further define soil and groundwater contamination detected during previous investigations. Additional field activities in May 1991 included completion of eight soil borings, installation of five monitoring wells, resampling of previously installed monitoring wells and piezometers, and analyses of soil and groundwater samples. Falling-head slug tests were conducted at various monitoring wells to determine typical hydraulic conductivity values associated with the Yorktown Aquifer. The 600gal UST, adjoining UST Tank Nos 1 and 2, was resampled and in addition, Tank No.4 was inspected to determine the volume of fluid, if any, remaining in the tank.

Samples from the 600gal tank were analyzed using a field gas chromatograph (GC). Field GC results indicated the presence of MeCl, which was also detected in laboratory samples analyzed in February 1991. In addition the field GC detected the presence of 1,1,1-Trichloroethane. The field GC was a Photovac 10S55. The Photovac 10S55 operates with a single column and the results are based entirely on the column's retention time, as compared to a standard run two to three times a day. Once a standard value is selected following analysis of a standard, the machine will then identify any peak within 10 percent of the standard value as that compound. In some instances, many compounds may have nearly the same retention times and may be identified as target compounds solely because their retention time fell within the 10 percent window of identification. Making a positive identification is difficult with this portable instrument in cases where a great many compounds are present, such as fuel spills. Therefore,

TABLE 2.2  
SITE 4 - SUMMARY OF ANALYTICAL RESULTS FOR TANKS 1, 2, AND 3.  
(Metcalf & Eddy, Dec. 1990)  
Virginia Air National Guard  
Richmond International Airport  
Sandston, Virginia

Chemical	Units	TANK 1		TANK 2		TANK 3			
		Sample Concentration	Method Reporting Limit	Sample Concentration	Method Reporting Limit	Top Layer		Bottom Layer	
						Sample Concentration	Method Reporting Limit	Sample Concentration	Method Reporting Limit
ARSENIC	mg/l	ND	0.2	ND	0.2	ND	2	ND	0.2
BARIUM	mg/l	ND	0.01	ND	0.01	ND	0.1	ND	0.01
BENZENE	mg/l	9.2	2.5	5.6	2.5			11	2.5
BENZYL ALCOHOL	mg/l	0.06	0.04	0.045	0.04			0.065	0.05
CADMIUM	mg/l	ND	0.01	ND	0.01	ND	0.1	ND	0.01
CHLORINE	mg/l					<0.1			
CHROMIUM	mg/l	ND	0.02	ND	0.02	ND	0.2	ND	0.02
CYANIDE	mg/l	ND	10	ND	10	ND	10	ND	10
LEAD	mg/l	0.2	0.1	0.2	0.1	143	1	0.1	0.1
MERCURY	mg/l	ND	0.0008	ND	0.0008	ND	0.02	ND	0.004
METHYLENE CHLORIDE	mg/l	ND	2.5	ND	2.5			5.1	2.5
2-METHYLNAPHTHALENE	mg/l	ND	0.04	ND	0.04			0.078	0.05
2-METHYLPHENOL	mg/l	.032	0.04	0.54	0.04			0.46	0.05
4-METHYLPHENOL	mg/l	0.09	0.04	0.064	0.04			0.12	0.05
NAPHTHALENE	mg/l	0.05	0.04	0.045	0.04			0.063	0.05
SELENIUM	mg/l	ND	0.3	ND	0.3	ND	1	ND	0.3
SILVER	mg/l	ND	0.02	ND	0.02	ND	0.2	ND	0.02
SULFIDE	mg/l	ND	32	ND	32	ND	43	ND	32
TOLUENE	mg/l	94	2.5	66	2.5			100	2.5
XYLENE (TOTAL)	mg/l	4.1	2.5	2.8	2.5			3.9	2.5
pH	S.U.	6.5		6.5				6.5	
FLASH POINT	F	>200		>200		<70		>200	
TOX	mg/l	ND	200	ND	200	ND	0.1%	ND	200
BRITISH THERMAL UNITS	BTU/lb	WNC		WNC		19100		WNC	

mg/l = MILLIGRAMS/LITRE = PPM  
ND - CHEMICAL NOT DETECTED IN THIS SAMPLE  
WNC (BTU/lb) - WILL NOT COMBUST

without a second column confirmation, the specific analytes such as MeCl and 1,1,1-Trichloroethane are difficult to confirm due to the many compounds that fall within the retention times for these analytes.

Based on measurements taken with an ORS oil/water interface probe, the inspection of Tank No.4 indicated that the bottom of the UST was at 16.24ft below the top of the fill pipe. The top of the liquid present in the UST was at 15.49ft below the top of the fill pipe. This indicates that approximately 0.75ft of fluid exists in the tank and that 0.29ft was petroleum-based product and the remainder was assumed to be water. The total amount of fluid in the tank is estimated to be 739gal, of which 381gal is petroleum-based product. It is assumed that the remaining 358gal of fluid is water, contaminated with aviation fuels, MeCl and 1,1,1-Trichloroethane. The contents of UST Tank No. 4 were not sampled during this field effort.

### **2.1.5 Site Assessment Activities, April 1992**

In April 1992, ASI resampled the inactive 600gal UST adjoining UST Tank Nos 1 and 2 as well as the inactive UST Tank No. 3 to determine if either tank contained non-fuel organics. Analytical results are tabulated in Table 2.3.

In addition to the fuel related compounds, results of the inactive 600gal UST sampling show that the tank does not contain MeCl. The results of the UST Tank No. 3 sampling indicate that MeCl is present in addition to the fuel related compounds. These results are similar to those recorded by Metcalf & Eddy, Inc. in December 1990 (Table 2.2).

## **2.2 PREVIOUS INVESTIGATIONS - SITE 5**

### **2.2.1 Tank Measurement/Sampling, December 1991**

In December 1991, Hatcher-Sayre was retained by Electrical Consultants, P.C. to sample the contents of 12 USTs at Site 5. Prior to the sampling of these USTs, Hatcher-Sayre measured the liquid levels in each tank. Measurements pertaining to the petroleum product/water interfaces, descriptions of the tank contents and product and water volumes are summarized in Table 2.4.

The samples collected from the USTs were submitted to Wadsworth/Alert Laboratories (North Canton, OH) and analyzed for VOCs, Bomb TOX, toxicity characteristic leaching procedure (TCLP) metals, corrosivity, reactivity, and flashpoint. Analytical results are tabulated in Table 2.5. These results indicate the tanks contain mixtures of water and AVGAS.

### **2.2.2 Site Assessment Activities, April 1992**

ASI conducted a site assessment of Site 5 in April 1992 (ASI, Sept 1992). This investigation consisted of the augering of 18 soil borings (SB01 through SB18) ranging in depth from 18ft to 30ft below grade. Four of the soil borings were converted to monitoring wells (MW01 through MW04) during the course of this investigation. Laboratory analyses of soil samples collected

TABLE 2.3  
SITE 4 - SUMMARY OF ANALYTICAL RESULTS OF THE ABANDONED USTs (UST NO. 3; 600-GAL.)  
(ADVANCED SCIENCES, INC., APRIL 1992)  
Virginia Air National Guard  
Richmond International Airport  
Sandston, Virginia

ASI/UST Laboratory Analytical Results, April 1992							
Location	Benzene (ppb)	Toluene (ppb)	Ethylbenzene (ppb)	Xylene (ppb)	1,2-Dichloroethane (ppb)	Methylene Chloride (ppb)	1,1,1-Trichloroethane (ppb)
600 gal UST	122,579	12,121	24,554	54,667	24.8	ND	ND
UST No. 3	97,185 <sup>2</sup>	17,456	37,332	76,584	27.5	17.9	26.1
Tentatively Identified Compounds							
600 gal UST:	Cyclopentane 1,1-Dimethylcyclopentane Cyclohexane Methylcyclopentane 2,3-Dimethylbutane 2,2,3,4-Tetramethylpentane 2,4-Dimethylpentane 2,3-Dimethylpentane				UST 3: Cyclopentane 1,1-Dimethylcyclopentane Cyclohexane Methylcyclopentane 2,3-Dimethylbutane 2,2,3,4-Tetramethylpentane 2,4-Dimethylpentane 2,3-Dimethylpentane 2,2,5-Trimethylhexane		

ppb = Parts per billion  
ND = Non Detect

UST = Underground Storage Tank

Analytical Methodology: Volatile Organics - EPA Method 8240 with confirmation analysis of halogenated hydrocarbon compounds using EPA Method 601.

TABLE 2.4  
SITE 5 - DEPTH TO TOP OF PRODUCT AND WATER IN 12 USTs  
ELECTRICAL CONSULTANTS, P.C./HATCHER-SAYRE, INC., JANUARY 1992  
Virginia Air National Guard  
Sandston, Virginia

TANK NO.	RISE PIPE LENGTH (FEET)	DEPTH FROM PROD RISER (FEET)	DEPTH FROM TANK (FEET)	DEPTH WATER FROM RISER (FEET)	DEPTH WATER FROM TANK (FEET)	TANK DIMENSION (FEET)	ELEV PROD IN TANK (FEET)	ELEV WATER IN TANK (FEET)	PRODUCT THICKNESS (FEET)	COMMENTS
1	4.33	4.42	0.09	4.56	0.23	10.50	10.41	10.27	0.14	PROD/H <sub>2</sub> O
2	4.92	4.68	-0.24	5.50	0.58	10.50	10.74	9.92	0.82	PROD/H <sub>2</sub> O
3	3.50	3.18	-0.32	—	—	3.50	3.82	—	3.50	PRODUCT
4	3.50	3.24	-0.26	6.44	2.94	3.50	3.76	0.56	3.20	PROD/H <sub>2</sub> O
5	0.33	4.37	4.04	5.21	4.88	10.50	6.46	5.62	0.84	PROD/H <sub>2</sub> O
6	4.17	4.41	0.24	5.46	1.29	10.50	10.26	9.21	1.05	PROD/H <sub>2</sub> O
7	0.25	3.97	3.72	4.70	4.45	10.50	6.78	6.05	0.73	PROD/H <sub>2</sub> O
8	0.58	4.45	3.87	5.01	4.43	10.50	6.63	6.07	0.56	PROD/H <sub>2</sub> O
9	3.00	—	—	3.16	0.16	3.50	—	3.34	3.34	WATER
10	3.00	3.16	0.16	6.50	3.50	3.50	3.34	0.00	3.34	PROD/H <sub>2</sub> O
11	4.67	—	—	4.39	-0.28	10.50	—	10.78	10.50	WATER
12	4.67	3.98	-0.69	4.98	0.31	10.50	11.19	10.19	1.00	PROD/H <sub>2</sub> O

NOTES:

- = Depth to top of product from the top of the riser pipe.
- = Depth to top of product from the top of the tank.
- Negative numbers indicate that the liquid level is above the top of the tank.
- = Depth to top of water from the top of the riser pipe.
- = Depth to top of water from the top of the tank.
- = Elevation of top of product above the bottom of the tank.
- = Elevation of top of water above the bottom of the tank.

TABLE 2.5  
SITE 5 - SUMMARY OF LABORATORY ANALYTICAL DATA, FOR CONTENTS OF 12-25,000GAL USTs  
ELECTRICAL CONSULTANTS, P.C./HATCHER-SAYRE, INC., JANUARY 1992  
Virginia Air National Guard  
Sandston, Virginia

TANK	DATE SAMPLED	BENZENE	TOLUENE	TOTAL XYLENES	CORROSIVITY pH (S.U.)	FLASH POINT CLOSED CUP	BURN POINT	BOMB TOX	TCLP BARIUM	TCLP LEAD
1	12/09/91	21 mg/l	60 mg/l	ND	7.0	>180°F	—	0.13%	0.3 mg/l	ND
2	12/09/91	20 mg/l	73 mg/l	ND	7.0	>180°F	—	0.12%	ND	4.2 mg/l
3	12/10/91	12,000 mg/kg	71,000 mg/kg	14,000 mg/kg	7.0	DNF	75°F	0.61%	ND	50 mg/l
4	12/10/91	16,000 mg/kg	60,000 mg/kg	7,800 mg/l	7.0	DNF	73°F	1.3%	ND	14 mg/l
5	12/11/91	21 mg/l	29 mg/l	4.3 mg/l	7.0	DNF	75°F	0.13%	ND	4.9 mg/l
6	12/10/91	22 mg/l	52 mg/l	7.6 mg/l	7.0	DNF	61°F	ND	ND	3.9 mg/l
7	12/10/91	54 mg/l	52 mg/l	ND	7.0	DNF	72°F	0.12%	0.2 mg/l	0.7 mg/l
8	12/10/91	48 mg/l	45 mg/l	ND	7.0	>180°F	—	0.11%	0.2 mg/l	ND
9	12/11/91	15,000 mg/kg	55,000 mg/kg	4,900 mg/kg	7.0	DNF	75°F	0.64%	ND	69 mg/l
10	12/11/91	16,000 mg/kg	53,000 mg/kg	4,700 mg/kg	7.0	DNF	74°F	0.59%	ND	180 mg/l
11	12/11/91	28 mg/l	44 mg/l	ND	7.0	>180°F	—	ND	0.2 mg/l	ND
12	12/11/91	39 mg/l	51 mg/l	ND	7.0	DNF	75°F	0.19%	0.2 mg/l	ND

NOTES:

S.U. = Standard Units  
ND = Not Detected  
DNF = Did Not Flash

Burn Point data provided verbally by the laboratory on January 22, 1992.

in the POL area detected maximum TPH and BTEX concentrations of 42.4ppm and 7494.6ppb, respectively. Laboratory analyses of groundwater samples collected beneath the POL area and immediately downgradient indicate levels of BTEX that range from 47.1ppb to 5296.2ppb. Additionally, laboratory analyses indicate that an area immediately downgradient from the POL has levels of Trichloroethene that range from 34.2ppb to 1994.2ppb.

In addition to the soil boring/monitoring well installations completed at Site 5, resampling of the UST No. 4 contents was conducted. Since the Bomb TOX test data from the December 1991 sampling event reports only the percentage of halogens as total chlorines, it was concluded that the chlorinated compounds should be specifically identified. Since the UST No. 4 contents reportedly contained the highest percentage of total chlorine (1.3 percent), a sample from UST No. 4 was analyzed for VOCs (EPA Method 8240). Confirmation of the VOC analytes was obtained using EPA Method 601.

Table 2.6 shows the analytical results of this confirmation and the specific halogenated compounds identified. 1,2-Dibromoethane, 1,2-Dichloroethane, 1,1,1-Trichloroethane, and Trichloroethene were typically used as AVGAS additives required by piston-driven aircraft used in the 1940s and 1950s.

TABLE 2.6  
 SITE 5 - SUMMARY OF LABORATORY ANALYTICAL DATA, UST NO. 4  
 ADVANCED SCIENCES, INC., APRIL 1992  
 Virginia Air National Guard  
 Richmond International Airport  
 Sandston, Virginia

Location	Benzene	1,2-Dibromoethane	1,2-Dichloroethane	Ethylbenzene	Toluene	1,1,1-Trichloroethane	Trichloroethene	Total Xylene
UST 4	220,112	57.8	22.0	57,887	21,249	37.3	27.9	97,886

Tentatively identified compounds (TIC) identified during the laboratory analysis include:

Cyclohexane  
 Methylcyclopentane  
 2,3-Dimethylbutane  
 2,3-Dimethylpentane  
 3-Methylhexane  
 2,5-Dimethylhexane  
 2,2,5-Trimethylhexane

All values are reported in parts per billion.



## **3.0 CLOSURE ASSESSMENT ACTIVITIES**

### **3.1 OBJECTIVES**

The objectives of the closure assessment were to determine the extent of contaminated soil adjacent to the USTs requiring excavation, to provide documentation of soil and groundwater conditions following excavation, and to document closure activities in accordance with applicable VADEQ regulations. During closure activities, ASI provided technical support to the Base to ensure that the UST removal contractor [(E & K, Inc.) hereinafter referred to as the Contractor] was in compliance with the technical requirements (as specified in the Plans and Specifications for Removal of Abandoned Underground Storage Tanks, Virginia Air National Guard, Richmond International Airport, Sandston, VA., dated July 1991 and revised April 1992, and Addendum Numbers 1 through 7) of the contract. ASI was also responsible for collecting soil and/or groundwater closure samples from the excavations, and providing off-site fixed based laboratory analysis to verify clean conditions within the excavations.

### **3.2 REGULATORY GUIDANCE**

The Water Division of the VADEQ has jurisdiction over closure of petroleum USTs, and requirements for assessing petroleum UST sites at closure are specified in VR 680-13-02, "Underground Storage Tanks: Technical Standards and Corrective Action Requirements," Part VII, effective October 25, 1989. The excavation zone soil will be considered clean if analysis by an approved EPA method indicates TPH concentrations are less than 100ppm. The VADEQ Water Division has jurisdiction over closure activities associated with all aspects of the inactive side of the Site 4 POL facility (except Tank No. 4) and the whole Site 5 POL facility.

The Waste Division of the VADEQ has jurisdiction over closure of hazardous waste USTs, and requirements for assessing hazardous waste USTs at closure are specified in VR 672-10-1, "Hazardous Waste Management Regulations," dated January 4, 1993. Tank No. 4 at Site 4 is subject to a Compliance Agreement between the former Virginia Waste Management Board (currently the VADEQ Waste Division) and the Virginia Air National Guard. The agreement took effect on February 17, 1993. The Compliance Agreement requires the Virginia Air National to conduct closure activities associated with Tank No. 4 in accordance with requirements of the VADEQ Waste Division.

### **3.3 SITE 4 CLOSURE ACTIVITIES**

Figure 3.1 depicts the USTs, tank manheads, valve pits, and associated fuel transfer piping that were removed from the inactive side of the Site 4 facility. Section 3.3.1 details closure activities associated with the petroleum USTs (Tank Nos. 1, 2, 3, and the 600gal tank), while Section 3.3.2 details closure activities associated with Tank No. 4. Selected photographs of closure activities conducted at Site 4 are shown in Appendix A.



# UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

## LEGEND:

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 8" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- 3 UNDERGROUND STORAGE TANK MANHEAD PITS
- 3 WATER CONTROL VALVES/PIT
- ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 8" WATER SUPPLY
- DENOTES LINE DISCONTINUITY
- 3635 BUILDING

GRID SCALE: 20 FT PER GRID

VANG BASE


192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

FIGURE 3.1

Site 4 - POL Facilities

ADVANCED SCIENCES, INC.

FILE: RANG40 DATE: 1996



### 3.3.1 Closure Activities Associated with Petroleum USTs

#### 3.3.1.1 Contractor Closure Activities

Closure activities are detailed as follows:

- Samples of contents from Tank Nos. 1, 2, and the 600gal tank were collected, composited, and sent for laboratory analysis by

Rickmond Environmental  
1643 Merrimac Trail  
Williamsburg, VA 23185

- Analysis of the composite sample(s) was performed by

Solutions Laboratories, Inc.  
814-B Greenbrier Circle  
Chesapeake, VA 23320

Although previous analyses had been performed on the tank contents, current characterization of the liquid contents was necessary for proper manifesting, treatment and/or disposal of the material. Analytical results are available through the Base Environmental Engineer.

- The contents of Tank Nos. 1, 2, 3, and the 600 gal tank were removed during the period of December 21, 1993 through January 5, 1994. Rickmond Environmental coordinated the removal, transportation, treatment and/or disposal of the petroleum-contaminated wastewater. Transportation of the fluids was performed by PTC, Inc. (EPA ID No. NCD986180867).

Rickmond Environmental removed approximately 76,200gal of benzene contaminated ballast water manifested as EPA-D018 (benzene; regular flammable liquid waste) (Table 3.1). All petroleum-contaminated wastewater was treated and/or disposed of at

ERC, Inc.  
2nd & Maury Street  
Richmond, VA 23224  
(EPA ID No. VAD086293719)

- Excavation and removal of Tank Nos. 1, 2, 3, and the 600gal tank, tank manheads and aquatrap pits, and associated piping and equipment were performed from January 14, 1994 through January 27, 1994. The excavation contractor was Onslow Environmental, Inc., Jacksonville, NC. Each 25,000gal UST was approximately 40ft long and 10.5ft in diameter. Each 600gal tank was approximately 8ft long and 3.5ft in diameter.

**TABLE 3.1**  
**SITE 4 - UNIFORM HAZARDOUS WASTE MANIFEST LIST FOR PETROLEUM-CONTAMINATED**  
**WASTEWATER REMOVED FROM UST NOS. 1, 2, 3, AND 600GAL TANK**  
**VIRGINIA AIR NATIONAL GUARD**  
**SANDSTON, VA**

SITE	DATE	GENERATOR'S EPA ID No.	MANIFEST DOCUMENT No.	TRANSPORTER COMPANY	TRANSPORTER'S EPA ID No.	DESIGNATED FACILITY	DESIGNATED FACILITY EPA ID No.	US DOT DESCRIPTION	CONTAINER No.	CONTAINER TYPE	TOTAL QUANTITY (gallons)	WASTE No.	COMMENTS
4	93/12/21	VA0572890002	00010	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/21	VA0572890002	00011	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	12400	D018	Pg. III, CLASS 3, BENZENE
4	93/12/22	VA0572890002	00012	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/22	VA0572890002	00013	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/22	VA0572890002	00014	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/22	VA0572890002	00015	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/22	VA0572890002	00016	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/22	VA0572890002	00017	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/22	VA0572890002	00018	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	43400	D018	Pg. III, CLASS 3, BENZENE
4	93/12/23	VA0572890002	00019	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/23	VA0572890002	00020	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/23	VA0572890002	00021	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
4	93/12/23	VA0572890002	00022	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	1200	D018	Pg. III, CLASS 3, BENZENE
											19600		
4	93/01/05	VA0572890002	00041	PTC, INC.	NCD986180867	ERC, INC	VAD086293719	Rg. Flammable liquid	001	TT	500	D018	Pg. III, CLASS 3, BENZENE
											500		
											76200		
										SUBTOTAL			

UST No. 4 (b)

NOTES:  
 (a) ALL TOTAL QUANTITY VOLUMES ARE AS PER TRANSPORTER  
 (b) TOTAL QUANTITY VOLUMES FOR UST No. 4 NOT YET AVAILABLE

All excavated soil was visibly inspected and screened in the field using a photoionization detector before stockpiling. Potentially contaminated soil was stockpiled adjacent to the excavations on plastic sheets. All soil determined to be contaminated was treated and/or disposed of in accordance with all applicable regulations.

- All USTs and associated piping and equipment were decontaminated, transported, and disposed of off-site by D&S Metal Recycling, Glen Allen, VA.

Dry ice was placed in the USTs to displace any potential explosive vapors, and the tanks and associated piping and equipment were decontaminated using SUPERCLEAN, an alkaline mixture containing detergents, phosphates, butoxyethanol and water. The material safety data sheet for SUPERCLEAN is attached as Appendix B.

A tar coating was removed from the outside of each of the 25,000gal USTs. The tar coating was originally used to protect the steel from corroding, and was easily chipped off the outside of the USTs. The tar coating was transported off-site and properly disposed of by D&S Metal Recycling.

Each 25,000gal UST was gas-cut into eight sections and loaded onto a flatbed truck for transportation and disposal off-site. All decontaminated steel was disposed of as scrap metal.

- All reinforced concrete structures were demolished within the excavations and allowed to remain as backfill.
- Backfilling was completed using crushed granite sand. Excavated soil that was determined to be non-contaminated was used as top soil and graded to promote drainage of any precipitation away from the former UST locations.

### **3.3.1.2 ASI Closure Assessment Sampling Activities**

As shown on Figure 3.2, a total of 11 samples were collected from the walls and floors of the excavations created by the removal of USTs Nos. 1, 2, 3 and the 600gal tank. The average depth at which these samples were collected in the excavations associated with the 25,000gal USTs was 16-18ft below grade. In the excavations associated with the aquatrap pits, samples were collected at an average depth of 8-10ft below grade. The grab soil samples were collected from the bucket of the hydraulic excavator and immediately placed into laboratory-provided glass containers.

The 11 soil samples were sent to Environmental Laboratories, Inc. and analyzed for gasoline range organics (GRO) and diesel range organics (DRO). Analyses for DRO and GRO were performed in accordance with EPA SW-846 Standard Methods 8100 and 8015, respectively. Analytical results are discussed in Section 4.



# UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

## LEGEND:

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 6" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- 3 [Symbol] UNDERGROUND STORAGE TANK
- [Symbol] MANHEAD PITS
- [Symbol] WATER CONTROL VALVES/PIT
- ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 6" [Symbol] WATER SUPPLY
- [Symbol] DENOTES LINE DISCONTINUITY
- 3635 BUILDING

GRID SCALE: 20 FT PER GRID




FIGURE 3.2

Site 4 - Sample Locations, UST Pit Nos. 1,2,3, and Aquatrap Pits

ADVANCED SCIENCES, INC.

FILE: RANG45 DATE: 1996

VANG BASE

192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

### 3.3.2 Closure Activities Associated with Tank No. 4

#### 3.3.2.1 Contractor Closure Activities

Closure activities are detailed as follows:

- Samples of Tank No. 4 contents (aqueous and non-aqueous phases) were obtained and sent for laboratory analysis by Rickmond Environmental. Analysis of the samples was performed by Solutions Laboratories, Inc. Samples were analyzed for TPH using EPA Method 418.1, TOX using EPA Method 9020, PCBs using EPA Method 8080, VOCs using EPA Method 8240, BTEX using EPA Method 8020, and reactivity, ignitability, corrosivity, and toxicity (TCLP metals only). Although previous analyses had been performed on the tank contents, current characterization of the liquid contents was necessary for proper manifesting, treatment and/or disposal of the material. Analytical results are attached as Appendix C.
- The contents of Tank No. 4 were removed on February 2, 1994. Rickmond Environmental coordinated the removal, transportation, treatment and/or disposal of the tank contents.
- On February 8, 1994, Tank No. 4 was exposed. The shallow soil that provided cover for the tank was excavated and stockpiled on plastic adjacent to the excavation. Deeper soil that could have been potentially impacted by the contents of the tank was excavated and placed in plastic-lined roll-off containers. On February 9, 1994, Tank No. 4 was removed using a 65 ton LinkBelt crane. The tank was placed on plastic adjacent to the excavation.
- Samples of the excavated soil associated with Tank No. 4 were taken on February 8, 1994 and sent for analysis to

EnviroCompliance Laboratories, Inc.  
Glen Allen, VA 13060

All soil samples were analyzed for VOCs using EPA Method 8240. Analytical results are available through the Base Environmental Engineer.

- Tank No. 4 and its contents along with all excavated soil associated with the tank have been disposed of in accordance with the approved closure plan (ASI 1996). The tank was decontaminated and wipe sampled in accordance with the approved closure plan. Results of the wipe sample analyses are available through the Base Environmental Engineer.
- Backfilling of the excavation was completed using crushed granite sand. Excavated soil that was determined to be non-contaminated was used as top soil and graded to promote drainage of any precipitation away from the former UST location.



### 3.3.2.2 ASI Closure Assessment Sampling Activities

As shown on Figure 3.3, a total of four samples were collected from the walls and floor of the excavation created by the removal of Tank No. 4. These samples were collected at an average depth of 16-18ft below grade. All samples were sent to Environmental Laboratories, Inc. and analyzed for VOCs using EPA Method 8240 and RCRA metals.

## 3.4 SITE 5


Figure 3.4 depicts the USTs, tank manheads, valve pits, and associated fuel transfer piping that were removed from the Site 5 facility. Section 3.4.1 details closure activities conducted by the Contractor. Section 3.4.2 details closure assessment sampling activities conducted by ASI. Selected photographs of closure activities conducted at Site 5 are shown in Appendix D.

### 3.4.1 Contractor Closure Activities

Closure activities are detailed as follows:

- Samples of contents from Tank Nos. 1, 2, 11, and 12 were obtained, composited, and sent for laboratory analysis by Rickmond Environmental. Analysis of the composite sample(s) was performed by Solutions Laboratories, Inc. Although previous analyses had been performed on the tank contents, current characterization of the liquid contents was necessary for proper manifesting, treatment and/or disposal of the material. Based on previous analyses of Site 5 tank contents, it was determined that a composite sample from Tank Nos. 1, 2, 11, and 12 would be representative of all tank contents from Site 5. Analytical results are available through the Base Environmental Engineer.
- The contents of all USTs and associated piping were removed during the period of December 17, 1993 through January 6, 1994. Rickmond Environmental coordinated the removal, transportation, treatment and/or disposal of the petroleum product and petroleum-contaminated wastewater. Transportation of the fluids was performed by Industrial Marine Services, Inc. and PTC, Inc. Rickmond Environmental removed approximately 209,900gal of petroleum-contaminated waste water manifested as EPA D-018 (benzene; regular flammable liquid waste) (Table 3.2). In addition, approximately 5,500gal of product were removed from the USTs and associated piping (Table 3.2). All petroleum-contaminated wastewater was treated and/or disposed of at ERC, Inc.
- Excavation of the USTs, valve pits, and associated piping began on December 16, 1993. The excavation contractor was Onslow Environmental, Inc. Soil that was visibly contaminated or contaminated as determined by periodic field screening using a photoionization detector was segregated from non-contaminated soil during excavation activities. Potentially contaminated soil was stockpiled adjacent to the





UST CAPACITY:

- UST NO. 1 - 25,000 GAL
- NO. 2 - 25,000 GAL
- NO. 3 - 25,000 GAL
- NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

LEGEND:

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 6\"/>

GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.

FILE: RANG44


DATE: 1996

FIGURE 3.3

Site 4 - Sample Location, UST Pit No. 4

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia



ADVANCED SCIENCES, INC.

FILE: RANG41

DATE: 1996

FIGURE 3.4

Site 5 - POL Facilities

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia

SITE 5 - UNIFORM HAZARDOUS WASTE MANIFEST LIST FOR PETROLEUM-CONTAMINATED  
WASTEWATER AND PRODUCT REMOVED FROM TANKS AND ASSOCIATED PIPING  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	DATE	GENERATOR'S EPA ID No.	MANIFEST DOCUMENT No.	COMPANY	EPA ID No.	FACILITY	DESIGNATED FACILITY EPA ID No.	US DOT DESCRIPTION	CONTAINER No.	CONTAINER TYPE	TOTAL QUANTITY (gallons)	WASTE No.	COMMENTS
UN 1203													
UST Nos. 3, 4, 9, 10, and LINES	5	93/12/17	BOL 4062	IMS, INC.						subtotal	5500		PRODUCT
											5500		
UN 1203													
UST Nos. 1, 2, 5, 6, 7, 8, 11, 12	5	93/12/18	VA0572890002	IMS, INC.	00001	VAD041441115	ERC, INC	Rg. Flammable liquid	001	TT	6495	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/18	VA0572890002	IMS, INC.	00002	VAD041441115	ERC, INC	Rg. Flammable liquid	001	TT	7620	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/18	VA0572890002	IMS, INC.	00003	VAD041441115	ERC, INC	Rg. Flammable liquid	001	TT	21817	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/20	VA0572890002	PTC, INC.	00004	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/20	VA0572890002	PTC, INC.	00005	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/20	VA0572890002	PTC, INC.	00006	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/20	VA0572890002	PTC, INC.	00007	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/20	VA0572890002	PTC, INC.	00008	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/20	VA0572890002	PTC, INC.	00009	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	37200	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/23	VA0572890002	PTC, INC.	00022	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	5000	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/23	VA0572890002	PTC, INC.	00023	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	6200	D018	Pg. III, CLASS 3, BENZENE
	5	93/12/23	VA0572890002	PTC, INC.	00024	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	17400	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/03	VA0572890002	PTC, INC.	00025	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/03	VA0572890002	PTC, INC.	00026	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/03	VA0572890002	PTC, INC.	00027	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/03	VA0572890002	PTC, INC.	00028	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/03	VA0572890002	PTC, INC.	00029	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/03	VA0572890002	PTC, INC.	00030	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	48000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/04	VA0572890002	PTC, INC.	00031	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/04	VA0572890002	PTC, INC.	00032	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/04	VA0572890002	PTC, INC.	00033	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/04	VA0572890002	PTC, INC.	00034	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/04	VA0572890002	PTC, INC.	00035	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/04	VA0572890002	PTC, INC.	00036	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/04	VA0572890002	PTC, INC.	00037	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	56000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/05	VA0572890002	PTC, INC.	00038	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/05	VA0572890002	PTC, INC.	00039	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/05	VA0572890002	PTC, INC.	00040	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	8000	D018	Pg. III, CLASS 3, BENZENE
	5	94/01/05	VA0572890002	PTC, INC.	00041	NCD986180867	ERC, INC	Rg. Flammable liquid	001	TT	5500	D018	Pg. III, CLASS 3, BENZENE
										subtotal	29500		
											209917		

NOTES:  
(a) ALL TOTAL QUANTITY VOLUMES AS PER TRANSPORTER

excavations on plastic sheets. All soil determined to be contaminated was treated and/or disposed of in accordance with all applicable regulations.


- All USTs and associated piping and equipment were decontaminated, transported, and disposed of off-site by D&S Salvage Company. Dry ice was placed in the USTs to displace any potential explosive vapors, and the tanks and associated piping and equipment were decontaminated using SUPERCLEAN. A tar coating was removed from the outside of each of the 25,000gal USTs. The tar coating was originally used to protect the steel from corroding, and was easily chipped off the outside of the USTs. The tar coating was transported off-site and properly disposed of by D&S Salvage Company. Each 25,000gal UST was gas-cut into eight sections, and loaded onto a flatbed truck for transportation and disposal off-site. All decontaminated steel was disposed of as scrap metal.
- All reinforced concrete structures were demolished within the excavations and allowed to remain as backfill.
- Excavation activities at Site 5 were completed on February 11, 1994. Backfilling was completed using crushed granite sand. Excavated soil that was determined to be non-contaminated was used as top soil and graded to promote drainage of any precipitation away from the former UST locations.


### **3.4.2 ASI Closure Assessment Sampling Activities**

Figure 3.5 reflects the location of the 22 soil samples that were collected from the walls and floors of the excavations associated with the removal of the eight 25,000gal USTs and the four 600gal USTs. The average depth at which these samples were collected in the pits associated with the 25,000gal USTs was 16-18ft below grade. Following the destruction of the aquatrap pits, samples were taken at an average depth of 7ft below grade.

As shown in Figure 3.6, 15 soil samples were taken beneath the fuel transfer piping, fill pits, valve pits, pressure control pits and air separator pit. These samples were taken at depths that ranged from 4 to 7ft below grade.

The grab soil samples were collected from the bucket of the hydraulic excavator and immediately placed into laboratory-provided glass containers. All soil samples were sent to Environmental Laboratories, Inc. for GRO and DRO analysis. Analyses for DRO and GRO were performed in accordance EPA SW-846 Standard Methods 8100 and 8015, respectively. Analytical results are discussed in Section 4.





ADVANCED SCIENCES, INC.

FILE: RANG42 DATE: 1996

**FIGURE 3.6**  
 Site 5 - Sample locations, Piperuns, Pressure Control Pits, Valve Pits, Fill Pits, and Air Separator

**VANG BASE**  
 192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

## **4.0 CLOSURE ASSESSMENT FINDINGS**

### **4.1 SITE 4 - CLOSURE SAMPLING RESULTS**

Within the excavations associated with the removal of UST Nos. 1, 2, 3 and one 600gal UST, a total of 11 soil samples were collected. Table 4.1 and Figure 4.1 show five of the 11 samples have GRO and/or DRO results above the detection limit of 5 mg/Kg. Except for Sample No. RMD4TP11C1801 collected from the south wall of the excavation for Tank No. 3 (DRO concentration of 448mg/Kg), combined GRO and DRO concentrations were well below the VADEQ Water Division action level of 100ppm. Laboratory analytical results and chain of custody forms for Site No. 4 are in located Appendix E. Associated laboratory quality control data is located in Appendix G.

In the excavation associated with the removal of Tank No. 4, four soil samples were collected. These soil samples were analyzed for RCRA Metals (Table 4.2) and VOCs (Table 4.3).

Cadmium, mercury, selenium and silver were detected at or below the method detection levels. Arsenic was detected at concentrations ranging from 1.3mg/kg to 2.0mg/kg, while barium was detected at concentrations ranging from 10.1mg/kg to 15.6 mg/kg. Background concentrations are not available for these constituents. Chromium and lead concentrations detected were within published background ranges for these constituents. Figures 4.2 through 4.5 depict analytical results for arsenic, barium, chromium, and lead, respectively.

As shown in Table 4.3 and on Figure 4.6, the only VOC to exceed detection limits was methylene chloride. With a analytical limit of quantitation of 5.0µg/Kg, three of the four samples had concentrations of methylene chloride ranging from 5.1µg/Kg to 10.2µg/Kg.

### **4.2 SITE 5 - CLOSURE SAMPLING RESULTS**

A total of 37 soil samples were collected at Site 5. Twenty-two of these samples were collected in excavations associated with UST Nos. 1 through 12. Table 4.4 and Figure 4.7 show 9 of the 22 samples having GRO and/or DRO concentrations above the detection limit of 5mg/kg. Combined GRO and DRO concentrations detected at these sample locations are below the VADEQ Water Division action level of 100ppm, except for concentrations associated with 2 samples collected from the excavation associated with Tank Nos. 1 and 2 (Sample Nos. RMD5TP9C2001 and RMD5TP10C1801). A maximum concentration of 375.5ppm was detected on the south wall of the excavation. Laboratory analytical results and chain of custody forms for Site 5 are in located in Appendix F. Associated laboratory quality control data is located in Appendix G.

15 soil samples were collected from excavations associated with the removal of the pipe runs, pressure control pits, valve pits, fill pits and air separator pits (Table 4.5). Laboratory analytical data indicate that none of these samples had concentrations that exceeded the detection limits.



**TABLE 4.1**  
**SITE 4 -- GRO/DRO LABORATORY ANALYTICAL RESULTS FOR**  
**SOIL SAMPLES FROM PITS FOR UST Nos. 1, 2, 3, and AQUATRA**  
**ADVANCED SCIENCES, INC., DECEMBER 1993-FEBRUARY 1994**  
**VIRGINIA AIR NATIONAL GUARD**  
**SANDSTON, VIRGINIA**

<b>UST PIT SAMPLE ID</b>	<b>GRO (1) RESULTS (mg/Kg)</b>	<b>GRO (1) DL (mg/Kg)</b>	<b>DRO (2) RESULTS (mg/Kg)</b>	<b>DRO (2) DL (mg/Kg)</b>
<b>UST No. 1/2 &amp; AQUATRAP PIT</b>				
1. RMD4TP5D1801	<5	5	<5	5
2. RMD4TP6C1801	<5	5	<5	5
3. RMD4TP3C1801	<5	5	<5	5
4. RMD4TP5C1801	<5	5	14.8	5
5. RMD4TP5B1801	<5	5	<5	5
6. RMD4TP6B1801	12	5	<5	5
7. RMD4AT6C1001	<5	5	<5	5
<b>UST No. 3 &amp; AQUATRAP PIT</b>				
8. RMD4AT8C1001	9.9	5	8.2	5
9. RMD4TP9C1801	<5	5	<5	5
10. RMD4TP10B1801	<5	5	5.7	5
11. RMD4TP11C1801	<5	5	448	5

**NOTES:**

**DL = DETECTION LIMIT**

**mg/Kg = milligrams/Kilograms = parts per million**

**(1) GRO = GASOLINE RANGE ORGANICS BY EPA METHOD 8015**

**(2) DRO = DIESEL RANGE ORGANICS BY EPA METHOD 8100**





UST CAPACITY:

UST NO. 1 - 25,000 GAL  
NO. 2 - 25,000 GAL  
NO. 3 - 25,000 GAL  
NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

LEGEND:

--- STORM DRAIN AND SANITARY SEWAGE  
--- WATER  
--- FIRE WATER LINES  
--- ABANDONED 6" AIRCRAFT FUEL LINE  
--- SPRINKLER SUPPLY LINE  
--- 3 UNDERGROUND STORAGE TANK MANHEAD PITS  
--- WATER CONTROL VALVES/PIT  
--- ELECTRIC FOR REMOTE CONTROL  
--- GASOLINE LINE  
--- DRAIN  
--- 6" WATER SUPPLY  
--- DENOTES LINE DISCONTINUITY  
--- BUILDING  
3635

NOTE:

SAMPLE LOCATIONS SHOWN WITHOUT RESULTS REPRESENT LOCATIONS WHERE GRO AND DRO CONCENTRATIONS WERE BELOW DETECTION LEVELS

(ALL RESULTS IN mg/kg)

GRID SCALE: 20 FT PER GRID




FIGURE 4.1

Site 4 - GRO/DRO Analytical Results from  
UST Pits 1,2,3 and Aquatrap Pits

ADVANCED SCIENCES, INC.

FILE: RANG52

DATE: 1996

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia

# SITE 4 - TOTAL METALS LABORATORY ANALYTICAL RESULTS FOR SOIL

JUST No.4 PIT

ADVANCED SCIENCES, INC., DECEMBER 1993-FEBRUARY 1994  
 VIRGINIA AIR NATIONAL GUARD  
 SANDSTON, VIRGINIA

SAMPLE ID	TOTAL METALS ARSENIC (1)		TOTAL METALS BARIUM (2)		TOTAL METALS CADMIUM (3)		TOTAL METALS CHROMIUM (4)		TOTAL METALS LEAD (5)		TOTAL METALS MERCURY (6)		TOTAL METALS SELENIUM (7)		TOTAL METALS SILVER (8)	
	RESULTS DL	(mg/Kg)	RESULTS DL	(mg/Kg)	RESULTS DL	(mg/Kg)	RESULTS DL	(mg/Kg)	RESULTS DL	(mg/Kg)	RESULTS DL	(mg/Kg)	RESULTS DL	(mg/Kg)	RESULTS DL	(mg/Kg)
RMD4TP9C1801	1.7	0.5	15.6	1.0	<0.1	0.1	4.9	0.8	6.8	0.5	<0.10	0.1C	<5.0	5.0	<0.2	0.2
RMD4TP10C1801	1.3	0.5	10.1	1.0	<0.1	0.1	7.0	0.8	6.5	0.5	<0.10	0.1C	<5.0	5.0	<0.2	0.2
RMD4TP10D1801	1.7	0.5	13.5	1.0	0.1	0.1	6.0	0.8	7.2	0.5	<0.10	0.1C	<5.0	5.0	<0.2	0.2
RDM4TP11C1801	2.0	0.5	12.8	1.0	<0.1	0.1	6.1	0.8	8.2	0.5	<0.10	0.1C	<5.0	5.0	<0.2	0.2
BACKGROUND RANGE (9)	NA	NA	NA	1.8 - 8.5	9.3 - 24.7	6.5 - 16.9	NA	NA	NA	NA	NA	NA	NA	NA	NA	NA

## NOTES:

DL = DETECTION LIMIT

NA=NOT AVAILABLE

mg/Kg = milligrams/Kilogram = parts per million

- (1) ANALYSIS PERFORMED ACCORDING TO EPA SW-846 METHOD 7060
- (2) ANALYSIS PERFORMED ACCORDING TO EPA SW-846 METHOD 7081
- (3) ANALYSIS PERFORMED ACCORDING TO EPA SW-846 METHOD 7131
- (4) ANALYSIS PERFORMED ACCORDING TO EPA SW-846 METHOD 7191
- (5) ANALYSIS PERFORMED ACCORDING TO EPA SW-846 METHOD 7421
- (6) ANALYSIS PERFORMED ACCORDING TO EPA SW-846 METHOD 7471
- (7) ANALYSIS PERFORMED ACCORDING TO EPA SW-846 METHOD 7740
- (8) ANALYSIS PERFORMED ACCORDING TO EPA SW-846 METHOD 7761

(9) BACKGROUND VALUES HAVE BEEN TAKEN FROM INFORMATION INCLUDED IN THE FINAL SITE INVESTIGATION REPORT, PREPARED BY METCALF AND EDDY

RMD4SA2.WQ1/24-Jan-96

**TABLE 4.3**  
**SITE 4 – VOLATILE ORGANIC LABORATORY ANALYTICAL RESULTS FOR SOIL**  
**UST No. 4 PIT**  
**ADVANCED SCIENCE, INC., DECEMBER 1993-FEBRUARY 1994**  
**VIRGINIA AIR NATIONAL GUARD**  
**SANDSTON, VIRGINIA**

ANALYTE	SAMPLE ID		SAMPLE ID		SAMPLE ID		SAMPLE ID	
	RMD4TP9C1801		RMD4TP10C1801		RMD4TP10D1801		RMD4TP11C1801	
	RESULTS	LOQ	RESULTS	LOQ	RESULTS	LOQ	RESULTS	LOQ
	(ug/Kg)	(ug/Kg)	(ug/Kg)	(ug/Kg)	(ug/Kg)	(ug/Kg)	(ug/Kg)	(ug/Kg)
Chloromethane	BDL	10	BDL	10	BDL	10	BDL	10
Bromomethane	BDL	10	BDL	10	BDL	10	BDL	10
Vinyl Chloride	BDL	10	BDL	10	BDL	10	BDL	10
Chloroethane	BDL	10	BDL	10	BDL	10	BDL	10
Methylene Chloride	10.2	5.0	BDL	5.0	9.2	5.0	5.1	5.0
Acetone	BDL	100	BDL	100	BDL	100	BDL	100
Carbon Disulfide	BDL	100	BDL	100	BDL	100	BDL	100
1,1-Dichloroethene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
1,1-Dichloroethane	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
trans-1,2-Dichloroethene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Chloroform	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
1,2-Dichloroethane	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
2-Butanone	BDL	50	BDL	50	BDL	50	BDL	50
1,1,1-Trichloroethane	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Carbon Tetrachloride	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Vinyl Acetate	BDL	50	BDL	50	BDL	50	BDL	50
Bromodichloromethane	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
1,1,2,2-Tetrachloroethane	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
1,2-Dichloropropane	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
trans-1,3-Dichloropropene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Trichloroethene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Dibromochloromethane	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
1,1,2-Trichloroethane	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Benzene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
cis-1,3-Dichloropropene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
2-Chloroethyl Vinyl ether	BDL	10	BDL	10	BDL	10	BDL	10
Bromoform	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
2-Hexanone	BDL	50	BDL	50	BDL	50	BDL	50
4-Methyl-2-Pentanone	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Tetrachloroethene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Toluene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Chlorobenzene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Ethyl Benzene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Styrene	BDL	5.0	BDL	5.0	BDL	5.0	BDL	5.0
Total Zylenes	BDL	15	BDL	15	BDL	15	BDL	15

NOTES:  
VOLATILE ORGANICS IN SOIL BY EPA SW-846 METHOD 8240  
ug/Kg = MICROGRAMS/KILOGRAM = parts per billion  
BDL = BELOW SPECIFIED DETECTION LIMIT.  
LOQ = ANALYTICAL LIMIT OF QUANTITATION.



# UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

## LEGEND:

--- STORM DRAIN AND SANITARY SEWAGE  
 --- WATER  
 --- FIRE WATER LINES  
 --- ABANDONED 6" AIRCRAFT FUEL LINE  
 --- SPRINKLER SUPPLY LINE  
 --- UNDERGROUND STORAGE TANK  
 --- MANHEAD PITS  
 3 [ ] WATER CONTROL VALVES/PIT  
 [ ] ELECTRIC FOR REMOTE CONTROL  
 --- GASOLINE LINE  
 --- DRAIN  
 6" WATER SUPPLY  
 T DENOTES LINE DISCONTINUITY  
 3635 BUILDING

(RESULTS IN mg/kg)

GRID SCALE: 20 FT PER GRID!




FIGURE 4.2

Site 4 - Total Metals, Arsenic Analytical Results,  
 UST Pit No. 4

VANG BASE

192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

ADVANCED SCIENCES, INC.

FILE: RANG48 DATE: 1996



# UST CAPACITY:


UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

## LEGEND:

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 6" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- UNDERGROUND STORAGE TANK
- MANHEAD PITS
- 3 [ ] WATER CONTROL VALVES/PIT
- [ ] ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 6" WATER SUPPLY
- J DENOTES LINE DISCONTINUITY
- 3635 BUILDING

(RESULTS IN mg/kg)



1 2 3 4 5 6 7 8 9 10 11 12  
 TO FLIGHTLINE

GRID SCALE: 20 FT PER GRID

FIGURE 4.3

VANG BASE  
 192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

Site 4 - Total Metals, Barium Analytical Results,  
 UST Pit No. 4

ADVANCED SCIENCES, INC.

FILE: RANG49 DATE: 1996



UST CAPACITY:

- UST NO. 1 - 25,000 GAL
- UST NO. 2 - 25,000 GAL
- UST NO. 3 - 25,000 GAL
- UST NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

LEGEND:

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 6" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- UNDERGROUND STORAGE TANK
- MANHOLE PITS
- 3 [Z] WATER CONTROL VALVES/PIT
- [X] ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 6" WATER SUPPLY
- DENOTES LINE DISCONTINUITY
- 3635 BUILDING

(RESULTS IN mg/kg)

GRID SCALE: 20 FT PER GRID.




FIGURE 4.4

Site 4 - Total Metals, Chromium Analytical Results, UST Pit No. 4

ADVANCED SCIENCES, INC.

FILE: RANG50 DATE: 1996

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia



UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

LEGEND:

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 6" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- UNDERGROUND STORAGE TANK
- MANHEAD PITS
- 3 ☒ WATER CONTROL VALVES/PIT
- ☒ ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 6" WATER SUPPLY
- DENOTES LINE DISCONTINUITY
- 3635 BUILDING

(RESULTS IN mg/kg)

GRID SCALE: 20 FT PER GRID;




FIGURE 4.5

Site 4 - Total Metals, Lead Analytical Results,  
 UST Pit No. 4

ADVANCED SCIENCES, INC.

FILE: RANG51

DATE: 1996

VANG BASE

192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia





UST CAPACITY:

UST NO. 1 - 25,000 GAL  
UST NO. 2 - 25,000 GAL  
UST NO. 3 - 25,000 GAL  
UST NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

LEGEND:

--- STORM DRAIN AND SANITARY SEWAGE  
--- WATER  
--- FIRE WATER LINES  
--- ABANDONED 6" AIRCRAFT FUEL LINE  
--- SPRINKLER SUPPLY LINE  
--- 3 UNDERGROUND STORAGE TANK MANHEAD PITS  
--- 3 WATER CONTROL VALVES/PIT  
--- ELECTRIC FOR REMOTE CONTROL  
--- GASOLINE LINE  
--- DRAIN  
--- 6" WATER SUPPLY  
--- DENOTES LINE DISCONTINUITY  
--- 3835 BUILDING  
--- BDL BELOW DETECTION LEVEL

(RESULTS IN  $\mu\text{g}/\text{kg}$ )

GRID SCALE: 20 FT PER GRID




FIGURE 4.6

Site 4 - Methylene Chloride Results,  
UST Pit No. 4

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia

ADVANCED SCIENCES, INC.

FILE: RANG47

DATE: 1996



**TABLE 4.4**  
**SITE 5 – GRO/DRO LABORATORY ANALYTICAL RESULTS FOR**  
**SOIL FROM UST PIT Nos. 1 THROUGH 12**  
**ADVANCED SCIENCES, INC., DECEMBER 1993-FEBRUARY 1994**  
**VIRGINIA AIR NATIONAL GUARD**  
**SANDSTON, VIRGINIA**

<b>UST PIT SAMPLE ID</b>	<b>GRO (1) RESULTS (mg/Kg)</b>	<b>GRO (1) DL (mg/Kg)</b>	<b>DRO (2) RESULTS (mg/Kg)</b>	<b>DRO (2) DL (mg/Kg)</b>
<i>UST No. 1/2/3 PIT</i>				
1. RMD5TP9B1801	<5.0	5.0	<5.0	5.0
2. RMD5TP10C1801	145.0	5.0	230.5	50.0
3. RMD5TP9C2001	9.9	5.0	92.2	50.0
4. RMD5TP8C1801	<5.0	5.0	<5.0	5.0
5. RMD5TP9D1801	<5.0	5.0	<5.0	5.0
6. RMD5AT7C0701	<5.0	5.0	<5.0	5.0
<i>UST No. 4/5/6 PIT</i>				
7. RMD5AT6C0701	<5.0	5.0	<5.0	5.0
8. RMD5TP4B1801	23.7	5.0	32.56	5.0
9. RMD5TP3C1801	BDL	5.0	14.7	5.0
10. RMD5TP4D1801	31.5	5.0	57.5	50.0
11. RMD5TP5C1801	BDL	5.0	5.3	5.0
<i>UST No. 7/8/9 PIT</i>				
12. RMD5TP4F1801	BDL	5.0	64.8	50.0
13. RMD5TP3G1801	BDL	5.0	<5.0	5.0
14. RMD5TP4H1801	<5.0	5.0	<5.0	5.0
15. RMD5TP5G1801	<5.0	5.0	<5.0	5.0
16. RMD5AT6G0701	<5.0	5.0	<5.0	5.0
<i>UST No. 10/11/12 PIT</i>				
17. RMD5AT7G0701	<5.0	5.0	<5.0	5.0
18. RMD5TP9F1801	<5.0	5.0	7.1	5.0
19. RMD5TP10G1801	<5.0	5.0	<5.0	5.0
20. RMD5TP9G2001	<5.0	5.0	33.87	5.0
21. RMD5TP8G1801	<5.0	5.0	<5.0	5.0
22. RMD5TP9H1801	<5.0	5.0	<5.0	5.0

**NOTES:**


BDL = BELOW DETECTION LIMIT

DL = DETECTION LIMIT

mg/Kg = milligrams/Kilogram = parts per million

(1) GRO = GASOLINE RANGE ORGANICS BY EPA METHOD 8015

(2) DRO = DIESEL RANGE ORGANICS BY EPA SW-846 METHOD 8100



- UST CAPACITY:
- UST NO. 1 - 25,000 GAL
  - UST NO. 2 - 25,000 GAL
  - UST NO. 5 - 25,000 GAL
  - UST NO. 6 - 25,000 GAL
  - UST NO. 7 - 25,000 GAL
  - UST NO. 8 - 25,000 GAL
  - UST NO. 11 - 25,000 GAL
  - UST NO. 12 - 25,000 GAL
  - UST NO. 3 - 600 GAL
  - UST NO. 4 - 600 GAL
  - UST NO. 9 - 600 GAL
  - UST NO. 10 - 600 GAL
- LEGEND:  
BDL BELOW DETECTION LEVEL

NOTE:  
SAMPLE LOCATIONS SHOWN WITHOUT RESULTS REPRESENT LOCATIONS WHERE GRO AND DRO CONCENTRATIONS WERE BELOW DETECTION LEVELS

(ALL RESULTS IN mg/kg)  
GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.	FIGURE 4.7		VANG BASE	
	Site 5 - GRO/DRO Analytical Results, UST Pit Nos. 1-12		192nd Tactical Fighter Group Richmond International Airport Sandston, Virginia	
FILE: RANG46	DATE: 1996			

**TABLE 4.5**  
**SITE 5 – GRO/DRO LABORATORY ANALYTICAL RESULTS FOR**  
**SOILS FROM PIPE RUNS, PRESSURE CONTROL PITS,**  
**VALVE PIT, FILL PIT AND AIR SEPARATOR PIT**  
**ADVANCED SCIENCES INC., DECEMBER 1993-FEBRUARY 1994**  
**VIRGINIA AIR NATIONAL GUARD**  
**SANDSTON, VIRGINIA**

<b>PIPE RUN/PIT SAMPLE ID</b>	<b>GRO RESULTS (mg/Kg)</b>	<b>GRO (1) DL (mg/Kg)</b>	<b>DRO RESULTS (mg/Kg)</b>	<b>DRO (2) DL (mg/Kg)</b>
-----------------------------------	------------------------------------	-----------------------------------	------------------------------------	-----------------------------------

**TABLE 4.5**  
**SITE 5 – GRO/DRO LABORATORY ANALYTICAL RESULTS FOR**  
**SOILS FROM PIPE RUNS, PRESSURE CONTROL PITS,**  
**VALVE PIT, FILL PIT AND AIR SEPARATOR PIT**  
**ADVANCED SCIENCES INC., DECEMBER 1993-FEBRUARY 1994**  
**VIRGINIA AIR NATIONAL GUARD**  
**SANDSTON, VIRGINIA**

<b>PIPE RUN/PIT SAMPLE ID</b>	<b>GRO RESULTS (mg/Kg)</b>	<b>GRO (1) DL (mg/Kg)</b>	<b>DRO RESULTS (mg/Kg)</b>	<b>DRO (2) DL (mg/Kg)</b>
-----------------------------------	------------------------------------	-----------------------------------	------------------------------------	-----------------------------------

**PIPE RUNS**

1. RMD5PR6A0601	<5.0	5.0	<5.0	5.0
2. RMD5PR6C0401	BDL	5.0	BDL	5.0
3. RMD5PR6F0401	BDL	5.0	BDL	5.0
4. RMD5PR10E0401	BDL	5.0	BDL	5.0
5. RMD5PR3E0401	BDL	5.0	BDL	5.0
6. RMD5PR1H0601	<5.0	5.0	<5.0	5.0
7. RMD5PR3H0601	<5.0	5.0	<5.0	5.0
8. RMD5PR6H0601	<5.0	5.0	<5.0	5.0
9. RMD5PR8H0601	<5.0	5.0	<5.0	5.0
10. RMD5PR10H0601	<5.0	5.0	<5.0	5.0

**PRESSURE CONTROL PITS**

11. RMD5PC6E0701	BDL	5.0	BDL	5.0
12. RMD5PC830701	BDL	5.0	BDL	5.0

**VALVE PIT**

13. RMD5VP9E0701	BDL	5.0	BDL	5.0
------------------	-----	-----	-----	-----

**FILL PIT**

14. RMD5FP11E0701	BDL	5.0	BDL	5.0
-------------------	-----	-----	-----	-----

**AIR SEPARATOR PIT**

15. RMD5AS6H0701	BDL	5.0	BDL	5.0
------------------	-----	-----	-----	-----

**NOTES:**

DL = DETECTION LIMIT

mg/Kg = milligrams/Kilogram = parts per million

(1) GRO = GASOLINE RANGE ORGANICS BY EPA METHOD 8015

(2) DRO = DIESEL RANGE ORGANICS BY EPA METHOD 8100

## 5.0 QUALITATIVE RISK EVALUATION FOR SITES 4 AND 5

Primary exposure scenarios include exposure of on-site workers to subsurface soil and exposure of downgradient receptors to groundwater. Since the POL facilities are secured, fenced areas with controlled access, worker exposure to localized, contaminated subsurface soil could occur during authorized excavation activities; however, localized subsurface soil contamination was detected at approximate depths of 16-18ft below grade.

Groundwater users who draw water from the shallow depths of the uppermost Yorktown/Columbia Aquifer could potentially be exposed to contaminated groundwater originating from Sites 4 and 5; however, the nearest residential/municipal water supply well in the vicinity of Site 4 that is screened in the Yorktown/Columbia aquifer is located approximately 3000ft upgradient of the Base to the north/northeast. The nearest downgradient residential drinking water supply is 3000ft south of the southern boundary of the Base. With an average groundwater velocity of 16 to 22ft/year across Sites 4 and 5, contaminant transport time to the nearest residential drinking water supply, assuming no retardation, would exceed 180 years. This indicates there is no current threat to downgradient groundwater users.

No critical ecological habitats or rare plant and animal species exist in the immediate vicinity of the Base. The White Oak Swamp Natural Area is located approximately four miles to the southeast of the Base. Assuming groundwater from the Yorktown/Columbia aquifer discharges to the White Oak Swamp Natural Area, groundwater velocity calculations indicate there is no current threat to downgradient groundwater users.

## **6.0 CONCLUSIONS**

### **6.1 SITE 4 - UST NOS. 1, 2, 3, AND 600GAL UST AND RELATED FACILITIES**

Except for Sample No. RMD4TP11C1801 collected from the south wall of the excavation for Tank No. 3 (DRO concentration of 448mg/Kg), combined GRO and DRO concentrations were well below the VADEQ Water Division action level of 100ppm. Since this sample was collected approximately 16-18ft below grade, this localized petroleum contamination does not appear to pose significant human health or ecological risks.

### **6.2 SITE 4 - UST NO. 4 AND RELATED FACILITIES**

Methylene chloride was the only VOC detected in the samples collected from the excavation associated with Tank No. 4. Methylene chloride was detected in three samples at concentrations ranging from 5.1µg/Kg to 10.2µg/Kg. The maximum concentration detected was approximately two times greater than the analytical limit of quantitation of 5.0µg/Kg. All samples from this excavation were collected approximately 16-18ft below grade, indicating these levels of contamination do not appear to pose significant human health or ecological risks. Please be aware that closure activities associated with Tank No. 4 were not conducted in exactly the same sequence specified in the typical closure schedule contained in the approved closure plan (ASI 1996).

### **6.3 SITE 5 - USTS AND REPLACED FACILITIES**

Except for Sample Nos. RMD5TP9C2001 (GRO/DRO concentration of 102.1 mg/Kg) and RMD5TP10C1801 (GRO/DRO concentration of 375.5 mg/Kg) collected from the excavation associated with Tank Nos. 1 and 2, combined GRO and DRO concentrations were below the VADEQ action level of 100ppm. Since these samples were collected approximately 16-18ft below grade, this localized petroleum contamination does not appear to pose significant human health or ecological risks.

### **6.4 RECOMMENDATIONS - SITES 4 AND 5**

Based on minimal human health and ecological risks associated with soil and groundwater contamination detected during UST closure activities and previous site investigations, the VANG requests clean closure of Sites 4 and 5 with the following condition:

- If future excavation activities are authorized at Sites 4 and 5, appropriate health and safety procedures will be implemented to protect workers from localized contamination.

## 7.0 REFERENCES

ASI (Advanced Sciences, Inc.) May 1991. "Supplemental Site Characterization Report, Virginia Air National Guard, Richmond International Airport, Sandston, Virginia," prepared for the National Guard Bureau NGB/CEVR, Andrews AFB, MD.

ASI (Advanced Sciences, Inc.) December 1991. "Site Assessment Report, Site 4 - Petroleum, Oils, and Lubricants Facility, Virginia Air National Guard, Richmond International Airport, Sandston, Virginia," prepared for the National Guard Bureau ANGRC/CEVR, Andrews AFB, MD.

ASI (Advanced Sciences, Inc.) September 1992. "Site Assessment Report, Site 5 - Petroleum, Oils, and Lubricants Facility, Virginia Air National Guard, Richmond International Airport, Sandston, Virginia," prepared for the National Guard Bureau ANGRC/CEVR, Andrews AFB, MD.

ASI (Advanced Sciences, Inc.) April 1996. "Closure Plan for Tank No. 4 at Site 4 - Petroleum, Oils, and Lubricants Facility, Virginia Air National Guard, Richmond International Airport, Sandston, Virginia," prepared for the National Guard Bureau ANGRC/CEVR, Andrews AFB, MD.

Clay, John W. 1975. "Soil Survey of Henrico County, Virginia," United States Department of Agriculture, Soil Conservation Service, and Virginia Polytechnic Institute.

Commonwealth of Virginia/Department of Waste Management, Hazardous Waste Management Regulation, VR 672-10-1, dated January 4, 1993.

Commonwealth of Virginia State Water Control Board, Underground Storage Tanks; Technical Standards and Corrective Action Requirements, VR 680-13-02, Adopted: August 1, 1989 - Effective: October 25, 1989.

Metcalf & Eddy, Inc., February 1991. "Site 4 Site Characterization, Virginia Air National Guard, Richmond International Airport, Sandston, Virginia," prepared for the National Guard Bureau NGB/CEVR, Andrews AFB, MD.

Metcalf & Eddy, Inc., January 1991. "Sampling Approach, Analytical Results, and Disposal Options for the Contents of Three Underground Storage Tanks at Site 4, Virginia Air National

Guard, Byrd Field, Sandstone, Virginia," prepared for the National Guard Bureau, Andrews AFB, MD.

Metcalf & Eddy, Inc., 1995. Final Site Investigation Report.

**SELECTED PHOTOGRAPHS OF SITE 4  
CLOSURE ACTIVITIES**

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	1	94/01/14	5	23	22	REFUELING OPERATIONS IN ACTIVE PORTION OF POL; VIEW TO THE NE.
4	1	94/01/14	5	22	21	EXCAVATION OF UST No. 2; VIEW TO THE SW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.





# UST CAPACITY:


UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

## LEGEND:

--- STORM DRAIN AND SANITARY SEWAGE  
 --- WATER  
 --- FIRE WATER LINES  
 --- ABANDONED 6" AIRCRAFT FUEL LINE  
 --- SPRINKLER SUPPLY LINE  
 3 UNDERGROUND STORAGE TANK MANHEAD PITS  
 [Hatched Box] WATER CONTROL VALVES/PIT  
 [Diamond] ELECTRIC FOR REMOTE CONTROL  
 --- GASOLINE LINE  
 --- DRAIN  
 --- 6" WATER SUPPLY  
 J DENOTES LINE DISCONTINUITY  
 3635 BUILDING

DIRECTION OF  
 PICTURE AND ROLL  
 RL1  
 F5



TO FLIGHTLINE

GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.

FILE: RANG65

DATE: 1994

SITE 4 - Photo Log No. 1

Photo Grid Location/Orientation  
 ,  
 January 14, 1994

VANG BASE

192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	2	94/01/25	5	19	18	VIEW INTO PIT AROUND CONCRETE MANWAY FOR UST No. 2;
4	2	94/01/25	5	18	17	UST No. 2 REMOVAL; VIEW TO THE NW.
4	2	94/01/25	5	17	16	UST No. 2 REMOVAL; VIEW TO THE WEST.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



# UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

## LEGEND:


--- STORM DRAIN AND SANITARY SEWAGE  
 --- WATER  
 --- FIRE WATER LINES  
 --- ABANDONED 6" AIRCRAFT FUEL LINE  
 --- SPRINKLER SUPPLY LINE  
 --- UNDERGROUND STORAGE TANK  
 --- MANHEAD PITS  
 --- WATER CONTROL VALVES/PIT  
 --- ELECTRIC FOR REMOTE CONTROL  
 --- GASOLINE LINE  
 --- DRAIN  
 --- 6" WATER SUPPLY  
 --- DENOTES LINE DISCONTINUITY  
 --- BUILDING  
 3635

DIRECTION OF  
 PICTURE AND ROLL  
 AND FRAME NUMBER  
 RL1  
 F5

## NOTE:

RL5.F19 IS A PHOTO LOOKING  
 DOWN AT RECENTLY REPAIRED  
 WATER MAIN

GRID SCALE: 20 FT PER GRID



ADVANCED SCIENCES, INC.

FILE: RANG66

DATE: 1994

SITE 4 - Photo Log No. 2

Photo Grid Location/Orientation  
 January 25, 1994

VANG BASE

192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	3	94/01/26	5	16	15	EXCAVATION OF UST No. 2; VIEW TO THE SW.
4	3	94/01/26	5	15	14	EXCAVATION OF UST No. 2; VIEW TO THE NW.
4	3	94/01/26	5	14	13	EXCAVATION OF UST No. 3; VIEW TO THE NW.
4	3	94/01/26	5	13	12	EXCAVATION OF UST No. 3; VIEW TO THE SE.
4	3	94/01/26	5	12	11	EXCAVATION OF UST No. 3; VIEW TO THE SE.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



# UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

## LEGEND:


--- STORM DRAIN AND SANITARY SEWAGE  
 --- WATER  
 --- FIRE WATER LINES  
 --- ABANDONED 6" AIRCRAFT FUEL LINE  
 --- SPRINKLER SUPPLY LINE  
 3 UNDERGROUND STORAGE TANK MANHEAD PITS  
 [Hatched Box] WATER CONTROL VALVES/PIT  
 [Diamond] ELECTRIC FOR REMOTE CONTROL  
 --- GASOLINE LINE  
 --- DRAIN  
 [Line with Arrow] 6" WATER SUPPLY  
 [Line with Arrow] DENOTES LINE DISCONTINUITY  
 [Box] 3635 BUILDING

↑ DIRECTION OF  
 PICTURE AND ROLL  
 RL1 AND FRAME NUMBER  
 F5

## NOTE:

RL5.F16 SHOWS EXCAVATOR  
 MANEUVERING IN SOFT SOIL

GRID SCALE: 20 FT PER GRID



ADVANCED SCIENCES, INC.

FILE: RANG67

DATE: 1994

SITE 4 - Photo Log No. 3

Photo Grid Location/Orientation  
 January 26, 1994

VANG BASE

192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
 UST REMOVAL  
 VIRGINIA AIR NATIONAL GUARD  
 SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	4	94/01/27	5	10	9	UST No. 2 REMOVAL; VIEW TO THE SW.

NOTE:  
 PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 NO. 2 - 25,000 GAL  
 NO. 3 - 25,000 GAL  
 NO. 4 - 25,000 GAL


AQUATRAP - 600 GAL

**LEGEND:**

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ARMORED 6" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- 3 UNDERGROUND STORAGE TANK
- MANHEAD PITS
- WATER CONTROL VALVES/PIT
- ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 6" WATER SUPPLY
- DENOTES LINE DISCONTINUITY
- 3635 BUILDING

DIRECTION OF  
 PICTURE AND ROLL  
 AND FRAME NUMBER  
 RL1  
 F5

GRID SCALE: 20 FT PER GRID



ADVANCED SCIENCES, INC.

FILE: RANG68

DATE: 1994

SITE 4 - Photo Log No. 4

Photo Grid Location/Orientation  
 January 27, 1994

VANG BASE

192nd Tactical Fighter Group  
 Richmond International Airport

Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
 UST REMOVAL  
 VIRGINIA AIR NATIONAL GUARD  
 SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	5	94/01/28	5	7	6	UST No. 3 IN TEMPORARY STORAGE AREA. VIEW OF THE SW.
4	5	94/01/28	5	6	5	UST Nos. 1 & 2 IN TEMPORARY STORAGE AREA. VIEW TO THE WEST.

NOTE:  
 PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.





# UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 UST NO. 2 - 25,000 GAL  
 UST NO. 3 - 25,000 GAL  
 UST NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

## LEGEND:


- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 6" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- 3 UNDERGROUND STORAGE TANK MANHEAD PHS
- WATER CONTROL VALVES/PIT
- ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 6" WATER SUPPLY
- J DENOTES LINE DISCONTINUITY
- 3635 BUILDING

DIRECTION OF  
 PICTURE AND ROLL  
 RL1 AND FRAME NUMBER  
 F5

## NOTES:

1. RL5,F6-TANK NO. 2 (LEFT)  
 TANK NO. 1 (RIGHT)
2. RL5,F7-LOOKING AT REMOVED  
 TANK NO. 3

GRID SCALE: 20 FT PER GRID



ADVANCED SCIENCES, INC.

FILE: RANG69

DATE: 1994

SITE 4 - Photo Log No. 5

Photo Grid Location/Orientation  
 January 28, 1994

VANG BASE

192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	6	94/01/29	5	5	4	UST No. 4 REMOVAL, DELIVERY OF ROLL-OFF CONTAINERS FOR EXCAVATED SOIL VIEW TO THE NW
4	6	94/01/29	5	4	3	UST No. 4 REMOVAL, PLASTIC LINED ROLL-OFF CONTAINERS PRIOR TO LOADING WITH SOIL; VIEW TO THE NW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



UST CAPACITY:

UST NO. 1 - 25,000 GAL  
NO. 2 - 25,000 GAL  
NO. 3 - 25,000 GAL  
NO. 4 - 25,000 GAL


AQUATRAP - 600 GAL

LEGEND:

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 6" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- UNDERGROUND STORAGE TANK
- MANHEAD PITS
- WATER CONTROL VALVES/PIT
- ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 6" WATER SUPPLY
- J. DENOTES LINE DISCONTINUITY
- 3635 BUILDING

DIRECTION OF  
PICTURE AND ROLL  
AND FRAME NUMBER  
RL1  
F5

GRID SCALE: 20 FT PER GRID



ADVANCED SCIENCES, INC.

FILE: RANG70

DATE: 1994

SITE 4 - Photo Log No. 6

Photo Grid Location/Orientation  
January 29, 1994

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	7	94/02/09	6	1	2	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NW.
4	7	94/02/09	6	2	3	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NW.
4	7	94/02/09	6	3	4	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NW.
4	7	94/02/09	6	4	5	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE SW.
4	7	94/02/09	6	5	6	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.
4	7	94/02/09	6	6	7	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NE.
4	7	94/02/09	6	7	8	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NW.
4	7	94/02/09	6	8	9	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NW.
4	7	94/02/09	6	9	10	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	7	94/02/09	6	10	11	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NW.
4	7	94/02/09	6	11	12	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE NE.
4	7	94/02/09	6	12	13	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE SW.
4	7	94/02/09	6	13	14	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE SW.
4	7	94/02/09	6	14	15	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE SW.
4	7	94/02/09	6	15	16	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.
4	7	94/02/09	6	16	17	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.
4	7	94/02/09	6	17	18	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE SW.
4	7	94/02/09	6	18	19	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
4	7	94/02/09	6	19	20	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.
4	7	94/02/09	6	20	21	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.
4	7	94/02/09	6	21	22	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.
4	7	94/02/09	6	22	23	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.
4	7	94/02/09	6	23	24	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE S.
4	7	94/02/09	6	24	END	UST No. 4 REMOVAL OPERATIONS; VIEW TO THE SW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



UST CAPACITY:

UST NO. 1 - 25,000 GAL  
UST NO. 2 - 25,000 GAL  
UST NO. 3 - 25,000 GAL  
UST NO. 4 - 25,000 GAL

AQUATRAP - 600 GAL

LEGEND:

- STORM DRAIN AND SANITARY SEWAGE
- WATER
- FIRE WATER LINES
- ABANDONED 6" AIRCRAFT FUEL LINE
- SPRINKLER SUPPLY LINE
- UNDERGROUND STORAGE TANK
- MANHOLE PITS
- WATER CONTROL VALVES/PI
- ELECTRIC FOR REMOTE CONTROL
- GASOLINE LINE
- DRAIN
- 6" WATER SUPPLY
- DENOTES LINE DISCONTINUITY
- BUILDING

DIRECTION OF  
PICTURE AND ROLL  
RL1  
F5

GRID SCALE: 20 FT PER GRID

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia


SITE 4 - Photo Log No. 7

Photo Grid Location/Orientation  
February 9, 1994

ADVANCED SCIENCES, INC.

FILE: RANG71

DATE: 1994





Site 4 - UST No. 2 Removal. View to the Northwest.  
(Photo Log No. 2; Roll No. 5/Frame No. 18)



Site 4 - UST No. 2 Removal. View to the West.  
(Photo Log No. 2; Roll No. 5/Frame No. 17)





Site 4 - UST No. 1 & UST No. 2. View to the West.  
(Photo Log No. 5; Roll No. 5/Frame No. 6)



Site 4 - UST No. 3. View to the Southwest.  
(Photo Log No. 5; Roll No. 5/Frame No. 7)



Site 4 - UST No. 4 Removal. View to the North.  
(Photo Log No. 7; Roll No. 6/Frame No. 1)



Site 4 - UST No. 4 Removal. View to the North.  
(Photo Log No. 7; Roll No. 6/Frame No. 3)



Site 4 - UST No. 4 Removal. Delivery of Roll-off Containers  
for Excavated Soil. View to the Northwest.  
(Photo Log No. 6; Roll No. 5/Frame No. 5)



Site 4 - UST No. 4 Removal. Plastic Lined Roll-off Containers  
Prior to Loading with Soil. View to the Northwest.  
(Photo Log No. 6; Roll No. 5/Frame No. 4)



Site 4 - UST No. 4 Removal. View to the South.  
(Photo Log No. 7; Roll No. 6/Frame No. 20)



Site 4 - UST No. 4 Removal. View to the South.  
(Photo Log No. 7; Roll No. 6/Frame No. 23)

**MSDS FOR TANK CLEANING FLUID**



\*\*\*MATERIAL SAFETY DATA SHEET\*\*\*

MANUFACTURER----- BULTJE SALES AND SERVICE, INC.  
Route 2 Box 141  
Liberty, S.C. 29657  
(803) 843-6278

MSDS PREPARED BY----- Winifred G. Palmer, Ph.D.  
Biomedical Toxicology Associates  
P.O. Box 3568  
Frederick, MD 21701

PREPARATION DATE----- May 4, 1988

PRODUCT NAME----- SUPER CLEAN

PRODUCT DESCRIPTION----- An alkaline mixture containing detergents, phosphates,  
butoxyethanol and water.

.. SECTION I - HAZARDOUS INGREDIENTS . . . . .

<u>Ingredients</u>	<u>ACGIH TLV</u>	<u>OSHA PEL</u>	<u>CAS NUMBER</u>
2-Butoxyethanol	25 ppm (skin)	50 ppm (skin)	111-76-2
Sodium hydroxide	2 mg/m <sup>3</sup> (ceiling)	2 mg/m <sup>3</sup>	1310-73-2

. SECTION II - PHYSICAL DATA . . . . .

pH-----	12.5 to 13	BOILING POINT-----	N/D
VAPOR PRESSURE-----	N/D	MELTING POINT-----	N/A
SOLUBILITY IN WATER-----	Complete	EVAP. RATE (Ether = 1)---	< 1
APPEARANCE AND ODOR-----	Clear purple liquid with mild odor.		

. SECTION III - FIRE AND EXPLOSION HAZARD DATA . . . . .

FLASH POINT----- None

FLAMMABLE LIMITS----- LFL--- N/A UFL--- N/A

EXTINGUISHING MEDIA----- This material is not flammable. Use extinguishers  
suitable for surrounding fire, e.g., water fog, CO<sub>2</sub>,  
dry chemical, foam.

SPECIAL FIRE FIGHTING PROCEDURES--- Fire fighters should wear full protective  
clothing and self-contained breathing apparatus.

UNUSUAL FIRE AND EXPLOSION HAZARDS--- None known

. SECTION IV - REACTIVITY DATA . . . . .

STABILITY----- Stable at ambient temperatures and pressures

CONDITIONS TO AVOID----- None known

INCOMPATIBILITY (Materials to avoid)--- Strong oxidizing agents.

HAZARDOUS DECOMPOSITION PRODUCTS--- Thermal-oxidative degradation products include  
carbon monoxide and carbon dioxide.

HAZARDOUS POLYMERIZATION-- Will not occur

. SECTION V - HEALTH HAZARD DATA . . . . .

ROUTE(S) OF ENTRY----- Inhalation, ingestion, skin and eye contact

N/D = Not determined

N/A = Not Applicable

## SUPER CLEAN

### HEALTH HAZARDS (ACUTE)

EYES-----

Contact can cause severe irritation and, with greater exposures, burns with possible blindness.

SKIN-----

Contact can irritate the skin. Prolonged contact can cause severe skin irritation or burns.

INHALATION-----

Exposure to mists can cause irritation and damage to mucous membranes and the respiratory passages.

INGESTION-----

Pneumonitis may occur.

SKIN ABSORPTION-----

Can cause irritation and burns of the digestive tract. Butoxyethanol is readily absorbed through the skin and may cause systemic effects such as headache, dizziness and nausea.

HEALTH HAZARDS (CHRONIC)--- Frequent and prolonged inhalation may cause lung damage.

CARCINOGENICITY: NTP?--- No IARC Monographs?--- No OSHA Regulated?--- No  
Components of this product are not known to cause cancer.

MEDICAL CONDITIONS GENERALLY AGGRAVATED BY EXPOSURE--- Persons with impaired pulmonary function may be at increased risk from exposure.

## SECTION VI - EMERGENCY AND FIRST AID PROCEDURES . . . . .

EYE CONTACT--- Immediately rinse with large amounts of water for at least 15 minutes, occasionally lifting upper and lower lids. Obtain medical attention immediately.

SKIN CONTACT--- Remove contaminated clothing. Immediately flush contaminated skin with large quantities of water. Obtain medical attention if irritation persists. Launder contaminated clothing before re-use.

INHALATION--- Remove to fresh air. If breathing is difficult, administer oxygen. If breathing has stopped, give artificial respiration. Keep person warm and quiet. Obtain medical attention immediately.

INGESTION--- Obtain medical attention immediately. Do not induce vomiting.

## SECTION VII - PRECAUTIONS FOR SAFE HANDLING AND USE . . . . .

STEPS TO BE TAKEN IN CASE MATERIAL IS RELEASED OR SPILLED--- Absorb with sand, vermiculite, or other suitable inert absorbent. Transfer to secure containers for proper disposal. Do not flush to sewer.

WASTE DISPOSAL METHOD--- Neutralize with dilute acid. Landfill wastes at approved sites. Dispose in accordance with Federal, State, and Local regulations.

PRECAUTIONS TO BE TAKEN IN HANDLING AND STORAGE--- Use with adequate ventilation; do not inhale mist or spray. Avoid contact with eyes, skin and clothing. Wash thoroughly after handling. Do not smoke or eat when working with this material.

## SECTION VIII - CONTROL MEASURES . . . . .

RESPIRATORY PROTECTION--- NIOSH/MSHA approved respirator is necessary if TLV is exceeded or if mists or sprays are generated which are not fully controlled by ventilation.

VENTILATION--- Provide sufficient ventilation (general and/or local exhaust) to maintain exposure below the TLV.

PROTECTIVE GLOVES--- Required

EYE PROTECTION--- Safety glasses with side shields or chemical safety goggles

SKIN PROTECTION--- Chemical resistant apron. Impervious clothing.

OTHER PROTECTIVE CLOTHING OR EQUIPMENT--- Safety shower and eye wash station.

.....  
This information is provided as a customer service and to the best of our knowledge is current and accurate. It is the user's obligation to determine the conditions of use of the product.

**ANALYTICAL RESULTS OF TANK NO. 4 CONTENTS**



SOLUTIONS LABORATORIES, INC.

214-B GREENBRIER CIRCLE  
CHESAPEAKE, VA 23320  
(T) (804) 420-0467  
(F) (804) 420-4204

REPORT OF ANALYSIS

DATE: JANUARY 14, 1994

RICHMOND ENVIRONMENTAL  
1643-A MERRIMAC TRAIL  
WILLIAMSBURG, VA 23185  
ATTN: JOHN KARAFIA  
PHONE #: 1-220-1607  
FAX #: 1-229-4683

PROJECT NAME: TANK REMOVAL  
PROJECT NUMBER: VA ANG BASE-SANDSTON, VA

SOLUTIONS LOG: 01101994-002-01  
MATRIX: LIQUID  
DATE/TIME SAMPLED: 01/10/94; 1130

<u>SOL LOG #</u>	<u>FIELD ID</u>	<u>ANALYSIS</u>	<u>RESULTS</u>	<u>UNITS</u>	<u>D.F.</u>	<u>DET LT.</u>	<u>METHOD/DATE/TIME/ANALYST</u>
01A1 (A)	RE4-2	TPH 418.1	207	mg/L	2.5	5.45	418.1/01-13-94/1300/LP
01A1 (A)	RE4-2	TOX	1.28	mg/L	5	0.5	9020/01-13-94/1000/LP
01A1 (HA)	RE4-2	TPH 418.1	102100	mg/L	1040	2270	418.1/01-13-94/1300/LP
01A1 (HA)	RE4-2	TOX	11.8	mg/L	5	0.5	9020/01-13-94/1000/LP

SOLUTIONS LABORATORIES, INC.

B14-B GREENBRIER CIRCLE  
CHESAPEAKE, VA 23320  
(T) (804) 420-0467  
(F) (804) 420-4204

REPORT OF ANALYSIS

DATE: JANUARY 14, 1994

RICHMOND ENVIRONMENTAL  
1643-A MERRIMAC TRAIL  
WILLIAMSBURG, VA 23185  
ATTN: JOHN KARAFI  
PHONE #: 1-220-1607  
FAX #: 1-229-4683

PROJECT NAME: TANK REMOVAL  
PROJECT NUMBER: VA ANG BASE-SANDSTON, VA

SOLUTIONS LOG: 01101994-002-01  
MATRIX: LIQUID  
DATE/TIME SAMPLED: 01/10/94; 1130

METHOD 8080-PCB

CLIENT NO:	RE4-2 (A)	RE4-2 (NA)	MDL*
LAB NO:	01A1	01A1	N/A
SAMPLE DATE:	01/10/94	01/10/94	N/A
RECEIVED DATE:	01/10/94	01/10/94	N/A
EXTRACTION DATE:	01/12/94	01/12/94	N/A
ANALYSIS DATE:	01/13/94	01/13/94	N/A
INSTRUMENT ID:	HP ECD	HP ECD	HP ECD
DILUTION FACTOR:	0.02	20	1
UNITS:	mg/L	mg/Kg	mg/L

COMPOUNDS

ALL AROCLORS	< 0.02	< 10	7.5
--------------	--------	------	-----

\*MDL IS THE METHOD DETECTION LIMIT. THE MDL IS USED TO DETERMINE THE PRACTICAL QUANTITATIVE LIMIT FOR EACH MATRIX TYPE. THE MATRIX FACTOR IS TABLED ON PAGE 8080-3 OF SW-846.

REVIEWED BY:

*Dorothy S. Small, Jr.*  
DOROTHY S. SMALL

SOLUTIONS LABORATORIES, INC.

114-B GREENBRIER CIRCLE  
CHESAPEAKE, VA 23320  
(T) (804) 420-0467  
(F) (804) 420-4204

REPORT OF ANALYSIS

DATE: JANUARY 13, 1994

RICKMOND ENVIRONMENTAL  
1643-A MERRIMAC TRAIL  
WILLIAMSBURG, VA 23185

ATTN: JOHN KARAFI  
PHONE #: 1-220-1607  
FAX #: 1-229-4683

PROJECT NAME: UST REMOVAL  
PROJECT NUMBER: VA ANG BASE-SANDSTON, VA

SOLUTIONS LOG: 01071994-005-01  
MATRIX: LIQUID  
DATE/TIME SAMPLED: 01/07/94; 1600

SOL LOC #	FIELD ID	ANALYSIS	RESULTS	UNITS	D.F.	DET LT.	METHOD/DATE/TIME/ANALYST
01A1 (A)	RE43-1	TCLP ARSENIC	0.276	mg/L	10	0.002	1311/7060/01-13-94/1000/ LP
01A1 (A)	RE43-1	TCLP BARIUM	<1.50	mg/L	10	0.150	1311/7080/01-13-94/1100/ LP
01A1 (A)	RE43-1	TCLP CADMIUM	7.1	mg/L	10	0.010	1311/7130/01-12-94/1730/DMF
01A1 (A)	RE43-1	TCLP CHROMIUM	12.5	mg/L	10	0.033	1311/7190/01-12-94/1800/DMF
01A1 (A)	RE43-1	TCLP LEAD	64.4	mg/L	10	0.099	1311/7420/01-12-94/1700/DMF
01A1 (A)	RE43-1	TCLP MERCURY	0.0125	mg/L	1	0.0002	1311/7470/01-13-94/1700/MRG
01A1 (A)	RE43-1	TCLP SELENIUM	5.41	mg/L	10	0.002	1311/7740/01-13-94/0900/ LP
01A1 (A)	RE43-1	TCLP SILVER	0.50	mg/L	1	0.016	1311/7760/01-12-94/1830/DMF
01A1 (A)	RE43-1	REACTIVITY	NEG.	N/A	N/A	N/A	SW846.CH7.3/01-10-94/2300/ LP
01A1 (A)	RE43-1	IGNITABILITY	>100oC	N/A	N/A	N/A	SW846.CH7.7.1/01-10-94/1710/MRG
01A1 (A)	RE43-1	CORROSIVITY	3.22	N/A	N/A	N/A	S2846.1110/01-10-94/1700/MRG
01A1 (NA)	RE43-1	TCLP ARSENIC	3.67	mg/L	10	0.002	1311/7060/01-13-94/1000/ LP
01A1 (NA)	RE43-1	TCLP BARIUM	15.0	mg/L	10	0.150	1311/7080/01-13-94/1100/ LP
01A1 (NA)	RE43-1	TCLP CADMIUM	0.93	mg/L	10	0.010	1311/7130/01-12-94/1730/DMF
01A1 (NA)	RE43-1	TCLP CHROMIUM	8.00	mg/L	10	0.033	1311/7190/01-12-94/1800/DMF
01A1 (NA)	RE43-1	TCLP LEAD	24.0	mg/L	10	0.099	1311/7420/01-12-94/1700/DMF
01A1 (NA)	RE43-1	TCLP MERCURY	0.0075	mg/L	10	0.0002	1311/7470/01-13-94/1700/MRG
01A1 (NA)	RE43-1	TCLP SELENIUM	4.73	mg/L	10	0.002	1311/7740/01-13-94/0900/ LP
01A1 (NA)	RE43-1	TCLP SILVER	2.42	mg/L	10	0.016	1311/7760/01-12-94/1830/DMF
01A1 (NA)	RE43-1	REACTIVITY	NEG	N/A	N/A	N/A	SW846.CH7.3/01-10-94/2300/ LP
01A1 (NA)	RE43-1	IGNITABILITY	<100oC	N/A	N/A	N/A	SW846.CH7.7.1/01-10-94/1710/MRG
01A1 (NA)	RE43-1	CORROSIVITY	3.37	N/A	N/A	N/A	S2846.1110/01-10-94/1715/MRG

# SOLUTIONS LABORATORIES, INC.

814-B GREENBRIER CIRCLE  
CHESAPEAKE, VA 23320  
(T) (804) 420-0467  
(F) (804) 420-4204

## REPORT OF ANALYSIS

DATE: JANUARY 13, 1994

RICHMOND ENVIRONMENTAL  
1643-A MERRIMAC TRAIL  
WILLIAMSBURG, VA 23185  
ATTN: JOHN KARAFI  
PHONE #: 1-220-1607  
FAX #: 1-229-4683

PROJECT NAME: UST REMOVAL  
PROJECT NUMBER: VA ANG BASE-SANDSTON, VA

SOLUTIONS LOG: 01071994-005-01  
MATRIX: LIQUID  
DATE/TIME SAMPLED: 01/07/94; 1600

### METHOD 8240

CLIENT NO:	RE43-1	RE43-1	MDL*
LAB NO:	01A1 (A)	01A1 (NA)	N/A
SAMPLE DATE:	01/07/94	01/07/94	N/A
RECEIVED DATE:	01/07/94	01/07/94	N/A
EXTRACTION DATE:	N/A	N/A	N/A
ANALYSIS DATE:	01/12/94	01/13/94	N/A
INSTRUMENT ID:	MS	MS	MS
DILUTION FACTOR:	1	1	1
UNITS:	ug/L	ug/Kg	ug/L

### COMPOUNDS

ACETONE	220000	<500	500
BENZENE	6300	47000	250
BROMODICHLOROMETHANE	<250	<250	250
BROMOFORM	<250	<250	250
BROMOMETHANE	<250	<250	250
2-BUTANONE	18000	<250	250
CARBON DISULFIDE	<250	<12500	12500
CARBON TETRACHLORIDE	<250	<250	250
CHLOROBENZENE	<250	<250	250
CHLOROETHANE	<250	<250	250
2-CHLOROETHYL VINYLETHYL	<250	<250	250
CHLOROFORM	<250	<250	250
CHLOROMETHANE	<250	<250	250
DIBROMOCHLOROMETHANE	<250	<250	250
1,2-DICHLOROETHANE	<250	<250	250
1,1-DICHLOROETHANE	<250	<250	250
1,1-DICHLOROETHENE	<250	<250	250
TRANS-1,2-DICHLOROETHENE	<250	<250	250
1,2-DICHLOROPROPANE	<250	<250	250
TRANS-1,3-DICHLOROPROPENE	<250	<250	250
CIS-1,3-DICHLOROPROPENE	<250	<250	250
ETHYLBENZENE	4000	<250	250
2-HEXANONE	<250	150000	250
4-METHYL-2-PENTANONE	<250	<250	250
METHYLENE CHLORIDE	<250	<250	6250
STYRENE	<250	<250	250
1,1,2,2-TETRACHLOROETHANE	<250	<250	250
TETRACHLOROETHENE	<250	<250	250
TOLUENE	14000	<250	250
1,1,1-TRICHLOROETHANE	<250	440000	500
1,1,2-TRICHLOROETHANE	<250	<250	250
TRICHLOROETHENE	490	<250	250
VINYL ACETATE	<6250	21000	250
VINYL CHLORIDE	<250	<6250	6250
XYLENE (TOTAL)	19000	<250	250
		730000	250

314-B GREENBRIER CIRCLE  
CHESAPEAKE, VA 23330  
(T) (804) 420-0467  
(F) (804) 420-4204

REPORT OF ANALYSIS

DATE: JANUARY 13, 1994

RICKMOND ENVIRONMENTAL  
1643-A MERRIMAC TRAIL  
WILLIAMSBURG, VA 23185  
ATTN: JOHN KARAFI  
PHONE #: 1-220-1607  
FAX #: 1-229-4683

PROJECT NAME: UST REMOVAL  
PROJECT NUMBER: VA ANG BASE-SANDSTON, VA

SOLUTIONS LOG: 01071994-005-01  
MATRIX: LIQUID  
DATE/TIME SAMPLED: 01/07/94; 1600

METHOD BTEX 8020

CLIENT NO:	RE43-1	RE43-1	MDL*
LAB NO:	01A1 (A)	01A1 (NA)	N/A
SAMPLE DATE:	01/07/94	01/07/94	N/A
RECEIVED DATE:	01/07/94	01/07/94	N/A
EXTRACTION DATE:	N/A	N/A	N/A
ANALYSIS DATE:	01/12/94	01/12/94	N/A
INSTRUMENT ID:	HP/P&T	HP/P&T	HP/P&T
DILUTION FACTOR:	2000	500000	1
UNITS:	mg/L	mg/L	mg/L

COMPOUNDS

BENZENE	5.77	1480	0.2
TOLUENE	15.2	11400	0.2
ETHYL BENZENE	1.40	4390	0.2
TOTAL XYLENES	8.51	21600	0.4

\*MDL IS THE METHOD DETECTION LIMIT.

REVIEWED BY:


*Dorothy S. Small*  
DOROTHY S. SMALL

**SELECTED PHOTOGRAPHS OF SITE 5  
CLOSURE ACTIVITIES**

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME		SUBJECT/DESCRIPTION
				No.	Negative No.	
5	1	93/12/14	1	1	22A	UST No. 5/6 CONCRETE MANWAY; BEFORE/DURING GRUBBING; VIEW TO THE NE.
5	1	93/12/14	1	2	3/3A	UST No. 4 CONCRETE MANWAY; BEFORE/DURING GRUBBING; VIEW TO THE NE.
5	1	93/12/14	1	3	4/4A	UST No. 3 CONCRETE MANWAY; BEFORE/DURING GRUBBING; VIEW TO THE NE.
5	1	93/12/14	1	4	5/5A	UST No. 1/2 CONCRETE MANWAY; BEFORE/DURING GRUBBING; VIEW TO THE NE.
5	1	93/12/14	1	5	6/6A	UST No. 1/2 CONCRETE MANWAY; BEFORE/DURING GRUBBING; VIEW TO THE NW.
5	1	93/12/14	1	6	7/7A	CONCRETE VALVE PIT/PRESSURE CONTROL PIT; BEFORE/DURING GRUBBING; VIEW TO THE NW.
5	1	93/12/14	1	7	8/8A	CONCRETE FILL PIT; BEFORE/DURING GRUBBING; VIEW TO THE SE.
5	1	93/12/14	1	8	9/9A	UST No. 11/12 CONCRETE MANWAY; BEFORE/DURING GRUBBING; VIEW TO THE NW.
5	1	93/12/14	1	9	10/10A	UST No. 11/12 CONCRETE MANWAY; BEFORE/DURING GRUBBING; VIEW TO THE SW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .



UST CAPACITY:

- UST NO. 1 - 25,000 GAL
- UST NO. 2 - 25,000 GAL
- UST NO. 5 - 25,000 GAL
- UST NO. 6 - 25,000 GAL
- UST NO. 7 - 25,000 GAL
- UST NO. 8 - 25,000 GAL
- UST NO. 11 - 25,000 GAL
- UST NO. 12 - 25,000 GAL
- UST NO. 3 - 600 GAL
- UST NO. 4 - 600 GAL
- UST NO. 9 - 600 GAL
- UST NO. 10 - 600 GAL

LEGEND:

DIRECTION OF  
PICTURE AND ROLL  
AND FRAME NUMBER  
RL1  
F5

GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.

FILE: RANG53 DATE: 1994

SITE 5 - Photo Log No. 1  
Photo Grid Location/Orientation  
December 14, 1993

VANG BASE  
192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia



PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE PHOTO LOG No. DATE ROLL No. FRAME No. NEGATIVE No. SUBJECT/DESCRIPTION

5 2 93/12/16 1 19 20/20A UST No. 5/6 CONCRETE MANWAY; AFTER GRUBBING; COMPARE w/PL 1, R1/F1; VIEW TO THE NE.

5 2 93/12/16 1 20 21/21A UST No. 3 CONCRETE MANWAY; AFTER GRUBBING; COMPARE w/PL 1, R1/F3; VIEW TO THE NE.

5 2 93/12/16 1 21 22/22A UST No. 1/2 CONCRETE MANWAY; AFTER GRUBBING; COMPARE w/PL 1, R1/F5; VIEW TO THE NW.

5 2 93/12/16 1 22 23/23A CONCRETE VALVE PIT/PRESSURE CONTROL PIT; COMPARE w/PL 1, R1/F6; VIEW TO THE NW.

5 2 93/12/16 1 23 24/24A UST No. 11/12 CONCRETE MANWAY; UNCOVERING UST No. 12; COMPARE w/PL 1, R1/F8; VIEW TO THE NW.

5 2 93/12/16 1 24 25/25A EXCAVATION TRENCH FOR REMOVAL OF PRINCIPAL 6 inch PIPELINE; VIEW TO THE NW.

5 2 93/12/16 1 25 26/26A FROM WITHIN THE TRENCH; VIEW TO THE NW.

5 2 93/12/16 1 26 27/27A AIR SEPARATOR PIT w/SIDE WALLS DESTROYED; VIEW TO THE NW.

5 2 93/12/16 1 27 28/28A EXCAVATION TRENCH FOR REMOVAL OF PRINCIPAL 6 inch PIPELINE; VIEW TO THE NW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.


PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SUBJECT/DESCRIPTION

SITE PHOTO DATE ROLL FRAME NEGATIVE  
LOG No. No. No. No.

5	2	93/12/16	1	28	29/29A	EXCAVATION TRENCH FOR REMOVAL OF PRINCIPAL 6 INCH PIPELINE. VIEW TO THE SE.
5	2	93/12/16	1	29	30/30A	UST No. 7/8 CONCRETE MAINWAY, AFTER GRUBBING; VIEW TO THE SE.
5	2	93/12/16	1	30	31/31A	CONCRETE FILL PIT/VALVE PIT, AFTER GRUBBING; COMPARE W/PL 1, 31/F/17, VIEW TO THE SE.
5	2	93/12/16	1	31	32/32A	UST No. 5/6 CONCRETE MAINWAY, AFTER GRUBBING; VIEW TO THE SE.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



UST CAPACITY:

- UST NO. 1 - 25,000 GAL
- UST NO. 2 - 25,000 GAL
- UST NO. 5 - 25,000 GAL
- UST NO. 6 - 25,000 GAL
- UST NO. 7 - 25,000 GAL
- UST NO. 8 - 25,000 GAL
- UST NO. 11 - 25,000 GAL
- UST NO. 12 - 25,000 GAL

- UST NO. 3 - 600 GAL
- UST NO. 4 - 600 GAL
- UST NO. 9 - 600 GAL
- UST NO. 10 - 600 GAL

LEGEND:

DIRECTION OF  
PICTURE AND ROLL  
AND FRAME NUMBER

GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.

FILE: RANG54

DATE: 1994


SITE 5 - Photo Log No. 2  
Photo Grid Location/Orientation  
December 16, 1993

VANG BASE  
192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	3	93/12/18	1	32	33/33A	VIEW TO WEST -- ACCESS ROAD COMING INTO POL; INITIAL PUMPING OPERATIONS RELATED TO UST No. 12.
5	3	93/12/18	1	33	34/34A	VIEW TO THE EAST -- ACROSS POL FOR PUMPING FROM UST No. 12.
5	3	93/12/18	1	34	35/35A	VIEW TO THE WEST -- ACCESS ROAD AND TANKER BEING LOADED.
5	3	93/12/18	1	35	36/36A	VIEW TO THE EAST OF GRUBBED POL AND LINES FOR PUMPING.
5	3	93/12/18	1	36	E	AIR SEPARATOR PIT AND GRUBBED SITE; VIEW TO THE SW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .



# UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 UST NO. 2 - 25,000 GAL  
 UST NO. 5 - 25,000 GAL  
 UST NO. 6 - 25,000 GAL  
 UST NO. 7 - 25,000 GAL  
 UST NO. 8 - 25,000 GAL  
 UST NO. 11 - 25,000 GAL  
 UST NO. 12 - 25,000 GAL

UST NO. 3 - 600 GAL  
 UST NO. 4 - 600 GAL  
 UST NO. 9 - 600 GAL  
 UST NO. 10 - 600 GAL

## LEGEND:

▲ DIRECTION OF  
 PICTURE AND ROLL  
 RL1  
 F5

GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.

SITE 5 - Photo Log No. 3

VANG BASE

Photo Grid Location/Orientation  
 December 18, 1993

192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

FILE: RANG55

DATE: 1994

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA


SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME		SUBJECT/DESCRIPTION
				No.	NEGATIVE No.	
5	4	94/01/06	2	3	4	4-600 gallon AQUATRAP TANKS/UST Nos. 3, 4, 9, 10; TEMPORARY STORAGE IN NW CORNER OF POL; VIEW TO THE WEST.
5	4	94/01/06	2	4	5	4-600 gallon AQUATRAP TANKS/UST Nos. 3, 4, 9, 10; TEMPORARY STORAGE IN NW CORNER OF POL; VIEW TO THE EAST.
5	4	94/01/06	2	5	6	4-600 gallon AQUATRAP TANKS/UST Nos. 3, 4, 9, 10; TEMPORARY STORAGE IN NW CORNER OF POL; VIEW TO THE NORTH.
5	4	94/01/06	2	6	7	EXCAVATING UST No. 11/12; VIEW TO THE NW.
5	4	94/01/06	2	7	8	EXCAVATING UST No. 11/12; VIEW TO THE NW.
5	4	94/01/06	2	8	9	EXCAVATING UST No. 11/12; VIEW TO THE NW.
5	4	94/01/06	2	9	10	EXCAVATING UST No. 11/12; VIEW TO THE NW.
5	4	94/01/06	2	10	11	EXCAVATING UST No. 11/12; VIEW TO THE SE.
5	4	94/01/06	2	11	12	EXCAVATING UST No. 11/12; VIEW TO THE SE.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	4	94/01/06	2	12	13	EXCAVATING UST No. 11/12; VIEW TO THE NW.
5	4	94/01/06	2	13	14	EXCAVATING UST No. 11/12; VIEW TO THE NW.
5	4	94/01/06	2	14	15	REMOVAL OF AIR SEPARATOR PIT EQUIPMENT; VIEW TO THE SE.
5	4	94/01/06	2	15	16	REMOVAL OF AIR SEPARATOR PIT EQUIPMENT; VIEW TO THE SE.
5	4	94/01/06	2	16	17	REMOVAL OF UST No. 12; VIEW TO THE NW.
5	4	94/01/06	2	17	18	REMOVAL OF UST No. 12; NOTE MINIMAL WATER IN PIT BOTTOM; VIEW TO THE NW.
5	4	94/01/06	2	18	19	REMOVAL OF UST No. 12; VIEW TO THE NW.
5	4	94/01/06	2	19	20	REMOVAL OF UST No. 12; VIEW TO THE NW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



ADVANCED SCIENCES, INC.

SITE 5 - Photo Log No. 4

Photo Grid Location/Orientation  
January 06, 1994

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia

FILE: RANG56

DATE: 1994



PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	5	94/01/07	2	20	21	UST No. 12 IN TEMPORARY STORAGE AREA; 600 gallon UST IN FOREGROUND; VIEW TO THE NE.
5	5	94/01/07	2	21	22	UST No. 12 IN TEMPORARY STORAGE AREA, VIEW TO THE NW
5	5	94/01/07	2	22	23	REMOVAL OF UST No. 11; VIEW TO THE NW.
5	5	94/01/07	2	23	24	REMOVAL OF UST No. 11; VIEW TO THE NW.
5	5	94/01/07	2	24	25	REMOVAL OF UST No. 11; VIEW TO THE NW
5	5	94/01/07	2	25	26	REMOVAL OF UST No. 11; VIEW TO THE NW.
5	5	94/01/07	2	26	27	REMOVAL OF UST No. 11; VIEW TO THE SW.
5	5	94/01/07	2	27	28	REMOVAL OF UST No. 11; VIEW TO THE SE
5	5	94/01/07	2	28	29	REMOVAL OF UST No. 11; VIEW TO THE SE.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA


SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	5	94/01/07	2	29	30	REMOVAL OF UST No. 11; VIEW TO THE SW.
5	5	94/01/07	2	30	31	REMOVAL OF UST No. 11; VIEW TO THE SW.
5	5	94/01/07	2	31	32	UST Nos. 11 & 12 IN TEMPORARY STORAGE; VIEW TO THE NW.
5	5	94/01/07	2	32	33	EXCAVATION OF UST No. 1; VIEW TO SE.
5	5	94/01/07	2	33	34	EXCAVATION OF UST No. 1; VIEW TO NW.
5	5	94/01/07	2	34	35	EXCAVATION OF UST No. 1; VIEW TO NW.
5	5	94/01/07	2	35	36	EXCAVATION OF UST No. 1; VIEW TO NE.
5	5	94/01/07	2	36	END	EXCAVATION OF UST No. 1; VIEW TO NE.
5	5	94/01/07	3	1	2	UST No. 1 REMOVAL; VIEW TO THE SE.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	5	94/01/07	3	2	3	UST No. 1 REMOVAL; VIEW TO THE SE.
5	5	94/01/07	3	3	4	UST No. 1 BEING TOWED TO TEMPORARY STORAGE;
5	5	94/01/07	3	4	5	VIEW INTO PIT CREATED BY UST No. 1 REMOVAL; NOTE LACK OF PIT FLUIDS; VIEW TO THE NW.
5	5	94/01/07	3	5	6	UST TEMPORARY STORAGE; VIEW TO THE NW.
5	5	94/01/07	3	6	7	UST TEMPORARY STORAGE; VIEW TO THE W.
5	5	94/01/07	3	7	8	EXCAVATION OF UST No. 8; VIEW TO THE SE.
5	5	94/01/07	3	8	9	EXCAVATION OF UST No. 8; VIEW TO THE SE.
5	5	94/01/07	3	9	10	EXCAVATION OF UST No. 8; VIEW TO THE NW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



# UST CAPACITY:

UST NO. 1 - 25,000 GAL  
 UST NO. 2 - 25,000 GAL  
 UST NO. 5 - 25,000 GAL  
 UST NO. 6 - 25,000 GAL  
 UST NO. 7 - 25,000 GAL  
 UST NO. 8 - 25,000 GAL  
 UST NO. 11 - 25,000 GAL  
 UST NO. 12 - 25,000 GAL

UST NO. 3 - 600 GAL  
 UST NO. 4 - 600 GAL  
 UST NO. 9 - 600 GAL  
 UST NO. 10 - 600 GAL

# LEGEND:

➔ DIRECTION OF  
 PICTURE AND ROLL  
 AND FRAME NUMBER  
 RL1  
 F5

GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.

FILE: RANG57

DATE: 1994

SITE 5 - Photo Log No. 5  
 Photo Grid Location/Orientation  
 January 07, 1994

VANG BASE  
 192nd Tactical Fighter Group  
 Richmond International Airport  
 Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA


SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	6	94/01/08	3	10	11	EXCAVATION OF UST No. 8; VIEW TO THE NW.
5	6	94/01/08	3	11	12	REMOVAL OF UST No. 8; VIEW TO THE NW.
5	6	94/01/08	3	12	13	REMOVAL OF UST No. 8; VIEW TO THE NW.
5	6	94/01/08	3	13	14	REMOVAL OF UST No. 8; VIEW TO THE NW.
5	6	94/01/08	3	14	15	REMOVAL OF UST No. 8; VIEW TO THE NW.
5	6	94/01/08	3	15	16	USTs IN TEMPORARY STORAGE; VIEW TO THE W.
5	6	94/01/08	3	16	17	EXCAVATION OF UST No. 7; VIEW TO THE NW.
5	6	94/01/08	3	17	18	REMOVAL OF UST No. 7; VIEW TO THE NW.
5	6	94/01/08	3	18	19	REMOVAL OF UST No. 7; VIEW TO THE NW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	6	94/01/08	3	19	20	REMOVAL OF UST No. 7; VIEW TO THE NW.
5	6	94/01/08	3	20	21	USTs IN TEMPORARY STORAGE; VIEW TO THE W.
5	6	94/01/08	3	21	22	EXCAVATION OF UST No. 5; VIEW TO THE SE.
5	6	94/01/08	3	22	23	EXCAVATION OF UST No. 5; VIEW TO THE SE.
5	6	94/01/08	3	23	24	EXCAVATION OF UST No. 5; VIEW TO THE NW.
5	6	94/01/08	3	24	END	EXCAVATION OF UST No. 5; VIEW TO THE NW.
5	6	94/01/08	4	1	2	REMOVAL OF UST No. 5; VIEW TO THE NW
5	6	94/01/08	4	2	3	REMOVAL OF UST No. 5; VIEW TO THE NW
5	6	94/01/08	4	3	4	REMOVAL OF UST No. 5; VIEW TO THE NW

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.



ADVANCED SCIENCES, INC.

FILE: RANG58

SITE 5 - Photo Log No. 6  
Photo Grid Location/Orientation  
January 08, 1994

VANG BASE  
192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	7	94/01/11	4	4	5	BACKFILL OPERATIONS, UST No. 7/8, VIEW TO THE NW;
5	7	94/01/11	4	5	6	DESTRUCTION OF AQUATRAP PIT FOR UST No. 10 VIEW TO THE E.
5	7	94/01/11	4	6	7	VIEW DOWN INTO AQUATRAP PIT FOR UST No. 4;
5	7	94/01/11	4	7	8	VIEW DOWN INTO AQUATRAP PIT FOR UST No. 4;
5	7	94/01/11	4	8	9	DESTRUCTION OF AQUATRAP PIT FOR UST No. 4; VIEW TO THE E.
5	7	94/01/11	4	9	10	VIEW FROM ACCESS ROAD INTO POL AREA; VIEW TO THE E.
5	7	94/01/11	4	10	11	EXCAVATED PIT FROM REMOVAL OF UST Nos. 11/12; VIEW TO THE NW.

5 7 94/01/11 4 11 12 BACKFILL OPERATIONS, UST No. 7/8, VIEW TO THE NW;

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .



PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	7	94/01/11	4	12	13	EXCAVATED PIT FROM REMOVAL OF UST No. 1; VIEW TO THE NW.
5	7	94/01/11	4	13	14	EXCAVATED PIT FROM REMOVAL OF UST No. 1; VIEW TO THE NW.
5	7	94/01/11	4	14	15	EXCAVATED PIT FROM REMOVAL OF UST No. 1; VIEW TO THE NW.
5	7	94/01/11	4	15	16	EXCAVATED PIT FROM REMOVAL OF UST No. 5; VIEW TO THE SE.


NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .



PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	8	94/01/13	5	24	23	BOTTOM OF TANK PIT FOR UST No. 6; VIEW TO THE SE.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .



PERIMETER FENCE

UST CAPACITY:

- UST NO. 1 - 25,000 GAL
- UST NO. 2 - 25,000 GAL
- UST NO. 5 - 25,000 GAL
- UST NO. 6 - 25,000 GAL
- UST NO. 7 - 25,000 GAL
- UST NO. 8 - 25,000 GAL
- UST NO. 11 - 25,000 GAL
- UST NO. 12 - 25,000 GAL

- UST NO. 3 - 600 GAL
- UST NO. 4 - 600 GAL
- UST NO. 9 - 600 GAL
- UST NO. 10 - 600 GAL

NOTE:

R5,F24 DEPICTS "GREENISH" LIQUID THAT WAS DETECTED BENEATH TANK NO. 6

LEGEND:

DIRECTION OF PICTURE AND ROLL  
RL1 AND FRAME NUMBER  
F5


GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.		SITE 5 - Photo Log No. 8		VANG BASE	
FILE: RANG60	DATE: 1994	Photo Grid Location/Orientation January 13, 1994		192nd Tactical Fighter Group Richmond International Airport Sandston, Virginia	

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME		NEGATIVE No.	SUBJECT/DESCRIPTION
					No.		
5	9	94/01/14	5	21	20		EQUIPMENT ON PAVED ROAD ADJACENT TO SITE 5; VIEW TO THE E.
5	9	94/01/14	5	20	19		EQUIPMENT ON PAVED ROAD ADJACENT TO SITE 5; VIEW TO THE NW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .



RL5, F20-21 ON  
PAVED ROADWAY  
WEST OF SITE 5

GRID SCALE: 20 FT PER GRID

TO FLIGHTLINE

LEGEND:

DIRECTION OF  
PICTURE AND ROLL  
RL1  
F5

UST CAPACITY:

- UST NO. 1 - 25,000 GAL
- UST NO. 2 - 25,000 GAL
- UST NO. 5 - 25,000 GAL
- UST NO. 6 - 25,000 GAL
- UST NO. 7 - 25,000 GAL
- UST NO. 8 - 25,000 GAL
- UST NO. 11 - 25,000 GAL
- UST NO. 12 - 25,000 GAL
- UST NO. 3 - 600 GAL
- UST NO. 4 - 600 GAL
- UST NO. 9 - 600 GAL
- UST NO. 10 - 600 GAL

ADVANCED SCIENCES, INC.

SITE 5 - Photo Log No. 9

Photo Grid Location/Orientation  
January 14, 1994

VANG BASE

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia


FILE: RANG61

DATE: 1994

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	10	94/01/27	5	11	10	VIEW FROM ACCESS ROAD INTO POL; VIEW TO THE EAST
5	10	94/01/27	5	9	8	USTs BEING DESTROYED; VIEW TO THE NW.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .



UST CAPACITY:

UST NO. 1 - 25,000 GAL  
UST NO. 2 - 25,000 GAL  
UST NO. 5 - 25,000 GAL  
UST NO. 6 - 25,000 GAL  
UST NO. 7 - 25,000 GAL  
UST NO. 8 - 25,000 GAL  
UST NO. 11 - 25,000 GAL  
UST NO. 12 - 25,000 GAL

UST NO. 3 - 600 GAL  
UST NO. 4 - 600 GAL  
UST NO. 9 - 600 GAL  
UST NO. 10 - 600 GAL

LEGEND:

➔ DIRECTION OF  
PICTURE AND ROLL  
RL1  
F5

GRID SCALE: 20 FT PER GRID

ADVANCED SCIENCES, INC.

SITE 5 - Photo Log No. 10

VANG BASE

Photo Grid Location/Orientation  
January 27, 1994

FILE: RANG62

DATE: 1994

192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia




PHOTOGRAPH DOCUMENTATION  
 UST REMOVAL  
 VIRGINIA AIR NATIONAL GUARD  
 SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
------	------------------	------	-------------	--------------	-----------------	---------------------

5	17	94/01/28	5	8	7	USTs IN TEMPORARY STORAGE; MANWAYS CUT-INTO TANK ENDS/SIDES.
---	----	----------	---	---	---	--

NOTE:  
 PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADIN VIEW TO THE NE.



PERIMETER  
FENCE

**UST CAPACITY:**

UST NO. 1 - 25,000 GAL  
UST NO. 2 - 25,000 GAL  
UST NO. 5 - 25,000 GAL  
UST NO. 6 - 25,000 GAL  
UST NO. 7 - 25,000 GAL  
UST NO. 8 - 25,000 GAL  
UST NO. 11 - 25,000 GAL  
UST NO. 12 - 25,000 GAL

UST NO. 3 - 600 GAL  
UST NO. 4 - 600 GAL  
UST NO. 9 - 600 GAL  
UST NO. 10 - 600 GAL

**NOTE:**

R5,F8 SHOWS TANK NO. 1  
AND 11 REMOVED WITH  
ACCESS OPENINGS CUT  
INTO ENDS

**LEGEND:**

DIRECTION OF  
PICTURE AND ROLL  
RL1 AND FRAME NUMBER  
F5

GRID SCALE: 20 FT PER GRID

TO FLIGHTLINE

ADVANCED SCIENCES, INC.

FILE: RANG63

DATE: 1994

SITE 5 - Photo Log No. 11  
Photo Grid Location/Orientation  
January 28, 1994

VANG BASE  
192nd Tactical Fighter Group  
Richmond International Airport  
Sandston, Virginia

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	12	94/02/10	7	1	2	VIEW FROM ACCESS ROAD INTO POL; VIEW TO THE EAST.
5	12	94/02/10	7	2	3	BACKFILLED AREA -- FORMERLY UST No. 5/6; VIEW TO THE SE.
5	12	94/02/10	7	3	4	FILL PIT/VALVE PIT AREA (CENTER); BACKFILLED AREAS FOR UST No. 5/6 (RIGHT), UST No. 7/8 (LEFT); VIEW TO THE SE.
5	12	94/02/10	7	4	5	BACKFILLED AREA FOR UST No. 11/12 IN BACKGROUND; VIEW TO THE SE.
5	12	94/02/10	7	5	6	EXCAVATION FOR PRINCIPAL 6 inch PIPELINE; VIEW TO THE SE.
5	12	94/02/10	7	6	7	CONCRETE AIR SEPARATOR BOX PRIOR TO REMOVAL; VIEW TO THE SW.
5	12	94/02/10	7	7	8	PIPE/VALVE PIT REMOVAL; VIEW TO THE NW.
5	12	94/02/10	7	8	9	CONCRETE VALVE BOX REMOVAL; VIEW TO THE SE.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	12	94/02/10	7	9	10	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	10	11	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	11	12	CONCRETE PRESSURE CONTROL BOX REMOVAL/VALVE PIT; VIEW TO THE SE.
5	12	94/02/10	7	12	13	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	13	14	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	14	15	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	15	16	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	16	17	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	17	18	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING.

PHOTOGRAPH DOCUMENTATION  
UST REMOVAL  
VIRGINIA AIR NATIONAL GUARD  
SANDSTON, VA

SITE	PHOTO LOG No.	DATE	ROLL No.	FRAME No.	NEGATIVE No.	SUBJECT/DESCRIPTION
5	12	94/02/10	7	18	19	CONCRETE PRESSURE CONTROL BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	19	20	CONCRETE AIR SEPARATOR BOX REMOVAL; VIEW TO THE SE.
5	12	94/02/10	7	20	21	CONCRETE AIR SEPARATOR BOX REMOVAL; VIEW TO THE NW.
5	12	94/02/10	7	21	22	CONCRETE AIR SEPARATOR BOX REMOVAL; VIEW INTO THE PIT.
5	12	94/02/10	7	22	23	CONCRETE AIR SEPARATOR BOX REMOVAL; VIEW INTO THE PIT.
5	12	94/02/10	7	23	24	CONCRETE AIR SEPARATOR BOX REMOVAL; VIEW INTO THE PIT.

NOTE:  
PHOTOGRAPHS INCLUDED IN THIS APPENDIX ARE INDICATED BY SHADING .





Site 5 - Grubbing Operations, UST Nos. 5/6. View to the East.  
(Photo Log No. 1; Roll No. 1/Frame No. 1)



Site 5 - After Grubbing UST Nos. 5/6. View to the East.  
(Photo Log No. 2; Roll No. 1/Frame No. 19)



Site 5 - Grubbing Operations, Fill Pit/Valve Pit. View to the Southeast.  
(Photo Log No. 1; Roll No. 1/Frame No. 17)



Site 5 - After Grubbing Operations, Fill Pit/Valve Pit. View to the Southeast.  
(Photo Log No. 2; Roll No. 1/Frame No. 30)





Site 5 - Grubbing Operations, UST Nos. 7/8. View to the Southeast.  
(Photo Log No. 1; Roll No. 1/Frame No. 16)



Site 5 - After Grubbing Operations, UST Nos. 7/8. View to the Southeast.  
(Photo Log No. 2; Roll No. 1/Frame No. 29)



Site 5 - Grubbing Operations, UST Nos. 5/6. View to the Southeast.  
(Photo Log No. 1; Roll No. 1/Frame No. 18)




Site 5 - After Grubbing Operations, UST Nos. 5/6. View to the Southeast.  
(Photo Log No. 2; Roll No. 1/Frame No. 31)



Site 5 - Four 600 gallon Aquatrap USTs After Removal. Temporary Storage Site Located in Northwest Corner of Site 5. View to the Northwest.

(Photo Log No. 4; Roll No. 2/Frame No. 3)



Site 5 - UST No. 12 Removal. View to the Northwest.  
(Photo Log No. 4; Roll No. 2/Frame No. 18)



Site 5 - UST No. 12 in Temporary Storage. View to the North.  
(Photo Log No. 5; Roll No. 2/Frame No. 21)



Site 5 - UST No. 11 Removal. View into the Pit.  
(Photo Log No. 5; Roll No. 2/Frame No. 24)



Site 5 - UST No. 11 Removal. View to the West.  
(Photo Log No. 5; Roll No. 2/Frame No. 27)



Site 5 - USTs After Manways have been cut in Tank-ends/sides.  
View to the Northwest  
(Photo Log No. 11; Roll No. 5/Frame No. 8)





Site 5 - Valve Pit/Pressure Control Pit Removal. View to the Southeast.  
(Photo Log No. 12; Roll No. 7/Frame No. 11)



Site 5 - Pipe/Valve Pit Removal. View to the Northwest  
(Photo Log No. 12; Roll No. 7/Frame No. 7)



Site 5 - Principal 6 inch  
AVGAS Pipeline Removal.  
View to the Northwest.  
(Photo Log No. 2;  
Roll No. 1/Frame No. 27)



Site 5 - Principal 6 inch  
AVGAS Pipeline Removal.  
View to the Southeast.  
(Photo Log No. 2;  
Roll No. 1/Frame No. 28)





Site 5 - Backfill Operations, UST Nos. 7/8. View to the Northwest.  
(Photo Log No. 7; Roll No. 4/Frame No. 4)



Site 5 - Backfill Operations, UST Nos. 7/8. View to the Northwest.  
(Photo Log No. 7; Roll No. 4/Frame No. 11)

**ANALYTICAL RESULTS FOR CLOSURE SAMPLES  
COLLECTED AT SITE 4**

# ENVIRONMENTAL LABORATORIES INC.

9211 Burge Avenue, Richmond, VA 23237

## CHAIN OF CUSTODY

Sheet ①

Client: Advanced Sciences, Inc. Address: 65 N. Ithaca Rd. off Route 20 37834  
 Company Contact: Hawk, Joseph Phone: (813) 483-1274 Submit Report to: Hawk, Joseph

P.O. No.: \_\_\_\_\_ Submit Bill to: \_\_\_\_\_

Sampler: Joe Hawk ANALYSIS REQUESTED \_\_\_\_\_

Project ID/Location: <u>9750-K10 / ADE SITE 4 Hawk BCL</u>		SAMPLE INFORMATION		Date		Time		N O.	C O M P	G R A B	C O N T.	REMARKS:
LAB ID (Lab Use) (Only)	Location											
1401285-01	R1D4TFB1801			1/25/94		0800		✓	✓	✓	✓	24K-TX-RAN
-02	R1D4TFB1801			1/25/94		0815		✓	✓	✓	✓	
-03	R1D4TFB1801			1/25/94		0840		✓	✓	✓	✓	
-04	R1D4TFB1801			1/25/94		0900		✓	✓	✓	✓	
-05	R1D4TFB1801			1/25/94		0940		✓	✓	✓	✓	
-06	R1D4TFB1801			1/25/94		1000		✓	✓	✓	✓	
-07	R1D4TFB1801			1/25/94		1600		✓	✓	✓	✓	
-08	R1D4TFB1801			1/25/94		1615		✓	✓	✓	✓	
-09	R1D4TFB1801			1/25/94		1630		✓	✓	✓	✓	

Samples Relinquished by:	Date	Time	Samples Received by:	Date	Time	Reason for Trans.
<u>Joe Hawk</u>	<u>1/25/94</u>	<u>1720</u>	<u>J. Chuldeas</u>	<u>1/26/94</u>	<u>17:20</u>	

Preservative check in lab: \_\_\_\_\_ Temp: \_\_\_\_\_ pH check: \_\_\_\_\_ Preservatives added: \_\_\_\_\_  
 Comments: \_\_\_\_\_

# ENVIRONMENTAL LABORATORIES INC.

9211 Burge Avenue, Richmond, VA 23237

## CHAIN OF CUSTODY

Client: ADAMSON SCIENCES, INC. Address: 165 NITTELL RD OAK RIDGE, TN 37830

Company Contact: HANK, JOSEPH Phone: (615) 833-1274 Submit Report to: HANK, JOSEPH

P.O. No.:

Submit Bill to:

Sampler: JOE HANK

Project ID/Location:

9750.K-10/ADG SITE 4 TADK RCL

### ANALYSIS REQUESTED

N O.

C O M P C O N T.

#### SAMPLE INFORMATION

LAB ID  
(Lab Use)  
(Only)

Location

Date Time

REMARKS:

RM04A T6C1001 1/29/94 0905

RM04A T6C1001 1/29/94 1015

Z4HKTOLKBN

Samples Relinquished by:

Date

Time

Samples Received by:

Date

Time

Reason for Trans.

Preservative check in lab:

Temp:

pH check:

Preservatives added:

Comments:

# ENVIRONMENTAL LABORATORIES INC.

9211 Burge Avenue, Richmond, VA 23237

## CHAIN OF CUSTODY

Client: ADVANCE SCIENCES INC Address: 165 MICHELE ROAD OAK RIDGE, TN 37830  
 Company Contact: D.J. McMullen Phone: 615/4831274 Submit Report to: McMullen, P.J.  
 P.O. No.: Submit Bill to: ASI - OAK RIDGE; Attn: Joe Hawk  
 Sampler: McMullen, P.J. ANALYSIS REQUESTED

LAB ID (Lab Use) (Only)	SAMPLE INFORMATION		Date		Time	C O M P		G R A B	C O N T.	N O.	REMARKS:
	Location										
	RMD4TP9C1801		02/09/94		1430			X		✓	As fast as possible
	RMD4TP10D1801		02/09/94		1440			X		✓	Verbal when available
	RMD4TP11C1801		02/09/94		1445			X		✓	
	RMD4TP10C1801		02/09/94		1450			X		✓	
	RMD4TP9C1801/02		02/09/94		1430			X		✓	Routing
	RMD4TP10D1801/02		02/09/94		1440			X		✓	
	RMD4TP11C1801/02		02/09/94		1445			X		✓	
	RMD4TP10C1801/02		02/09/94		1450			X		✓	

Samples Relinquished by:	Date	Time	Samples Received by:	Date	Time	Reason for Trans
D.J. McMullen	02/09/94	1557	Joe Hawk	2/9/94	15:57	

Preservative check in lab: Temp: pH check: Preservatives added:

Comments:

Advance Sciences Inc.  
165 Mitchell Road  
Oak Ridge, TN 37830  
  
Attn: P. J. McMullen

Purchase Order: Subcontract #9750-3-94  
Invoice Number:

Sampled by Advanced Sciences Inc.

Order #: 94-01-225  
Date: 01/31/94 17:35  
Work ID: 9750-K10 TANK PULL  
Date Received: 01/26/94  
Date Completed: 01/30/94

Client Code: 1103

SAMPLE IDENTIFICATION

Sample Number	Sample Description	Sample Number	Sample Description
01	RMD4TP5D1801	06	RMD4TP3C1801
02	RMD4TP6C1801	07	RMD4TP11C1801
03	RMD4TP6B1801	08	RMD4TP9C1801
04	RMD4TP5C1801	09	RMD4TP10B1801
05	RMD4TP5B1801		

Mundy Baldwin  
Certified By

Order # 94-01-225  
01/31/94 17:35

Page 2

## TEST RESULTS BY SAMPLE

Sample: 01AR RMD4TP5D1801

Collected: 01/26/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Gasoline Range Organics	BDL	5.0	mg/Kg	01/27/94	JTS

Sample: 01BR RMD4TP5D1801

Collected: 01/26/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Diesel Range Organics	BDL	5.0	mg\Kg	01/27/94	SN

Sample: 02AR RMD4TP6C1801

Collected: 01/26/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Gasoline Range Organics	BDL	5.0	mg/Kg	01/27/94	JTS

Sample: 02BR RMD4TP6C1801

Collected: 01/26/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Diesel Range Organics	BDL	5.0	mg\Kg	01/27/94	SN

Sample: 03AR RMD4TP6B1801

Collected: 01/26/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Gasoline Range Organics	12.0	5.0	mg/Kg	01/27/94	JTS

Sample: 03B RMD4TP6B1801

Collected: 01/26/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Diesel Range Organics	BDL	5.0	mg\Kg	01/27/94	SN

Sample: 04AR RMD4TP5C1801

Collected: 01/26/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Gasoline Range Organics	BDL	5.0	mg/Kg	01/27/94	JTS

Order # 94-01-225  
01/31/94 17:35

## TEST RESULTS BY SAMPLE

Page 3

Sample: 04BR RMD4TP5C1801

Collected: 01/26/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
14.8	5.0	mg/Kg	01/27/94	SN

Sample: 05AR RMD4TP5B1801

Collected: 01/26/94 Category: SOIL

Test Description  
Gasoline Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
BDL	5.0	mg/Kg	01/27/94	JTS

Sample: 05BR RMD4TP5B1801

Collected: 01/26/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
BDL	5.0	mg/Kg	01/27/94	SN

Sample: 06AR RMD4TP3C1801

Collected: 01/26/94 Category: SOIL

Test Description  
Gasoline Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
BDL	5.0	mg/Kg	01/27/94	JTS

Sample: 06BR RMD4TP3C1801

Collected: 01/26/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
BDL	5.0	mg/Kg	01/27/94	SN

Sample: 07AR RMD4TP11C1801

Collected: 01/26/94 Category: SOIL

Test Description  
Gasoline Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
BDL	5.0	mg/Kg	01/27/94	JTS

Sample: 07BR RMD4TP11C1801

Collected: 01/26/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
448.8	125	mg/Kg	01/27/94	SN



Order # 94-01-225  
01/31/94 17:35

TEST RESULTS BY SAMPLE

Sample: 08AR RMD4TP9C1801	Collected: 01/26/94 Category: SOIL			
<u>Test Description</u> Gasoline Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0	<u>Units</u> mg/Kg	<u>Analyzed</u> 01/27/94
				<u>By</u> JTS
Sample: 08BR RMD4TP9C1801	Collected: 01/26/94 Category: SOIL			
<u>Test Description</u> Diesel Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0	<u>Units</u> mg\Kg	<u>Analyzed</u> 01/27/94
				<u>By</u> SN
Sample: 09AR RMD4TP10B1801	Collected: 01/26/94 Category: SOIL			
<u>Test Description</u> Gasoline Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0	<u>Units</u> mg/Kg	<u>Analyzed</u> 01/27/94
				<u>By</u> JTS
Sample: 09BR RMD4TP10B1801	Collected: 01/26/94 Category: SOIL			
<u>Test Description</u> Diesel Range Organics	<u>Result</u> 5.7	<u>Limit</u> 5.0	<u>Units</u> mg\Kg	<u>Analyzed</u> 01/27/94
				<u>By</u> SN

Order # 94-01-225  
01/31/94 17:35

Page 5

TEST METHODOLOGIES

Diesel Range Organics in Soil analysis was performed according to EPA SW846  
Standard Methods, Method 8100.

Advance Sciences Inc.  
165 Mitchell Road  
Oak Ridge, TN 37830

Attn: P. J. McMullen

Purchase Order: Subcontract #9750-3-94  
Invoice Number:

Order #: 94-01-245  
Date: 01/31/94 18:01  
Work ID: 9750-K10 TANK PULL  
Date Received: 01/29/94  
Date Completed: 01/29/94

Client Code: 1103

SAMPLE IDENTIFICATION

Sample Number	Sample Description
01	RMD4AT8C1001

Sample Number	Sample Description
02	RMD4AT6C1001

Mundy Baldwin  
Certified By

Order # 94-01-245  
01/31/94 18:01

TEST RESULTS BY SAMPLE

Sample: 01A RMD4AT8C1001

Collected: 01/29/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Gasoline Range Organics	9.9	5.0	mg/Kg	01/29/94	MB

Sample: 01B RMD4AT8C1001

Collected: 01/29/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Diesel Range Organics	8.2	5.0	mg\Kg	01/29/94	SN

Sample: 02A RMD4AT6C1001

Collected: 01/29/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Gasoline Range Organics	<5.0	5.0	mg/Kg	01/29/94	MB

Sample: 02B RMD4AT6C1001

Collected: 01/29/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Diesel Range Organics	<5.0	5.0	mg\Kg	01/29/94	SN

Order # 94-01-245  
01/31/94 17:53

Page 3

TEST METHODOLOGIES

Diesel Range Organics in Soil analysis was performed according to EPA SW846  
Standard Methods, Method 8100.

Advance Sciences Inc.  
165 Mitchell Road  
Oak Ridge, TN 37830

Attn: *Joe Hawk*

Purchase Order: Subcontract #9750-3-94  
Invoice Number:

Order #: 94-02-106  
Date: 02/23/94 17:54  
Work ID: 9750K10-VANG TANKPULL SITE4/5  
Date Received: 02/09/94  
Date Completed: 02/23/94

Client Code: 1103

Sampled by Advance Sciences

SAMPLE IDENTIFICATION

Sample Number	Sample Description
01	RMD4TP9C1801 GRAB
02	RMD4TP10D1801 GRAB

Sample Number	Sample Description
03	RMD4TP11C1801 GRAB
04	RMD4TP10C1801 GRAB

*Mindy Beldwin, Michelle Hugner*  
Certified By

Order # 94-02-106  
02/23/94 17:54

TEST RESULTS BY SAMPLE

Sample: 01B		RMD4TP9C1801/02 GRAB	Collected: 02/09/94		Category: SOIL
<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Arsenic	1.7	0.5	mg/Kg	02/17/94	MLH
Barium	15.6	1.0	mg/Kg	02/23/94	MLH
Cadmium	<0.1	0.1	mg/Kg	02/22/94	MLH
Chromium	4.9	0.8	mg/Kg	02/18/94	MLH
Lead	6.8	0.5	mg/Kg	02/20/94	MLH
Mercury	<0.10	0.10	mg/Kg	02/18/94	MLH
Selenium	<5.0	5.0	mg/Kg	02/18/94	MLH
Silver	<0.2	0.2	mg/Kg	02/15/94	MLH
TOTAL METALS	02/14/94		Complete		MLH

Sample: 02B		RMD4TP10D1801/02 GRAB	Collected: 02/09/94		Category: SOIL
<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Arsenic	1.7	0.5	mg/Kg	02/17/94	MLH
Barium	13.5	1.0	mg/Kg	02/23/94	MLH
Cadmium	0.1	0.1	mg/Kg	02/22/94	MLH
Chromium	6.0	0.8	mg/Kg	02/18/94	MLH
Lead	7.2	0.5	mg/Kg	02/20/94	MLH
Mercury	<0.10	0.10	mg/Kg	02/18/94	MLH
Selenium	<5.0	5.0	mg/Kg	02/18/94	MLH
Silver	<0.2	0.2	mg/Kg	02/15/94	MLH
TOTAL METALS	02/14/94		Complete		MLH

Sample: 03B		RMD4TP11C1801/02 GRAB	Collected: 02/09/94		Category: SOIL
<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Arsenic	2.0	0.5	mg/Kg	02/17/94	MLH
Barium	12.8	1.0	mg/Kg	02/23/94	MLH
Cadmium	<0.1	0.1	mg/Kg	02/22/94	MLH
Chromium	6.1	0.8	mg/Kg	02/18/94	MLH
Lead	8.2	0.5	mg/Kg	02/20/94	MLH
Mercury	<0.10	0.10	mg/Kg	02/18/94	MLH
Selenium	<5.0	5.0	mg/Kg	02/18/94	MLH

Order # 94-02-106  
02/23/94 17:54

TEST RESULTS BY SAMPLE

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Silver	<0.2	0.2	mg/Kg	02/15/94	MLH
TOTAL METALS	02/14/94		Complete		MLH

Sample: 04B RMD4TP10C1801/02 GRAB Collected: 02/09/94 Category: SOIL

<u>Test Description</u>	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
Arsenic	1.3	0.5	mg/Kg	02/17/94	MLH
Barium	10.1	1.0	mg/Kg	02/23/94	MLH
Cadmium	<0.1	0.1	mg/Kg	02/22/94	MLH
Chromium	7.0	0.8	mg/Kg	02/18/94	MLH
Lead	6.5	0.5	mg/Kg	02/20/94	MLH
Mercury	<0.10	0.10	mg/Kg	02/18/94	MLH
Selenium	<5.0	5.0	mg/Kg	02/18/94	MLH
Silver	<0.2	0.2	mg/Kg	02/15/94	MLH
TOTAL METALS	02/14/94		Complete		MLH



Order # 94-02-106  
02/23/94 17:54

TEST RESULTS BY SAMPLE  
Page 4

Sample Description: RMD4TP9C1801 GRAB Lab No: 01A  
Test Description: Volatile Organics in Soil Method: METHOD 8240 Test Code: M8240S  
Collected: 02/09/94 14:30 Category: SOIL

VOLATILE ORGANICS IN SOIL BY METHOD 8240 UNITS ug/Kg

ANALYTE	RESULT	LOQ	ANALYTE	RESULT	LOQ
Chloromethane	BDL	10	1,2-Dichloropropane	BDL	5.0
Bromomethane	BDL	10	trans-1,3-Dichloropropene	BDL	5.0
Vinyl Chloride	BDL	10	Trichloroethene	BDL	5.0
Chloroethane	BDL	10	Dibromochloromethane	BDL	5.0
Methylene Chloride	10.2	5.0	1,1,2-Trichloroethane	BDL	5.0
Acetone	BDL	100	Benzene	BDL	5.0
Carbon Disulfide	BDL	100	cis-1,3-Dichloropropene	BDL	5.0
1,1-Dichloroethene	BDL	5.0	2-Chloroethyl Vinyl ether	BDL	10
1,1-Dichloroethane	BDL	5.0	Bromoform	BDL	5.0
trans-1,2-Dichloroethene	BDL	5.0	2-Hexanone	BDL	50
Chloroform	BDL	5.0	4-Methyl-2-Pentanone	BDL	50
1,2-Dichloroethane	BDL	5.0	Tetrachloroethene	BDL	5.0
2-Butanone	BDL	100	Toluene	BDL	5.0
1,1,1-Trichloroethane	BDL	5.0	Chlorobenzene	BDL	5.0
Carbon Tetrachloride	BDL	5.0	Ethyl Benzene	BDL	5.0
Vinyl Acetate	BDL	50	Styrene	BDL	5.0
Bromodichloromethane	BDL	5.0	Total Xylenes	BDL	15
1,1,2,2-Tetrachloroethane	BDL	5.0			

NOTES AND DEFINITIONS FOR THIS REPORT

All results Reported in micrograms/kilogram unless otherwise specified.  
BDL=Below Specified Detection Limit  
LOQ=Analytical Limit of Quantitation.  
\* = Sample not Analyzed for this Compound.

Order # 94-02-106  
02/23/94 17:54

TEST RESULTS BY SAMPLE

Page 5

Sample Description: RMD4TP1001801 GRAB Lab No: 02A  
Test Description: Volatile Organics in Soil Method: METHOD 8240 Test Code: M8240S  
Collected: 02/09/94 14:40 Category: SOIL

VOLATILE ORGANICS IN SOIL BY METHOD 8240				UNITS ug/Kg	
ANALYTE	RESULT	LOQ	ANALYTE	RESULT	LOQ
Chloromethane	BDL	10	1,2-Dichloropropane	BDL	5.0
Bromomethane	BDL	10	trans-1,3-Dichloropropene	BDL	5.0
Vinyl Chloride	BDL	10	Trichloroethene	BDL	5.0
Chloroethane	BDL	10	Dibromochloromethane	BDL	5.0
Methylene Chloride	9.2	5.0	1,1,2-Trichloroethane	BDL	5.0
Acetone	BDL	100	Benzene	BDL	5.0
Carbon Disulfide	BDL	100	cis-1,3-Dichloropropene	BDL	5.0
1,1-Dichloroethene	BDL	5.0	2-Chloroethyl Vinyl ether	BDL	10
1,1-Dichloroethane	BDL	5.0	Bromoform	BDL	5.0
trans-1,2-Dichloroethene	BDL	5.0	2-Hexanone	BDL	50
Chloroform	BDL	5.0	4-Methyl-2-Pentanone	BDL	50
1,2-Dichloroethane	BDL	5.0	Tetrachloroethene	BDL	5.0
2-Butanone	BDL	5.0	Toluene	BDL	5.0
1,1,1-Trichloroethane	BDL	5.0	Chlorobenzene	BDL	5.0
Carbon Tetrachloride	BDL	5.0	Ethyl Benzene	BDL	5.0
Vinyl Acetate	BDL	50	Styrene	BDL	5.0
Bromodichloromethane	BDL	5.0	Total Xylenes	BDL	15
1,1,2,2-Tetrachloroethane	BDL	5.0			

NOTES AND DEFINITIONS FOR THIS REPORT

All results Reported in micrograms/kilogram unless otherwise specified.  
BDL=Below Specified Detection Limit  
LOQ=Analytical Limit of Quantitation.  
\* = Sample not Analyzed for this Compound.

Order # 94-02-106

02/23/94 17:54

TEST RESULTS BY SAMPLE

Page 6

Sample Description: RMD4TP11C1801 GRAB

Lab No: 03A

Test Description: Volatile Organics in Soil Method: METHOD 8240 Test Code: M8240S

Collected: 02/09/94 14:45

Category: SOIL

## VOLATILE ORGANICS IN SOIL BY METHOD 8240 UNITS ug/Kg

ANALYTE	RESULT	LOQ	ANALYTE	RESULT	LOQ
Chloromethane	BDL	10	1,2-Dichloropropane	BDL	5.0
Bromomethane	BDL	10	trans-1,3-Dichloropropene	BDL	5.0
Vinyl Chloride	BDL	10	Trichloroethene	BDL	5.0
Chloroethane	BDL	10	Dibromochloromethane	BDL	5.0
Methylene Chloride	5.1	5.0	1,1,2-Trichloroethane	BDL	5.0
Acetone	BDL	100	Benzene	BDL	5.0
Carbon Disulfide	BDL	100	cis-1,3-Dichloropropene	BDL	5.0
1,1-Dichloroethene	BDL	5.0	2-Chloroethyl Vinyl ether	BDL	10
1,1-Dichloroethane	BDL	5.0	Bromoform	BDL	5.0
trans-1,2-Dichloroethene	BDL	5.0	2-Hexanone	BDL	50
Chloroform	BDL	5.0	4-Methyl-2-Pentanone	BDL	50
1,2-Dichloroethane	BDL	5.0	Tetrachloroethene	BDL	5.0
2-Butanone	BDL	50	Toluene	BDL	5.0
1,1,1-Trichloroethane	BDL	5.0	Chlorobenzene	BDL	5.0
Carbon Tetrachloride	BDL	5.0	Ethyl Benzene	BDL	5.0
Vinyl Acetate	BDL	50	Styrene	BDL	5.0
Bromodichloromethane	BDL	5.0	Total Xylenes	BDL	15
1,1,2,2-Tetrachloroethane	BDL	5.0			

## NOTES AND DEFINITIONS FOR THIS REPORT

All results Reported in micrograms/kilogram unless otherwise specified.

BDL=Below Specified Detection Limit

LOQ=Analytical Limit of Quantitation.

\* = Sample not Analyzed for this Compound.

Order # 94-02-106

02/23/94 17:54

TEST RESULTS BY SAMPLE

Page 7

Sample Description: RMD4TP10C1801 GRAB

Lab No: 04A

Test Description: Volatile Organics in Soil

Method: METHOD 8240

Test Code: M8240S

Collected: 02/09/94 14:50

Category: SOIL

VOLATILE ORGANICS IN SOIL BY METHOD 8240

UNITS ug/Kg

ANALYTE	RESULT	LOQ	ANALYTE	RESULT	LOQ
Chloromethane	BDL	10	1,2-Dichloropropane	BDL	5.0
Bromomethane	BDL	10	trans-1,3-Dichloropropene	BDL	5.0
Vinyl Chloride	BDL	10	Trichloroethene	BDL	5.0
Chloroethane	BDL	10	Dibromochloromethane	BDL	5.0
Methylene Chloride	BDL	5.0	1,1,2-Trichloroethane	BDL	5.0
Acetone	BDL	100	Benzene	BDL	5.0
Carbon Disulfide	BDL	100	cis-1,3-Dichloropropene	BDL	5.0
1,1-Dichloroethene	BDL	5.0	2-Chloroethyl Vinyl ether	BDL	10
1,1-Dichloroethane	BDL	5.0	Bromoform	BDL	5.0
trans-1,2-Dichloroethene	BDL	5.0	2-Hexanone	BDL	50
Chloroform	BDL	5.0	4-Methyl-2-Pentanone	BDL	50
1,2-Dichloroethane	BDL	5.0	Tetrachloroethene	BDL	5.0
2-Butanone	BDL	50	Toluene	BDL	5.0
1,1,1-Trichloroethane	BDL	5.0	Chlorobenzene	BDL	5.0
Carbon Tetrachloride	BDL	5.0	Ethyl Benzene	BDL	5.0
Vinyl Acetate	BDL	50	Styrene	BDL	5.0
Bromodichloromethane	BDL	5.0	Total Xylenes	BDL	15.0
1,1,2,2-Tetrachloroethane	BDL	5.0			

NOTES AND DEFINITIONS FOR THIS REPORT

All results Reported in micrograms/kilogram unless otherwise specified.

BDL=Below Specified Detection Limit

LOQ=Analytical Limit of Quantitation.

\* = Sample not Analyzed for this Compound.

Order # 94-02-106  
02/23/94 17:54

TEST METHODOLOGIES

Page 8

Volatile Organics in Soil analysis was performed according to EPA method 8240.

Mercury analysis was performed according to EPA SW-846 method 7471.

Silver analysis was performed according to EPA SW-846 method 7761.

Arsenic analysis was performed according to EPA SW-846 method 7060.

Barium analysis was performed according to EPA SW-846 method 7081.

Cadmium analysis was performed according to EPA SW-846 method 7131.

Chromium analysis was performed according to EPA SW-846 method 7191.

Lead analysis was performed according to EPA SW-846 method 7421.

Selenium analysis was performed according to EPA SW-846 method 7740.

**ANALYTICAL RESULTS FOR CLOSURE SAMPLES  
COLLECTED AT SITE 5**

9211 Burge Avenue, Richmond, VA 23237

client: ADVANCED SCIENCES, INC

Address: 165 Mitchell Road, Oak Ridge, TN 37830

Company contact: P. J. McMullen

Phone: 615/4831274

Submit Report to: D.J. McMullen

P.O. No.:

Submit Bill to:

Sampler: McMullen, P.J

ANALYSIS REQUESTED

Project ID/Location:

9750. K10 RICHMOND-VIRGINIA AIR NATIONAL GUARD-TANK FULL

## SAMPLE INFORMATION

**LAB ID  
(Lab Use)  
(Only)**

### Location

Date | Time

Time

$$\mathbf{z} \cdot \mathbf{o}$$

CONT.  
GRAB  
COMP.

## SAMPLE INFORMATION

Date | Time

Time

REMARKS:

9401058-01A	RMD5TP9H1801	01/06/94 1500	X	X	X	24hr TURNAROUND
02A	RMD5TP8G1801	01/06/94 1530	X	X	X	24hr TURNAROUND
03A	RMD5TP10G1801	01/06/94 1520	X	X	X	24hr TURNAROUND
04A	RMD5 PR 140601	01/06/94 1545	X	X	X	
05A	RMD5 PR 6A0601	01/06/94 1550	X	X	X	

**Samples Relinquished by:**

Date \_\_\_\_\_

Time

Samples Received by:

Date \_\_\_\_\_

Time

Reason for Trans.

**Preservative check in lab:**

Temp:

**pH check:**

**Preservatives added:**

**Comments:**

# ENVIRONMENTAL LABORATORIES INC.

9211 Burge Avenue, Richmond, VA 23237

## CHAIN OF CUSTODY

②

Client: ADVANCED SCIENCES INC

Address: 165 MITCHELL RD, Oak Ridge, TN 37830

Company Contact: McMullen, P.J.

Phone: 615/4831274 Submit Report to: McMullen, P.J.

P.O. No.:

Submit Bill to:

Sampler: McMullen, P.J.

### ANALYSIS REQUESTED

Project ID/Location:

9750-K10 - VANU-TANK Pull

LAB ID (Lab Use) (Only)	SAMPLE INFORMATION Location	C O M P			Date	Time	G R A B			N O.	C O N T.					REMARKS:
14D10TT-01	RMD5TP9F1801				01/07/94	0845				X	X	X	X	X	X	24hr TURNAROUND
02	RMD5TP9G2001				01/07/94	0920				X	X	X	X	X	X	
03	RMD5TP9B1801				01/07/94	1045				X	X	X	X	X	X	
04	RMD5TP10C1801				01/07/94	1135				X	X	X	X	X	X	
05	RMD5TP8C1801				01/07/94	1340				X	X	X	X	X	X	
06	RMD5TP9D1801				01/07/94	1430				X	X	X	X	X	X	
07	RMD5TP4H1801				01/07/94	1630				X	X	X	X	X	X	
08	RMD5TP5G1801				01/07/94	1645				X	X	X	X	X	X	
09	RMD5TP9C2001				01/07/94	1700				X	X	X	X	X	X	

Samples Relinquished by: \_\_\_\_\_ Date \_\_\_\_\_ Time \_\_\_\_\_ Reason for Trans. \_\_\_\_\_

P.J. McMullen 01/08/94 0650 McMullen 7/8/94 6:50

Preservative check in lab: \_\_\_\_\_ Temp: \_\_\_\_\_ pH check: \_\_\_\_\_ Preservatives added: \_\_\_\_\_

Comments:



# ENVIRONMENTAL LABORATORIES INC.

9211 Burge Avenue, Richmond, VA 23237

## CHAIN OF CUSTODY

Client: ADVANCED SCIENCES, INC Address: 135 Mitchell Road Oak Ridge, TN 37830

Company Contact: Mc Mullen, P.J. Phone: 615/4831274 Submit Report to: Mc Mullen

P.O. No.: Submit Bill to:

Sampler: Mc Mullen, P.J.

Project ID/Location:

9750.K10 VANG-TANK FILL

### ANALYSIS REQUESTED

REMARKS:

LAB ID  
(Lab Use)  
(Only)

### SAMPLE INFORMATION

Location

Date

Time

C O M P

G R A B

N O.

C O N T.

GRD 8015

DRB 8015

Samples Relinquished by:

Date

Time

Samples Received by:

Date

Time

Reason for Trans.

Preservative check in lab:

Temp:

pH check:

Preservatives added:

Comments:

ENVIRONMENTAL LABORATORIES INC.  
9211 Burge Avenue, Richmond, VA 23237

CHAIN OF CUSTODY

③

Client: ADVANCED SCIENCES, INC Address: 165 Mitchell Road, Oak Ridge, TN 37830  
Company Contact: Mc Mullen, P.J Phone: 615/4831274 Submit Report to: Mc Mullen, P.J  
P.O. No.: Submit Bill to:

Sampler: Mc Mullen, P.J. ANALYSIS REQUESTED

Project ID/Location:

9750-K10-VAN6-Trank Pull

LAB ID (Lab Use) (Only)	SAMPLE INFORMATION			Date	Time	C O M P	G R A B	N O.	REMARKS:				
	Location												
9401078-01A	RMD5 TP361801			01/08/94	0810		X		X				24hr TURNAROUND
9401078-02A	RMD5 TP4F1801			01/08/94	0910		X		X				
9401078-03A	RMD5 TP5C1801			01/08/94	1320		X		X				
9401078-04A	RMD5 TP4B1801			01/08/94	1340		X		X				
9401078-05A	RMD5 TP3C1801			01/08/94	1410		X		X				
9401078-06A	RMD5 TP4D1801			01/08/94	1515		X		X				

Samples Relinquished by:		Date	Time	Samples Received by:		Date	Time	Reason for Trans.	
D.J. Mc Mullen		01/08/94	1610	[Signature]		01/08/94	4:13		

Preservative check in lab: Temp: pH check: Preservatives added: Comments:

# ENVIRONMENTAL LABORATORIES INC.

9211 Burge Avenue, Richmond, VA 23237

## CHAIN OF CUSTODY

Client: ADVANCED SCIENCES, INC Address: 165 MITCHELL ROAD, DOCK RIDGE, TN 37830  
 Company Contact: Mc MULLEN, P.J Phone: 615/4831274 Submit Report to: Mc MULLEN, P.J.  
 P.O. No.: Submit Bill to:

Sampler: Mc MULLEN

Project ID/Location: 9750.K10 - VAN 6 Tank Full

LAB ID (Lab Use) (Only)	SAMPLE INFORMATION			Date	Time	ANALYSIS REQUESTED			REMARKS:	
	Location	C O M P				G R A B	N O.	C O N T.		
	RMD 5 AT 760701			1/11/94	0950					
	RMD 5 AT 660701			01/11/94	1130					24 hr turnaround
	RMD 5 AT 760701			01/11/94	1530					11
	<u>RMD 6</u>									11
	RMD 5 66 0701			01/10/94	1610					11

Samples Relinquished by:	Date	Time	Samples Received by:	Date	Time	Reason for Trans.
<u>P.J. Mc Mullen</u>	<u>01/12/94</u>	<u>1040</u>	<u>Jaycha J. Mullens</u>	<u>1/12/94</u>	<u>10:40</u>	

Preservative check in lab: Temp: \_\_\_\_\_ pH check: \_\_\_\_\_ Preservatives added: \_\_\_\_\_  
 Comments:

# ENVIRONMENTAL LABORATORIES INC.

9211 Burge Avenue, Richmond, VA 23237

CHAIN OF CUSTODY SAMPLE LOG (5)

Client: ADVANCED SCIENCES, INC Address: 165 Mitchell Road, Oak Ridge, TN 37830

Company Contact: Joe Hawk

Phone: 615/4831274

Submit Report to: Joe Hawk

P.O. No.:

Submit Bill to: ASI - Oak Ridge, ATTN: Joe Hawk

Sampler: Mc Mullen, P.J.

ANALYSIS REQUESTED

Project ID/Location:

9753 K10-VANG-TANK FILL SITE 4/5

LAB ID (Lab Use) (Only)	Location	SAMPLE INFORMATION		Date	Time	CONT.		REMARKS:
		C O M P	G R A B			C O M P	G R A B	
	RMD5FP11E0701		X	2/10/94	0930		X	ROUTINE TIME
	RMD5VP9E0701		X	2/10/94	0950		X	for TURNAROUND
	RMD5PC8E0701		X	2/10/94	1150		X	
	RMD5PC6E0701		X	2/10/94	1330		X	
	RMD5PR10E0401		X	2/10/94	1345		X	
	RMD5AS6H0701		X	2/10/94	1430		X	
								Do NOT NEED
								24 hr TURNAROUND

Samples Relinquished by:	Date	Time	Samples Received by:	Date	Time	Reason for Trans.
P.J. Mc Mullen	2/11/94	1215	Georgie Ross	11 Feb 94	1215	
Georgie Ross	14 Feb 94	1230	Georgie Ross	2/14/94	1227	
Georgie Ross	2/14/94	1335	Georgie Ross	2/14/94	1335	

Preservative check in lab:

Temp:

pH check:

Preservatives added:

Comments:

# ENVIRONMENTAL LABORATORIES INC.

9211 Burge Avenue, Richmond, VA 23237

## CHAIN OF CUSTODY

Client: ADVANCED SCIENCES, INC

Address: 165 Mitchell Road, Oak Ridge, TN 37830

Company Contact: Joe Hawk

Phone: 615/4831274 Submit Report to: Joe Hawk

P.O. No.:

Submit Bill to: ASI - Oak Ridge, ATTN: Joe Hawk

Sampler: McMullen, P.J

ANALYSIS REQUESTED

Project ID/Location:

9750-K10-VANG-TANK FILL, Site 4/5

LAB ID (Lab Use) (Only)	SAMPLE INFORMATION		Date		Time		C O M P		G R A B		N O.	REMARKS:					
	Location																
	RMD 5 PR 6F 0401		2/11/94		1000							✓	✓	✓	✓	✓	Routine
	RMD 5 PR 3E 0401		2/11/94		1020							✓	✓	✓	✓	✓	
	RMD 5 PR 6C 0401		2/11/94		1035							✓	✓	✓	✓	✓	Do Not NEED 24 hr turnaround

Samples Relinquished by:	Date	Time	Samples Received by:	Date	Time	Reason for Trans.
<u>P.J. McMullen</u>	<u>2/11/94</u>	<u>1215</u>	<u>Joseph W. Mikhlik</u>	<u>11 Feb 94</u>	<u>1215</u>	
<u>Joseph W. Mikhlik</u>	<u>14 Feb 94</u>	<u>1230</u>	<u>Georgie Ross</u>	<u>2/14/94</u>	<u>1227</u>	
<u>Georgie Ross</u>	<u>2/14/94</u>	<u>1336</u>	<u>Childress</u>	<u>2/14/94</u>	<u>1336</u>	

Preservative check in lab: Temp: \_\_\_\_\_ pH check: \_\_\_\_\_ Preservatives added: \_\_\_\_\_

Comments:

Advance Sciences Inc.  
6739 Academy Rd. NE  
Alberquerque, NM 87109  
  
Attn: Ellie Krueger  
Invoice Number:

Order #: 94-01-058  
Date: 01/19/94 11:36  
Work ID: 9750.K10 RICH,VA. A.N.G TANK  
Date Received: 01/07/94  
Date Completed: 01/18/94  
Client Code: 1103

Sampled by Advance Sciences

SAMPLE IDENTIFICATION

<u>Sample Number</u>	<u>Sample Description</u>
01	RMD5TP9H1801 GRAB
02	RMD5TP8G1801 GRAB
03	RMD5TP10G1801 GRAB

<u>Sample Number</u>	<u>Sample Description</u>
04	RMD5PR1H0601 GRAB
05	RMD5PR6A0601 GRAB

Mindy Baldwin  
Certified By

Order # 94-01-058  
01/19/94 11:36

TEST RESULTS BY SAMPLE

Sample: 01A	RMD5TP9H1801	GRAB	Collected: 01/06/94	Category: SOIL					
<u>Test Description</u>									
Diesel Range Organics									
			<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>		
			<5.0	5	mg/Kg	01/07/94	SN		
Sample: 01B	RMD5TP9H1801	GRAB	Collected: 01/06/94	Category: SOIL					
<u>Test Description</u>									
Gasoline Range Organics									
			<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>		
			<5.0	5	mg/Kg	01/07/94	JTS		
Sample: 02A	RMD5TP8G1801	GRAB	Collected: 01/06/94	Category: SOIL					
<u>Test Description</u>									
Diesel Range Organics									
			<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>		
			<5.0	5.0	mg/Kg	01/07/94	SN		
Sample: 02B	RMD5TP8G1801	GRAB	Collected: 01/06/94	Category: SOIL					
<u>Test Description</u>									
Gasoline Range Organics									
			<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>		
			<5.0	5	mg/Kg	01/07/94	JTS		
Sample: 03A	RMD5TP10G1801	GRAB	Collected: 01/06/94	Category: SOIL					
<u>Test Description</u>									
Diesel Range Organics									
			<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>		
			<5.0	5.0	mg/Kg	01/07/94	SN		
Sample: 03B	RMD5TP10G1801	GRAB	Collected: 01/06/94	Category: SOIL					
<u>Test Description</u>									
Gasoline Range Organics									
			<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>		
			<5.0	5	mg/Kg	01/07/94	JTS		
Sample: 04A	RMD5PR1H0601	GRAB	Collected: 01/06/94	Category: SOIL					
<u>Test Description</u>									
Diesel Range Organics									
			<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>		
			<5.0	5.0	mg/Kg	01/07/94	SN		



Order # 94-01-058  
01/19/94 11:36

TEST RESULTS BY SAMPLE

Sample: 04B	RMD5PR1H0601	GRAB	Collected: 01/06/94	Category: SOIL	
<u>Test Description</u>					
Gasoline Range Organics			<u>Result</u> <5.0	<u>Limit</u> 5	<u>Units</u> mg/Kg
					<u>Analyzed</u> 01/07/94
					<u>By</u> JTS
Sample: 05A	RMD5PR6A0601	GRAB	Collected: 01/06/94	Category: SOIL	
<u>Test Description</u>					
Diesel Range Organics			<u>Result</u> <5.0	<u>Limit</u> 5.0	<u>Units</u> mg/Kg
					<u>Analyzed</u> 01/07/94
					<u>By</u> SN
Sample: 05B	RMD5PR6A0601	GRAB	Collected: 01/06/94	Category: SOIL	
<u>Test Description</u>					
Gasoline Range Organics			<u>Result</u> <5.0	<u>Limit</u> 5	<u>Units</u> mg/Kg
					<u>Analyzed</u> 01/07/94
					<u>By</u> JTS



Order # 94-01-058  
01/18/94 15:38

Page 4  
TEST METHODOLOGIES

Diesel Range Organics in Soil analysis was performed according to EPA SW846  
Standard Methods, Method 8100.

Advance Sciences Inc.  
6739 Academy Rd. NE  
Alberquerque, NM 87109  
  
Attn: Ellie Krueger  
Invoice Number:

Order #: 94-01-077  
Date: 01/18/94 16:38  
Work ID: 9750-K10-VANG-TANK PULL  
Date Received: 01/08/94  
Date Completed: 01/18/94  
Client Code: 1103

Sampled by Advance Sciences

SAMPLE IDENTIFICATION

Sample Number	Sample Description
01	RMD5TP9F1801
02	RMD5TP9G2001
03	RMD5TP9B1801
04	RMD5TP10C1801
05	RMD5TP8C1801
06	RMD5TP9D1801
07	RMD5TP4H1801

Sample Number	Sample Description
08	RMD5TP5G1801
09	RMD5TP9C2001
10	RMD5PR3H0601
11	RMD5PR6H0601
12	RMD5PR8H0601
13	RMD5PR10H0601

Mindy Baldwin  
Certified By

Order # 94-01-077  
01/18/94 16:38

TEST RESULTS BY SAMPLE

Sample: 01A	RMD5TP9F1801	Collected: 01/07/94	Category: SOIL		
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5	mg/Kg	01/08/94 JTS
Sample: 01B	RMD5TP9F1801	Collected: 01/07/94	Category: SOIL		
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		7.1	5	mg/Kg	01/08/94 SN
Sample: 02A	RMD5TP9G2001	Collected: 01/07/94	Category: SOIL		
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5	mg/Kg	01/08/94 JTS
Sample: 02B	RMD5TP9G2001	Collected: 01/07/94	Category: SOIL		
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		33.87	5	mg/Kg	01/08/94 SN
Sample: 03A	RMD5TP9B1801	Collected: 01/07/94	Category: SOIL		
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5	mg/Kg	01/08/94 JTS
Sample: 03B	RMD5TP9B1801	Collected: 01/07/94	Category: SOIL		
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5.0	mg/Kg	01/08/94 SN
Sample: 04A	RMD5TP10C1801	Collected: 01/07/94	Category: SOIL		
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		145	5	mg/Kg	01/08/94 JTS

Order # 94-01-077  
01/18/94 16:38

Page 3

## TEST RESULTS BY SAMPLE

Sample: 04B RMD5TP10C1801

Collected: 01/07/94 Category: SOIL

Test Description  
Diesel Range OrganicsResult  
230.5Limit  
50Units  
mg/KgAnalyzed  
01/08/94By  
SN

Sample: 05A RMD5TP8C1801

Collected: 01/07/94 Category: SOIL

Test Description  
Gasoline Range OrganicsResult  
<5.0Limit  
5Units  
mg/KgAnalyzed  
01/08/94By  
JTS

Sample: 05B RMD5TP8C1801

Collected: 01/07/94 Category: SOIL

Test Description  
Diesel Range OrganicsResult  
<5.0Limit  
5.0Units  
mg/KgAnalyzed  
01/08/94By  
SN

Sample: 06A RMD5TP9D1801

Collected: 01/07/94 Category: SOIL

Test Description  
Gasoline Range OrganicsResult  
<5.0Limit  
5Units  
mg/KgAnalyzed  
01/08/94By  
JTS

Sample: 06B RMD5TP9D1801

Collected: 01/07/94 Category: SOIL

Test Description  
Diesel Range OrganicsResult  
<5.0Limit  
5.0Units  
mg/KgAnalyzed  
01/08/94By  
SN

Sample: 07A RMD5TP4H1801

Collected: 01/07/94 Category: SOIL

Test Description  
Gasoline Range OrganicsResult  
<5.0Limit  
5Units  
mg/KgAnalyzed  
01/08/94By  
JTS

Sample: 07B RMD5TP4H1801

Collected: 01/07/94 Category: SOIL

Test Description  
Diesel Range OrganicsResult  
<5.0Limit  
5.0Units  
mg\KgAnalyzed  
01/08/94By  
SN

Order # 94-01-077  
01/18/94 16:38

TEST RESULTS BY SAMPLE

<b>Sample: 08A</b>	<b>RMD5TP5G1801</b>	<b>Collected: 01/07/94 Category: SOIL</b>			
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5	mg/Kg	01/08/94 JTS
<b>Sample: 08B</b>	<b>RMD5TP5G1801</b>	<b>Collected: 01/07/94 Category: SOIL</b>			
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5.0	mg/Kg	01/08/94 SN
<b>Sample: 09A</b>	<b>RMD5TP9C2001</b>	<b>Collected: 01/07/94 Category: SOIL</b>			
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		9.9	5	mg/Kg	01/08/94 JTS
<b>Sample: 09B</b>	<b>RMD5TP9C2001</b>	<b>Collected: 01/07/94 Category: SOIL</b>			
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		92.2	50	mg/Kg	01/08/94 SN
<b>Sample: 10A</b>	<b>RMD5PR3H0601</b>	<b>Collected: 01/07/94 Category: SOIL</b>			
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5	mg/Kg	01/08/94 JTS
<b>Sample: 10B</b>	<b>RMD5PR3H0601</b>	<b>Collected: 01/07/94 Category: SOIL</b>			
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5.0	mg/Kg	01/08/94 SN
<b>Sample: 11A</b>	<b>RMD5PR6H0601</b>	<b>Collected: 01/07/94 Category: SOIL</b>			
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u> <u>By</u>
		<5.0	5	mg/Kg	01/08/94 JTS

Order # 94-01-077  
01/18/94 16:38

Page 5

TEST RESULTS BY SAMPLE

Sample: 11B RMD5PR6H0601

Collected: 01/07/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
<5.0	5.0	mg/Kg	01/08/94	SN

Sample: 12A RMD5PR8H0601

Collected: 01/07/94 Category: SOIL

Test Description  
Gasoline Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
<5.0	5	mg/Kg	01/08/94	JTS

Sample: 12B RMD5PR8H0601

Collected: 01/07/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
<5.0	5.0	mg/Kg	01/08/94	SN

Sample: 13A RMD5PR10H0601

Collected: 01/07/94 Category: SOIL

Test Description  
Gasoline Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
<5.0	5	mg/Kg	01/08/94	JTS

Sample: 13B RMD5PR10H0601

Collected: 01/07/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
<5.0	5.0	mg/Kg	01/08/94	SN

Order # 94-01-077  
01/18/94 15:39

Page 6

TEST METHODOLOGIES

Diesel Range Organics in Soil analysis was performed according to EPA SW846  
Standard Methods, Method 8100.

Advance Sciences Inc.  
6739 Academy Rd. NE  
Alberquerque, NM 87109  
  
Attn: Ellie Krueger  
Invoice Number:

Order #: 94-01-078  
Date: 01/18/94 16:38  
Work ID: 9750K10-VANG-TANK PULL  
Date Received: 01/08/94  
Date Completed: 01/18/94  
Client Code: 1103

Sampled by Advance Sciences

SAMPLE IDENTIFICATION

<u>Sample Number</u>	<u>Sample Description</u>
01	RMD5TP3G1801
02	RMD5TP4F1801
03	RMD5TP5C1801

<u>Sample Number</u>	<u>Sample Description</u>
04	RMD5TP4B1801
05	RMD5TP3C1801
06	RMD5TP4D1801

Mindy Baldwin  
Certified By



Order # 94-01-078  
01/18/94 16:38

TEST RESULTS BY SAMPLE

<b>Sample: 01A RMD5TP3G1801</b>		<b>Collected: 01/08/94 Category: SOIL</b>			
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed By</u>
Gasoline Range Organics		BDL	5	mg/Kg	01/08/94 JTS
<b>Sample: 01B RMD5TP3G1801</b>		<b>Collected: 01/08/94 Category: SOIL</b>			
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed By</u>
Diesel Range Organics		<5.0	5.0	mg/Kg	01/09/94 SN
<b>Sample: 02A RMD5TP4F1801</b>		<b>Collected: 01/08/94 Category: SOIL</b>			
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed By</u>
Gasoline Range Organics		BDL	5	mg/Kg	01/08/94 JTS
<b>Sample: 02B RMD5TP4F1801</b>		<b>Collected: 01/08/94 Category: SOIL</b>			
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed By</u>
Diesel Range Organics		64.8	50	mg/Kg	01/09/94 SN
<b>Sample: 03A RMD5TP5C1801</b>		<b>Collected: 01/08/94 Category: SOIL</b>			
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed By</u>
Gasoline Range Organics		BDL	5	mg/Kg	01/08/94 JTS
<b>Sample: 03B RMD5TP5C1801</b>		<b>Collected: 01/08/94 Category: SOIL</b>			
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed By</u>
Diesel Range Organics		5.3	5.0	mg/Kg	01/09/94 SN
<b>Sample: 04A RMD5TP4B1801</b>		<b>Collected: 01/08/94 Category: SOIL</b>			
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed By</u>
Gasoline Range Organics		23.7	5	mg/Kg	01/08/94 JTS

Order # 94-01-078  
01/18/94 16:38

## TEST RESULTS BY SAMPLE

Page 3

Sample: 04B RMD5TP4B1801

Collected: 01/08/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
32.56	5.0	mg/Kg	01/09/94	SN

Sample: 05A RMD5TP3C1801

Collected: 01/08/94 Category: SOIL

Test Description  
Gasoline Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
BDL	5	mg/Kg	01/08/94	JTS

Sample: 05B RMD5TP3C1801

Collected: 01/08/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
14.7	5.0	mg/Kg	01/09/94	SN

Sample: 06A RMD5TP4D1801

Collected: 01/08/94 Category: SOIL

Test Description  
Gasoline Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
31.5	5	mg/Kg	01/08/94	JTS

Sample: 06B RMD5TP4D1801

Collected: 01/08/94 Category: SOIL

Test Description  
Diesel Range Organics

<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>	<u>By</u>
57.5	50.0	mg/Kg	01/09/94	SN

Order # 94-01-078  
01/18/94 15:39

Page 4

TEST METHODOLOGIES

Diesel Range Organics in Soil analysis was performed according to EPA SW846  
Standard Methods, Method 8100.

Advance Sciences Inc.  
6739 Academy Rd. NE  
Alberquerque, NM 87109  
  
Attn: Ellie Krueger  
Invoice Number:

Order #: 94-01-111  
Date: 01/18/94 16:39  
Work ID: 9750.K10-VANG TANK PULL  
Date Received: 01/12/94  
Date Completed: 01/18/94  
Client Code: 1103

Sampled by Advance Sciences

SAMPLE IDENTIFICATION

Sample Number	Sample Description
01	RMD5 AT7G0701 GRAB
02	RMD5 AT 6C0701 GRAB

Sample Number	Sample Description
03	RMD5 AT 7C0701 GRAB
04	RMD56G0701 GRAB

AT

Mindy Baldwin  
Certified By

Order # 94-01-111  
01/18/94 16:39

TEST RESULTS BY SAMPLE

Sample: 01A	RMD5 AT7G0701 GRAB	Collected: 01/11/94	Category: SOIL	
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u> <5.0	<u>Limit</u> 5	<u>Units</u> mg/Kg
				<u>Analyzed</u> 01/12/94
				<u>By</u> JTS
Sample: 01B	RMD5 AT7G0701 GRAB	Collected: 01/11/94	Category: SOIL	
<u>Test Description</u>	Diesel Range Organics	<u>Result</u> <5.0	<u>Limit</u> 5.0	<u>Units</u> mg/Kg
				<u>Analyzed</u> 01/12/94
				<u>By</u> SN
Sample: 02A	RMD5 AT 6C0701 GRAB	Collected: 01/11/94	Category: SOIL	
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u> <5.0	<u>Limit</u> 5	<u>Units</u> mg/Kg
				<u>Analyzed</u> 01/12/94
				<u>By</u> JTS
Sample: 02B	RMD5 AT 6C0701 GRAB	Collected: 01/11/94	Category: SOIL	
<u>Test Description</u>	Diesel Range Organics	<u>Result</u> <5.0	<u>Limit</u> 5.0	<u>Units</u> mg/Kg
				<u>Analyzed</u> 01/12/94
				<u>By</u> SN
Sample: 03A	RMD5 AT 7C0701 GRAB	Collected: 01/11/94	Category: SOIL	
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u> <5.0	<u>Limit</u> 5	<u>Units</u> mg/Kg
				<u>Analyzed</u> 01/12/94
				<u>By</u> JTS
Sample: 03B	RMD5 AT 7C0701 GRAB	Collected: 01/11/94	Category: SOIL	
<u>Test Description</u>	Diesel Range Organics	<u>Result</u> <5.0	<u>Limit</u> 5.0	<u>Units</u> mg/Kg
				<u>Analyzed</u> 01/12/94
				<u>By</u> SN
Sample: 04A	RMD56G0701 GRAB	Collected: 01/10/94	Category: SOIL	
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u> <5.0	<u>Limit</u> 5	<u>Units</u> mg/Kg
				<u>Analyzed</u> 01/12/94
				<u>By</u> JTS

Order # 94-01-111  
01/18/94 16:39

Page 3

TEST RESULTS BY SAMPLE

Sample: 04B RMD56G0701 GRAB Collected: 01/10/94 Category: SOIL

Test Description	Result	Limit	Units	Analyzed	By
Diesel Range Organics	<5.0	5.0	mg/Kg	01/12/94	SN

Order # 94-01-111  
01/18/94 15:38

Page 4  
TEST METHODOLOGIES

Diesel Range Organics in Soil analysis was performed according to EPA SW846  
Standard Methods, Method 8100.

Advance Sciences Inc.  
165 Mitchell Road  
Oak Ridge, TN 37830

Attn: P. J. McMullen

Purchase Order: Subcontract #9750-3-94  
Invoice Number:

Sampled by Advance Sciences

Order #: 94-02-141  
Date: 02/21/94 12:54  
Work ID: 9750K10-VANG-TANKPULL SITE4/5  
Date Received: 02/14/94  
Date Completed: 02/17/94

Client Code: 1103

SAMPLE IDENTIFICATION

Sample Number	Sample Description
01	RMD5FP11E0701 GRAB
02	RMD5VP9E0701 GRAB
03	RMD5PC8E0701 GRAB

Sample Number	Sample Description
04	RMD5PC6E0701 GRAB
05	RMD5PR10E0401 GRAB
06	RMD5AS6H0701 GRAB

Mindy Baldwin  
Certified By



Order # 94-02-141  
02/21/94 12:54

Page 2

## TEST RESULTS BY SAMPLE

Sample: 01A	RMD5FP11E0701 GRAB	Collected: 02/10/94	Category: SOIL
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u> BDL	<u>Limit</u> 5
		<u>Units</u> mg/Kg	<u>Analyzed</u> 02/17/94
			<u>By</u> EVY
Sample: 01B	RMD5FP11E0701 GRAB	Collected: 02/10/94	Category: SOIL
<u>Test Description</u>	Diesel Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0
		<u>Units</u> mg/Kg	<u>Analyzed</u> 02/16/94
			<u>By</u> SN
Sample: 02A	RMD5VP9E0701 GRAB	Collected: 02/10/94	Category: SOIL
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0
		<u>Units</u> mg/Kg	<u>Analyzed</u> 02/16/94
			<u>By</u> EVY
Sample: 02B	RMD5VP9E0701 GRAB	Collected: 02/10/94	Category: SOIL
<u>Test Description</u>	Diesel Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0
		<u>Units</u> mg/Kg	<u>Analyzed</u> 02/16/94
			<u>By</u> SN
Sample: 03A	RMD5PC8E0701 GRAB	Collected: 02/10/94	Category: SOIL
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0
		<u>Units</u> mg/Kg	<u>Analyzed</u> 02/16/94
			<u>By</u> EVY
Sample: 03B	RMD5PC8E0701 GRAB	Collected: 02/10/94	Category: SOIL
<u>Test Description</u>	Diesel Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0
		<u>Units</u> mg/Kg	<u>Analyzed</u> 02/16/94
			<u>By</u> SN
Sample: 04A	RMD5PC6E0701 GRAB	Collected: 02/10/94	Category: SOIL
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u> BDL	<u>Limit</u> 5.0
		<u>Units</u> mg/Kg	<u>Analyzed</u> 02/16/94
			<u>By</u> EVY

Order # 94-02-141  
02/21/94 12:54

TEST RESULTS BY SAMPLE

Sample: 04B	RMD5PC6E0701 GRAB	Collected: 02/10/94	Category: SOIL		
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>
Diesel Range Organics		BDL	5.0	mg/Kg	02/16/94
					By SN
Sample: 05A	RMD5PR10E0401 GRAB	Collected: 02/10/94	Category: SOIL		
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>
Gasoline Range Organics		BDL	5.0	mg/Kg	02/16/94
					By EVY
Sample: 05B	RMD5PR10E0401 GRAB	Collected: 02/10/94	Category: SOIL		
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>
Diesel Range Organics		BDL	5.0	mg/Kg	02/16/94
					By SN
Sample: 06A	RMD5AS6H0701 GRAB	Collected: 02/10/94	Category: SOIL		
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>
Gasoline Range Organics		BDL	5.0	mg/Kg	02/16/94
					By EVY
Sample: 06B	RMD5AS6H0701 GRAB	Collected: 02/10/94	Category: SOIL		
<u>Test Description</u>		<u>Result</u>	<u>Limit</u>	<u>Units</u>	<u>Analyzed</u>
Diesel Range Organics		BDL	5.0	mg/Kg	02/16/94
					By SN

Order # 94-02-141  
02/21/94 12:54

Page 4

TEST METHODOLOGIES

Diesel Range Organics in Soil analysis was performed according to EPA SW846  
Standard Methods, Method 8100.

Advance Sciences Inc.  
165 Mitchell Road  
Oak Ridge, TN 37830

Attn: P. J. McMullen

Purchase Order: Subcontract #9750-3-94  
Invoice Number:

Order #: 94-02-142  
Date: 02/21/94 12:54  
Work ID: 9750K10-VANG-TANKPULL SITE4/5  
Date Received: 02/14/94  
Date Completed: 02/17/94

Client Code: 1103

Sampled by Advance Sciences

SAMPLE IDENTIFICATION

Sample Number	Sample Description
01	RMD5PR6F0401 GRAB
02	RMD5PR3E0401 GRAB

Sample Number	Sample Description
03	RMD5PR6C0401 GRAB

Mindy Baldwin  
Certified By

Order # 94-02-142  
02/21/94 12:54

TEST RESULTS BY SAMPLE

<b>Sample: 01A</b>	<b>RMD5PR6F0401 GRAB</b>	<b>Collected: 02/11/94 Category: SOIL</b>		
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>
		BDL	5.0	mg/Kg
				<u>Analyzed</u>
				02/16/94
				<u>By</u>
				EVY
<b>Sample: 01B</b>	<b>RMD5PR6F0401 GRAB</b>	<b>Collected: 02/11/94 Category: SOIL</b>		
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>
		BDL	5.0	mg\Kg
				<u>Analyzed</u>
				02/16/94
				<u>By</u>
				SN
<b>Sample: 02A</b>	<b>RMD5PR3E0401 GRAB</b>	<b>Collected: 02/11/94 Category: SOIL</b>		
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>
		BDL	5.0	mg/Kg
				<u>Analyzed</u>
				02/16/94
				<u>By</u>
				EVY
<b>Sample: 02B</b>	<b>RMD5PR3E0401 GRAB</b>	<b>Collected: 02/11/94 Category: SOIL</b>		
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>
		BDL	5.0	mg\Kg
				<u>Analyzed</u>
				02/16/94
				<u>By</u>
				SN
<b>Sample: 03A</b>	<b>RMD5PR6C0401 GRAB</b>	<b>Collected: 02/11/94 Category: SOIL</b>		
<u>Test Description</u>	Gasoline Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>
		BDL	5.0	mg/Kg
				<u>Analyzed</u>
				02/16/94
				<u>By</u>
				EVY
<b>Sample: 03B</b>	<b>RMD5PR6C0401 GRAB</b>	<b>Collected: 02/11/94 Category: SOIL</b>		
<u>Test Description</u>	Diesel Range Organics	<u>Result</u>	<u>Limit</u>	<u>Units</u>
		BDL	5.0	mg\Kg
				<u>Analyzed</u>
				02/16/94
				<u>By</u>
				SN

Order # 94-02-142  
02/21/94 12:54

Page 3

TEST METHODOLOGIES

Diesel Range Organics in Soil analysis was performed according to EPA SW846  
Standard Methods, Method 8100.

**LABORATORY QUALITY CONTROL DATA**

# ENVIRONMENTAL LABORATORIES INC.

Certified

Drinking Water Laboratory  
Virginia Dept. General Services

Approved

Virginia Dept. Environmental Quality  
Water Division

Accredited

American Industrial Hygiene  
Association

U.S. Dept. Commerce  
National Voluntary Laboratory  
Accreditation Program


May 6, 1994

Advanced Sciences, Inc.  
Attn: Mr. Joseph Hawk (9750.K10)  
165 Mitchell Road  
Oak Ridge, Tennessee 37830-7919

Dear Sir:

The laboratory quality control data required under our recent contract with your firm is enclosed. Please let me know if you have any questions or comments.

Sincerely,



Terry W. Hall, CIH  
Quality Assurance Coordinator




**QA/QC REPORT  
for  
ADVANCE SCIENCES**

Work Orders

94-01-058  
94-01-077  
94-01-078  
94-01-111  
94-01-225  
94-01-245  
94-02-106  
94-02-141  
94-02-142

Submitted by: \_\_\_\_\_

  
Terry W. Hall, CIH  
Quality Assurance Coordinator

May 6, 1994

## QA/QC REPORT TABLE OF CONTENTS

**Client:** Advance Sciences  
**Project:** 9750-K10-VANG Tank Pull  
**Report Date:** 05/06/94

	page #
Analytical Run Summary	1
Matrix Spikes and Matrix Spike Duplicates	2 - 6
Blanks	7 - 12

# ENVIRONMENTAL LABORATORIES INC.

## QA/QC REPORT ANALYTICAL RUN SUMMARY

Report Date: 05/06/94

Work Order #	Analysis	Run Date/Time	Instrument
9401058	DRO	1/7/94	GC01
	GRO	1/7/94	GC03
9401077	DRO	1/8/94	GC01
	GRO	1/8/94	GC03
	GRO	1/9/94	GC03
9401078	DRO	1/9/94	GC01
	GRO	1/8/94	GC03
	GRO	1/9/94	GC03
9401111	DRO	1/12-13/94	GC01
	GRO	1/12/94	GC03
9401225	DRO	1/27/94	GC01
	GRO	1/27-29/94	GC03
9401245	DRO	1/29/94	GC01
	GRO	1/27-29/94	GC03
9402106	Arsenic	2/17/94 09:19	AA_G2
	Arsenic	4/28/94 16:49	AA_G2
	Barium	2/23/94 09:17	AA_G2
	Chromium	2/17/94 16:59	AA_G2
	Lead	2/20/94 14:29	AA_G2
	Mercury	2/18/94 16:25	AA_CV
	Selenium	2/18/94 11:37	AA_G2
	Silver	2/15/94 08:50	AA_G2
	Volatiles	2/14/94 11:58	MS01
	Volatiles	2/16/94 15:03	MS01
9402141	DRO	2/16/94	GC01
	GRO	2/16-17/94	GC03
9402142	DRO	2/16/94	GC01
	GRO	2/16-17/94	GC03

# ENVIRONMENTAL LABORATORIES INC.

QA/QC REPORT  
MATRIX SPIKES, MATRIX SPIKE DUPLICATES  
Report Date: 05/06/94

Run Date/Time:		2/18/94 16:25		Instrument: AA_CV		Analyst: BZ		Units: mg/L	
Method:		AAS Cold Vapor							
Sample #		Analyte – Matrix	Original Result	Spike Amount	Spike Result	Recovery ( % )	Limits	RPD	Limit
9402122–01A	KM	Hg – TCLP	0.00005	0.002	0.00222	108.5	75–125		
9402122–01A	KMD	Hg – TCLP	0.00005	0.002	0.00219	107.0	75–125	1.4	20
9402066–02M	KM	Hg – Water	0.0001	0.002	0.00214	102.0	80–120		
9402066–02M	KMD	Hg – Water	0.0001	0.002	0.00204	97.0	80–120	4.8	20
9402106–04B	KM	Hg – Soil	0.00014	0.002	0.00235	110.5	75–125		
9402106–04B	KMD	Hg – Soil	0.00014	0.002	0.00218	102.0	75–125	7.5	20
9402176–01A	KM	Hg – TCLP	0.00006	0.002	0.00232	113.0	75–125		

Run Date/Time:		2/17/94 16:59	Instrument: AA_G2		Analyst: MH		Units: mg/L		
Method:		AAS Furnace							
Sample #		Analyte-Matrix	Original Result	Spike Amount	Spike Recovery Result ( % )		Limits	RPD	Limit
9402073-01A	KM	Cr - Oil	0.0036	0.002	0.0054	90.0	75-125		
9402073-01A	KMD	Cr - Oil	0.0036	0.002	0.0054	90.0	75-125	0	20
9402095-02C	KM	Cr - Water	0.0008	0.002	0.0026	90.0	80-120		
9402095-02C	KMD	Cr - Water	0.0008	0.002	0.0025	85.0	80-120	3.9	20
9402110-02A	KM	Cr - Oil	0.0071	0.0025	0.0096	100.0	75-125		
9402110-05A	KM	Cr - Oil	0.0044	0.002	0.0069	125.0	75-125		
9402110-05A	KMD	Cr - Oil	0.0044	0.002	0.006	80.0	75-125	14	20
9402130-01A	KM	Cr - Water	0.0056	0.0025	0.0077	84.0	80-120		
9402054-05D	KM	Cr - Water	0.0034	0.0025	0.0055	84.0	80-120		
9402106-03B	KM	Cr - Soil	0.0061	0.0025	0.0082	84.0	75-125		

Run Date/Time:		2/15/94 08:50	Instrument: AA_G2		Analyst: MH		Units: mg/L		
Method:		AAS Furnace							
Sample #		Analyte-Matrix	Original Result	Spike Amount	Spike Recovery Result ( % )		Limits	RPD	Limit
9402029-03A	KM	Ag - Water	0.003	0.002	0.00523	111.5	80-120		
9402029-03A	KMD	Ag - Water	0.003	0.002	0.00454	77.0	80-120	14.1	20
9402106-02B	KM	Aq - Soil	0.00015	0.0033	0.00268	76.7	75-125		

Run Date/Time:		2/17/94 09:19		Instrument: AA_G2		Analyst: MH		Units: mg/L	
Method:		AAS Furnace							
Sample #		Analyte-Matrix		Original Result	Spike Amount	Spike Recovery Result ( % ) Limits		RPD Limit	
9402061--01F	KM	As - Water		0.0023	0.025	0.028	102.8	80-120	
9402066--02M	KMD	As - Water		0.0023	0.02	0.0204	90.5	80-120	
9402066--02M	KMD	As - Water		0.0023	0.02	0.0215	96.0	80-120	5.3 20
9402073--01	KM	As - Oil		0.0014	0.02	0.0237	111.5	75-125	
9402073--01	KMD	As - Oil		0.0014	0.02	0.0207	96.5	75-125	13.5 20
9402050--01E	KM	As - Soil		0.0018	0.025	0.023	84.8	75-125	
9402106--04B	KM	As - Soil		0.0134	0.02	0.0367	116.5	75-125	
9402106--04B	KMD	As - Soil	1	0.0134	0.02	0.021	38.0	75-125	54.4 20
9402110--01A	KM	As - Oil		0.0025	0.025	0.0289	105.6	75-125	
9402110--05A	KM	As - Oil		BDL	0.02	0.0209	104.5	75-125	
9402110--05A	KMD	As - Oil		BDL	0.02	0.0204	102.0	75-125	2.4 20

<sup>1</sup> Analysis was repeated 4/28/94. Subsequent recovery acceptable.

# ENVIRONMENTAL LABORATORIES INC.

QA/QC REPORT  
MATRIX SPIKES, MATRIX SPIKE DUPLICATES  
Report Date: 05/06/94

Run Date/Time:		2/20/94 14:29		Instrument: AA_G2		Analyst: MH		Units: mg/L	
Method:		AAS Furnace							
Sample #		Analyte-Matrix	Original Result	Spike Amount	Spike Recovery Result ( % ) Limits		RPD	Limit	
9402087-01B	KM	Pb - Water	0.0034	0.02	0.0244	105.0 80-120			
9402087-01B	KMD	Pb - Water	0.0034	0.02	0.0238	102.0 80-120	2.5	20	
9402095-02C	KM	Pb - Water	0.0024	0.02	0.0227	101.5 80-120			
9402095-02C	KMD	Pb - Water	0.0024	0.02	0.0193	84.5 80-120	16.2	20	
9402117-01A	KM	Pb - Water	0.0183	0.025	0.0422	95.6 80-120			
9402131-01A	KM	Pb - Water	0.0012	0.025	0.0244	92.8 80-120			
9402106-02B	KM	Pb - Soil	0.0719	0.025	0.098	104.4 75-125			
9402106-04B	KM	Pb - Soil	0.0654	0.02	0.0844	95.0 75-125			
9402106-04B	KMD	Pb - Soil	0.0654	0.02	0.0841	93.5 75-125	0.4	20	
9402110-04A	KM	Pb - Oil	0.0743	0.025	0.0957	85.6 75-125			
9402110-05A	KM	Pb - Oil 1	0.0643	0.02	0.0954	128.7 75-125			
9402110-05A	KMD	Pb - Oil 1	0.0643	0.02	0.073	70.3 75-125	26.6	20	
1 Acceptable performance limits under evaluation at time of analysis.									

<sup>1</sup> Acceptable performance limits under evaluation at time of analysis.

Run Date/Time:	2/18/94 11:37	Instrument:	AA_G2	Analyst:	MH	Units:	mg/L
Method:	AAS Furnace						
Sample #	Analyte—Matrix	Original Result	Spike Amount	Spike Recovery Result ( % )	Limits	RPD Limit	
9402106—04B KM	Se — Soil	BDL	0.025	0.0231	92.4 75—125		

Run Date/Time:		2/23/94 09:17		Instrument: AA_G2		Analyst: MH		Units: mg/L	
Method:		AAS Furnace							
Sample #		Analyte-Matrix	Original Result	Spike Amount	Spike Result	Recovery ( % )	Limits	RPD	Limit
9402106-03B	KM	Ba - Soil	0.064	0.025	0.093	116.0	75-125		
9402106-04B	KM	Ba - Soil	0.098	0.02	0.107	45.0	75-125		
9402106-04B	KMD	Ba - Soil	0.098	0.02	0.033	42.5	75-125	105.	20
9402177-03A	KM	Ba - Water	0.068	0.025	0.099	124.0	80-120		
9402178-01A	KM	Ba - Water	0.011	0.02	0.031	100.0	80-120		
9402178-01A	KMD	Ba - Water	0.011	0.02	0.032	105.0	80-120	3.2	20

Run Date/Time:		2/21/94 15:57		Instrument: AA_G2		Analyst: MH		Units: mg/L	
Method:		AAS Furnace							
Sample #		Analyte – Matrix		Original Result	Spike Amount	Spike Recovery Result ( % ) Limits		RPD Limit	
9402106–04B	KM	Cd – Soil	<sup>1</sup>	0.00029	0.002	0.00322	132.0 75–125		
9402106–04B	KMD	Cd – Soil	<sup>1</sup>	0.00029	0.002	0.00325	133.5 75–125	0.9	20
9402110–01A	KM	Cd – Oil		0.00171	0.002	0.0042	124.5 75–125		
9402110–05A	KM	Cd – Oil	<sup>2</sup>	0.00165	0.0005	0.00195	32.5 75–125		
9402110–05A	KMD	Cd – Oil	<sup>2</sup>	0.00165	0.0005	0.0016	17.5 75–125	19.7	20
<sup>1</sup> Analysis was repeated by Standard Additions									
<sup>2</sup> Spike recovery masked by high dilution factor.									

<sup>1</sup> Analysis was repeated by Standard Additions

<sup>2</sup> Spike recovery masked by high dilution factor.

# ENVIRONMENTAL LABORATORIES INC.

QA/QC REPORT  
MATRIX SPIKES, MATRIX SPIKE DUPLICATES  
Report Date: 05/06/94

Run Date/Time:		4/28/94 1649		Instrument: AA_G2		Analyst: MH		Units: mg/L	
Method:		AAS Furnace							
Sample #		Analyte—Matrix	Original Result	Spike Amount	Spike Recovery Result	( % )	Limits	RPD Limit	
9402106—04B KM		As — Soil	0.0128	0.02	0.0323	97.5	75—125		
9402106—04B KMD		As — Soil	0.0128	0.02	0.0334	103.0	75—125	3.3	20

Run Date/Time:		2/16/94		Instrument: MS_01		Analyst: EVY		Units: ug/kg	
Method:		8240							
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result	( % )	Limits	RPD	Limit
9402106-01A	KM	1,1-Dichloroethene	BDL	50	77.6	155.2	59-172		
9402106-01A	KMD		BDL	50	79.6	159.2		2.5	22
9402106-01A	KM	Trichloroethene	BDL	50	45.9	91.8	62-137		
9402106-01A	KMD		BDL	50	46	92.0		0.2	24
9402106-01A	KM	Benzene	BDL	50	55.9	111.8	66-142		
9402106-01A	KMD		BDL	50	55.6	111.2		0.5	21
9402106-01A	KM	Toluene	BDL	50	48.7	97.4	59-139		
9402106-01A	KMD		BDL	50	49	98.0		0.6	21
9402106-01A	KM	Chlorobenzene	BDL	50	48.8	97.6	60-133		
9402106-01A	KMD		BDL	50	48.9	97.8		0.2	31

Run Date/Time: 1/7/94			Instrument: GC_03		Analyst: TS		Units: mg/kg	
Method: GRO								
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result ( % )		Limits	RPD Limit
9401058-01	KM	GRO	< 5	0.25	0.26	104.0	none	
	KMD	GRO	< 5	0.25	0.24	96.0	none	8 none

Run Date/Time: 1/8/94			Instrument: GC_03		Analyst: TS		Units: mg/kg	
Method: GRO								
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result ( % )		Limits	RPD Limit
9401078-01	KM	GRO	< 5	0.25	0.257	102.8	none	
	KMD	GRO	< 5	0.25	0.24	96.0	none	6.8 none

Run Date/Time: 1/9/94			Instrument: GC_03		Analyst: MB		Units: mg/kg	
Method: GRO								
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result ( % )		Limits	RPD Limit
9401078-01	KM	GRO	< 5	0.25	0.215	86.0	none	
(re-run)	KMD	GRO	< 5	0.25	0.284	113.6	none	27.7 none

Run Date/Time: 1/12/94			Instrument: GC_03		Analyst: TS		Units: mg/kg	
Method: GRO								
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result ( % )		Limits	RPD Limit
9401111-01		KM GRO	< 5	0.25	0.24	96.0	none	
		KMD GRO	< 5	0.25	0.29	116.0	none	18.9 none

# ENVIRONMENTAL LABORATORIES INC.

## MATRIX SPIKES, MATRIX SPIKE DUPLICATES

Report Date: 05/06/94

Run Date/Time:		1/27-29/94		Instrument: GC_03		Analyst: MB		Units: mg/kg	
Method:		GRO							
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result	( % )	Limits	RPD Limit	
9401245-02	KM	GRO	< 5	0.25	0.188	75.2	none		
	KMD	GRO	< 5	0.25	0.175	70.0	none	7.2 none	

Run Date/Time:		2/16-17/94		Instrument: GC_03		Analyst: EVY		Units: mg/kg	
Method:		GRO							
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result	( % )	Limits	RPD Limit	
9402141-02	KM	GRO	< 5	0.25	0.23	92.0	none		
	KMD	GRO	< 5	0.25	0.25	100.0	none	8.3 none	

Run Date/Time:		1/7/94		Instrument: GC_01		Analyst: SN		Units: mg/kg	
Method:		DRO							
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result	( % ) Limits	RPD Limit		
9401058-01	KM	DRO	BDL	500	227.6	46.0 none			
	KMD	DRO	BDL	500	347.3	69.0 none	41.6 none		

Run Date/Time:		1/8/94	Instrument: GC_01		Analyst: SN	Units: mg/kg
Method:		DRO				
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result ( % )	Limits RPD Limit
9401077-01	KM	DRO	7.1	500	370.8 74.0	none

Run Date/Time:		1/9/94		Instrument: GC_01		Analyst: SN		Units: mg/kg	
Method:		DRO							
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result	( % ) Limits	RPD Limit		
9401078-01	KM	DRO	BDL	500	292	53.0 none			
	KMD	DRO	BDL	500	256.6	51.0 none	12.9 none		

Run Date/Time:		1/12-13/94		Instrument: GC_01		Analyst: SN		Units: mg/kg	
Method:		DRO							
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result	( % ) Limits	RPD Limit		
9401111-04	KM	DRO	BDL	500	251.4	50.0 none			
	KMD	DRO	BDL	500	273.9	54.0 none	8.6 none		

Run Date/Time: 1/27/94			Instrument: GC_01		Analyst: SN		Units: mg/kg	
Method: DRO								
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result	( % ) Limits	RPD Limit	
9401225-01	KM	DRO	BDL	500	259.4	52.0 none		
	KMD	DRO	BDL	500	278.1	56.0 none	7 none	

# ENVIRONMENTAL LABORATORIES INC.

## QA/QC REPORT

### MATRIX SPIKES, MATRIX SPIKE DUPLICATES

Report Date:

05/06/94

Run Date/Time:		1/29/94	Instrument: GC_01		Analyst: SN	Units:	mg/kg
Method:		DRO					
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result ( % )	Limits	RPD Limit
9401245-01	KM	DRO	8.2	500	235.9	47.0 none	

Run Date/Time:		2/16/94	Instrument: GC_01		Analyst: SN	Units:	mg/kg
Method:		DRO					
Sample #		Analyte	Original Result	Spike Amount	Spike Recovery Result ( % )	Limits	RPD Limit
9402141-01	KM	DRO	BDL	500	209.4	42.0 none	
	KMD	DRO	BDL	500	187.3	37.0 none	11.1 none



# ENVIRONMENTAL LABORATORIES INC.

## QA/QC REPORT

### BLANKS

Report Date:

05/06/94

Run Date/Time: 2/18/94 16:25		Instrument: AA_CV		Analyst: BZ	Units: mg/L
Method: AAS Cold Vapor					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
TC BK 2/18	Hg	TCLP	0.00003	50	0.01

Run Date/Time: 2/17/94 16:59		Instrument: AA_G2		Analyst: MH Units: mg/L	
Method: AAS Furnace					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DG BK 2/8	Cr	Oil	0.003	500	0.4
DG BK 2/14	Cr	Water	0.0004	1	0.008
DG BK 2/14	Cr	Soil	0.0054	100	0.08
DG BK 2/14	Cr	Oil	0.0056	500	0.4
DG BK 2/15	Cr	Water	< 0.0008	1	0.0008

Run Date/Time: 2/10/94 09:27		Instrument: AA_G2		Analyst: MH Units: mg/L	
Method: AAS Furnace					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DG BK 2-4	Ag	Water	0.00004	1	0.0005
DG BK 2-8	Ag	Water	0.00002	1	0.0005

Run Date/Time: 2/15/94 08:50		Instrument: AA_G2		Analyst: MH Units: mg/L	
Method: AAS Furnace					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DG BK 2-14	Ag	Soil	0.00001	100	0.05
DG BK 2-8	Ag	Water	0.0011	1	0.0005
DG BK 2/18 OIL	Ag	Oil	0.0003	500	0.25
DG BK 2-8	Ag	Soil	0.0013	100	0.05
DG BK 2-15	Ag	Water	0.0018	1	0.0005
DG BK 2-14	Ag	Oil	0.0018	500	0.25

Run Date/Time: 2/20/94 14:29		Instrument: AA_G2		Analyst: MH Units: mg/L	
Method: AAS Furnace					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DG BK 2-9	Pb	Water	0.002	1	0.005
DG BK 2-14	Pb	Water	0.0064	1	0.005
DG BK 2-15	Pb	Water	0.0048	1	0.005
DG BK 2-14	Pb	Soil	0.0028	100	0.5
DG BK 2/14	Pb	Oil	0.0017	500	2.5

Run Date/Time: 2/18/94		Instrument: AA_G2		Analyst: MH Units: mg/L	
Method: AAS Furnace					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DG BK 2/8	Se	Soil	0.0008	100	0.5
DG BK 2/8	Se	Water	0.0009	1	0.005
DG BK 2/14	Se	Soil	0.0035	100	0.5

# ENVIRONMENTAL LABORATORIES INC.

## QA/QC REPORT

### BLANKS

Report Date:

05/06/94

Run Date/Time: 2/23/94 09:17		Instrument: AA_G2		Analyst: MH Units: mg/L	
Method: AAS Furnace					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DG BK 2/14	Ba	Soil	- 0.002	100	0.5
DG BK 2/22	Ba	Water	- 0.001	1	0.005

Run Date/Time: 2/21/94 15:57		Instrument: AA_G2		Analyst: MH Units: mg/L	
Method: AAS Furnace					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DG BK 2/14	Cd	Soil	0.00022	100	0.05
DG BK 2/14 OIL	Cd	Oil	0.00042	500	0.25

Run Date/Time: 4/28/94 16:49		Instrument: AA_G2		Analyst: MH Units: mg/L	
Method: AAS Furnace					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DG BK 4/28	As	Soil	0.0017	100	0.005

# ENVIRONMENTAL LABORATORIES INC.

## QA/QC REPORT

### BLANKS

Report Date:

05/06/94

Run Date/Time: 2/14/94 11:58		Instrument: MS_01		Analyst: EVY Units: ug/kG		
Method: 8240						
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit	
DI Blank	Chloromethane	Soil	BDL	1	10	
DI Blank	Vinyl chloride	Soil	BDL	1	10	
DI Blank	Bromomethane	Soil	BDL	1	10	
DI Blank	Chloroethane	Soil	BDL	1	10	
DI Blank	Trichlorofluoroethane	Soil	****	1	****	
DI Blank	Acrolein	Soil	****	1	****	
DI Blank	Acetone	Soil	BDL	1	100	
DI Blank	1,1-Dichloroethene	Soil	BDL	1	2.8	
DI Blank	Methylene chloride	Soil	BDL	1	2.8	
DI Blank	Carbon disulfide	Soil	BDL	1	100	
DI Blank	Acrylonitrile	Soil	****	1	****	
DI Blank	(trans) 1,2-Dichloroethene	Soil	BDL	1	1.6	
DI Blank	Vinyl acetate	Soil	BDL	1	50	
DI Blank	1,1-Dichloroethane	Soil	BDL	1	4.7	
DI Blank	2-Butanone	Soil	BDL	1	100	
DI Blank	Chloroform	Soil	BDL	1	1.6	
DI Blank	1,1,1-Trichloroethane	Soil	BDL	1	3.8	
DI Blank	Carbon tetrachloride	Soil	BDL	1	2.8	
DI Blank	1,2-Dichloroethane	Soil	BDL	1	2.8	
DI Blank	Benzene	Soil	BDL	1	4.4	
DI Blank	Trichloroethene	Soil	BDL	1	1.9	
DI Blank	1,2-Dichloropropane	Soil	BDL	1	6	
DI Blank	Bromochloromethane	Soil	BDL	1	2.2	
DI Blank	2-Chloroethylvinyl ether	Soil	BDL	1	50	
DI Blank	4-Methyl-2-pentanone	Soil	BDL	1	10	
DI Blank	(cis) 1,3-Dichloropropene	Soil	BDL	1	5	
DI Blank	Toluene	Soil	BDL	1	6	
DI Blank	(trans) 1,3-Dichloropropene	Soil	BDL	1	5	
DI Blank	1,1,2-Trichloroethane	Soil	BDL	1	5	
DI Blank	2-Hexanone	Soil	BDL	1	10	
DI Blank	Tetrachloroethene	Soil	BDL	1	4.1	
DI Blank	Dibromochloromethane	Soil	BDL	1	3.1	
DI Blank	Chlorobenzene	Soil	BDL	1	6	
DI Blank	Ethylbenzene	Soil	BDL	1	7.2	
DI Blank	m,p-Xylene	Soil	BDL	1	10	
DI Blank	o-Xylene	Soil	BDL	1	5	
DI Blank	Styrene	Soil	BDL	1	5	
DI Blank	Bromoform	Soil	BDL	1	4.7	
DI Blank	1,1,2,2-Tetrachloroethane	Soil	BDL	1	6.9	
DI Blank	1,3-Dichlorobenzene	Soil	****	1	****	
DI Blank	1,4-Dichlorobenzene	Soil	****	1	****	
DI Blank	1,2-Dichlorobenzene	Soil	****	1	****	

# ENVIRONMENTAL LABORATORIES INC.

## QA/QC REPORT

### BLANKS

Report Date:

05/06/94

Run Date/Time: 2/16/94 15:03		Instrument: MS_01		Analyst: EVY Units: ug/kG	
Method: 8240					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DI Blank	Chloromethane	Soil	BDL	1	10
DI Blank	Vinyl chloride	Soil	BDL	1	10
DI Blank	Bromomethane	Soil	BDL	1	10
DI Blank	Chloroethane	Soil	BDL	1	10
DI Blank	Trichlorofluoroethane	Soil	****	1	****
DI Blank	Acrolein	Soil	****	1	****
DI Blank	Acetone	Soil	BDL	1	100
DI Blank	1,1-Dichloroethene	Soil	BDL	1	2.8
DI Blank	Methylene chloride	Soil	BDL	1	2.8
DI Blank	Carbon disulfide	Soil	BDL	1	100
DI Blank	Acrylonitrile	Soil	****	1	****
DI Blank	(trans) 1,2-Dichloroethene	Soil	BDL	1	1.6
DI Blank	Vinyl acetate	Soil	BDL	1	50
DI Blank	1,1-Dichloroethane	Soil	BDL	1	4.7
DI Blank	2-Butanone	Soil	BDL	1	100
DI Blank	Chloroform	Soil	BDL	1	1.6
DI Blank	1,1,1-Trichloroethane	Soil	BDL	1	3.8
DI Blank	Carbon tetrachloride	Soil	BDL	1	2.8
DI Blank	1,2-Dichloroethane	Soil	BDL	1	2.8
DI Blank	Benzene	Soil	BDL	1	4.4
DI Blank	Trichloroethene	Soil	BDL	1	1.9
DI Blank	1,2-Dichloropropane	Soil	BDL	1	6
DI Blank	Bromochloromethane	Soil	BDL	1	2.2
DI Blank	2-Chloroethylvinyl ether	Soil	BDL	1	50
DI Blank	4-Methyl-2-pentanone	Soil	BDL	1	10
DI Blank	(cis) 1,3-Dichloropropene	Soil	BDL	1	5
DI Blank	Toluene	Soil	BDL	1	6
DI Blank	(trans) 1,3-Dichloropropene	Soil	BDL	1	5
DI Blank	1,1,2-Trichloroethane	Soil	BDL	1	5
DI Blank	2-Hexanone	Soil	BDL	1	10
DI Blank	Tetrachloroethene	Soil	BDL	1	4.1
DI Blank	Dibromochloromethane	Soil	BDL	1	3.1
DI Blank	Chlorobenzene	Soil	BDL	1	6
DI Blank	Ethylbenzene	Soil	BDL	1	7.2
DI Blank	m,p-Xylene	Soil	BDL	1	10
DI Blank	o-Xylene	Soil	BDL	1	5
DI Blank	Styrene	Soil	BDL	1	5
DI Blank	Bromoform	Soil	BDL	1	4.7
DI Blank	1,1,2,2-Tetrachloroethane	Soil	BDL	1	6.9
DI Blank	1,3-Dichlorobenzene	Soil	****	1	****
DI Blank	1,4-Dichlorobenzene	Soil	****	1	****
DI Blank	1,2-Dichlorobenzene	Soil	****	1	****

# ENVIRONMENTAL LABORATORIES INC.

## QA/QC REPORT

### BLANKS

Report Date:

05/06/94

Run Date/Time: 1/7/94		Instrument: GC_03		Analyst: TS	Units: mg/kG
Method: GRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DI Blank	Gasoline Range Organics	Soil	BDL	1	5

Run Date/Time: 1/8/94		Instrument: GC_03		Analyst: TS	Units: mg/kg
Method: GRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DI Blank	Gasoline Range Organics	Soil	BDL	1	5

Run Date/Time: 1/9/94		Instrument: GC_03		Analyst: MB		Units: mg/kG
Method: GRO						
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit	
DI Blank	Gasoline Range Organics	Soil	BDL	1	5	

Run Date/Time: 1/12/94		Instrument: GC_03		Analyst: TS	Units: mg/kG
Method: GRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DI Blank	Gasoline Range Organics	Soil	BDL	1	5

Run Date/Time: 1/27-29/94		Instrument: GC_03		Analyst: MB		Units: mg/kG
Method: GRO						
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit	
DI Blank	Gasoline Range Organics	Soil	BDL	1	5	
DI Blank	Gasoline Range Organics	Soil	BDL	1	5	

Run Date/Time: 2/16-17/94		Instrument: GC_03		Analyst: EVY Units: mg/kG	
Method: GRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
DI Blank	Gasoline Range Organics	Soil	BDL	1	5
DI Blank	Gasoline Range Organics	Soil	BDL	1	5

# ENVIRONMENTAL LABORATORIES INC.

## QA/QC REPORT

### BLANKS

Report Date:

05/06/94

Run Date/Time: 1/7/94		Instrument: GC_01		Analyst: SN	Units: mg/kg
Method: DRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
PREP BLANK	Diesel Range Organics	Soil	BDL	1	5

Run Date/Time: 1/8/94		Instrument: GC_01		Analyst: SN	Units: mg/kg
Method: DRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
PREP BLANK	Diesel Range Organics	Soil	BDL	1	5

Run Date/Time: 1/9/94		Instrument: GC_01		Analyst: SN	Units: mg/kg
Method: DRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
PREP BLANK	Diesel Range Organics	Soil	BDL	1	5

Run Date/Time: 1/12–13/94		Instrument: GC_01		Analyst: SN	Units: mg/kg
Method: DRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
PREP BLANK	Diesel Range Organics	Soil	BDL	1	5

Run Date/Time: 1/27/94		Instrument: GC_01		Analyst: SN Units: mg/kg	
Method: DRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
PREP BLANK	Diesel Range Organics	Soil	BDL	1	5

Run Date/Time: 1/29/94		Instrument: GC_01		Analyst: SN Units: mg/kg	
Method: DRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
PREP BLANK	Diesel Range Organics	Soil	BDL	1	5

Run Date/Time: 2/16/94		Instrument: GC_01		Analyst: SN	Units: mg/kg
Method: DRO					
Sample #	Analyte	Matrix	Result	Dilution Factor	Detection Limit
PREP BLANK	Diesel Range Organics	Soil	BDL	1	5